The LEWES HOUSE Collection of ANCIENT GEMS & &


Library of

Mellesley



Cullege.

Purchased from The Porstord Kund.
Nº 100493





# THE LEWES HOUSE COLLECTION OF ANCIENT GEMS

Oxford University Press Edinburgh Glasgow New York Toronto Melbourne Cape Town Bombay

Humphrey Milford Publisher to the University

London

# THE LEWES HOUSE COLLECTION OF ANCIENT GEMS

BY

J. D. BEAZLEY
STUDENT OF CHRIST CHURCH

OXFORD
AT THE CLARENDON PRESS

1920

12.11.

Art Lilianey

A 55 E

L5 W3

### TO ANDREW GOW

#### PREFACE

Y principal debts are on the one hand to Mr. E. P. Warren, for setting me the pleasant task of cataloguing his choice and splendid collection of ancient gems, and for placing his time, his scholarship, and his experience at my disposal; and on the other to the late Professor Furtwängler, whose great history will be found quoted on every page. Mr. Andrew Gow encouraged me, collaborated in part of the work, read the proofs, and made many useful suggestions. The late Dr. L. W. King wrote, and Dr. Stephen Langdon revised, the account of two Oriental stones with which I was not competent to deal. Mr. Arthur Smith enabled me, at the earliest possible moment, to study the collection of gems at the British Museum, and assisted me in several other ways. Sir Arthur Evans allowed me to consult him on several questions, Mr. G. F. Hill on certain numismatical points, Professor Percy Gardner on another, the late Professor Haverfield on one or two Roman matters, Mr. J. A. Howe on a geological one, and my colleague, Mr. G. T. Hutchinson, on horses and deer.

Permission to publish illustrative pieces was kindly granted by Mr. Arthur Smith, by Mr. C. F. Bell of the Ashmolean, by Dr. L. D. Caskey of the Museum at Boston, and by Miss Richter of the Metropolitan Museum in New York: by Lady Cook, by Lord Southesk, and by Sir Arthur Evans. Mr. De Ridder not only gave me leave to publish a stone in the Louvre, but sent me his own imprints of two gems in the De Clercq collection. Mr. A. P. Ready furnished me with imprints of the Lewes House gems, and of British Museum gems while the originals were inaccessible. My wife has done me many services.

To all these helpers I offer my sincere thanks.

The gems are arranged according to period, and, within the period, chronologically as far as possible. In the free Greek period it has been convenient to keep the animals together, and in the Greco-Roman the portraits. Some of the finest gems have been reproduced twice: in their real size; and with a magnification of two diameters.

Some of the terms employed in describing beetles are taken from the frontispiece of Petrie's Scarabs and Cylinders.

# CONTENTS

									PAGE
INTAGLIOS									
CRETAN AND N	IYCE	ENEAN		•	•	•	•	•	I
MESOPOTAMIAN		•		•	0		•		3
PERSIAN .	•		•	•		•	•	•	5
PHOENICIAN AN	D G	RECO-	PH	OENIC	ΊA	Ν.			6
GREEK : ARCHA	IC	•	•			•		•	10
ETRUSCAN : AR	CHA	IC	•	•		•	•	•	31
GREEK: FREE S	TYL	E	•	•		•	•	•	41
ETRUSCAN; FR	EE S	TYLE	: A	ND IT	AI	LIOTE	•	•	71
GREEK: HELLE	NIST	ГIС	•	•	•	•		•	78
GRECO-ROMAN	•	•		•	•	•	•		88
RENAISSANCE	•	•	•	•	•	•	•	•	103
CAMEOS					•	•		٠	104
SUPPLEMENT : IN	NTA	GLIO	S	•	•	•	•		112
ADDENDA .	•		•	•	•	٠	•	•	115
INDEX	•	•	•	٠		•	•	•	119
DESCRIPTION OF	PI.	ATES	A	AND	В				123



#### ABBREVIATIONS

THE groups of letter and number immediately following the catalogue number refer to the archives: B. B., Black Book; G. P., General Provisional; R., Register; T. L., Temporary List; Bu. with letter and number after it, to the exhibition of ancient Greek art at the Burlington Fine Arts Club in 1904.

Babelon, Traité: Traité des monnaies grecques et romaines.

Beschreibung: Furtwängler, Königliche Museen zu Berlin: Beschreibung der geschnittenen Steine im Antiquarium.

B. M. Catalogue: Arthur Smith, A Catalogue of the Engraved Gems in the British Museum.

B. M. Coins of (Ionia, &c.): British Museum: Catalogue of the Greek Coins of (Ionia, &c.).

B. M. Finger Rings: F. H. Marshall, Catalogue of the Finger Rings, Greek, Etruscan, and Roman, in the Department of Antiquities, British Museum.

Brunn-Bruckmann: Denkmäler griechischer und römischer Skulptur.

Burlington Catalogue: Burlington Fine Arts Club: Exhibition of Ancient Greek Art, 1904: Illustrated Catalogue.

F.: Furtwängler, Die antiken Gemmen: Geschichte der Steinschneiderkunst im klassischen Altertum: vol. i, Tafeln; vol. ii, Erläuterungen; vol. iii, Geschichte.

F. R.: Furtwängler and Reichhold, Griechische Vasenmalerei.

F. R. H.: The same, continued by Hauser.

Furtwängler, Beschreibung: see Beschreibung.

Gardner, Types: Percy Gardner, The Types of Greek Coins.

Jahrbuch: Jahrbuch des Kaiserlich Deutschen Archäologischen Instituts.

Jahreshefte: Jahreshefte des Oesterreichischen Archäologischen Institutes.

J. H. S.: Journal of Hellenic Studies.

- Southesk Catalogue: Catalogue of the Collection of Antique Gems formed by James, Ninth Earl of Southesk, K.T., edited by his daughter, Lady Helena Carnegie.
- Vases in America: Beazley, Attic Red-figured Vases in American Museums.
- Vives: Antonio Vives y Escudero, Estudio de Arqueología cartaginesa: la Necrópoli de Ibiza.
- Wyndham Cook Catalogue: Cecil H. Smith and C. Amy Hutton: Catalogue of the Antiquities (Greek, Etruscan, and Roman) in the Collection of the late Wyndham Francis Cook, Esqre: the gems by Miss Hutton.

# INTAGLIOS

#### CRETAN AND MYCENEAN

I

B. B. 37, 7. R. 1304. Bu. O 35. Pl. 1. Bought in Athens, 1898, and said to have come from Mycenae.

Lenticular. Translucent sard.

Ground line. Two lions biting a stag in the throat. All three animals are standing on their hind legs. The heads of the lions frontal and their forelegs stretched straight down. The stag's head is pressed right back, and its tongue lolls out of its mouth: its forelegs are very long.

A bull with its head pressed back like our stag's occurs on a lenticular red jasper from Rethymnos in the Evans collection:

the period is Late Minoan I-II.

2

G. P. 144, 114. R. 1966. Bu. O 47. Pl. 1. Bought in 1900 from Professor R. D. Norton.

Lenticular. Sard.

A lion attacking a bull. The lion's head is concealed by the bull's; such a design, as where two bodies are conjoined in one head (F., pl. 3, 23), a motive which, according to Evans, is found in Late Minoan I and is characteristic of Late Minoan II and III.

3

G. P. 301, 2. Pl. 1. Sent from Athens, 1904.

Lenticular. Murky sard.

A lioness standing on a bull and tearing at its foreleg. The lioness is maned (see number 58): her head is frontal and the face very narrow.

В

Somewhat similar stones in Athens, 3137 (F. iii, p. 51, fig. 31) and 2573. For the antipodal position, compare the lenticular onyx from the Vaphio tomb (F., pl. 3, 32).

4

G. P. 341, 2. Bu. L 14. Pl. 1. From Mycenae. Bought in Paris. Formerly in the Evans collection. Evans, J. H. S. xxi, p. 156 (enlarged drawing); Von Fritze, Jahrbuch, xviii, p. 60, fig. 5, after Evans.

Rock-crystal ring with engraving on the convex elliptical bezel. Two ground lines. On either side of a tree, a bull couched

with head turned back: behind each, another tree.

An example of a not uncommon motive, two animals grouped symmetrically about a tree or pillar: so on two gold rings from Mycenae in Athens (F. iii, p. 42, and F., pl. 3, 25) and another from Enkomi in the British Museum (B. M. Finger Rings, pl. 1, number 7): see Evans, loc. cit., and Jolles, Jahrbuch, xix, p. 34. A Greek example of the motive on a stone in the Arndt collection, published by Bulle in Zeitschrift des Münchner Altertumsvereins, 1903–4 (Antike geschnittene Steine, plate, number 12).

5

G. P. 341, 7. Pl. 1. From Crete. Bought in Paris, 1911. Formerly in the Evans collection. Previously in the possession of the schoolmaster at Chersonesos in Crete.

Thin equiconvex cylinder, flattened at the ends; as Furtwängler, *Beschreibung*, p. 6, number 51: a shape first found, according to Evans, in Middle Minoan III (c. 1850–1600 B.C.). Streaked chalcedony.

A cow suckling and licking her calf.

A common subject on Mycenean gems: examples in Athens (F., pl. 3, 10, from Mycenae), in Berlin (Furtwängler, Beschreibung, pl. 1, number 24), in Munich (Münchener Jahrbuch, iv, pl. 2, 2), in Boston (Duffield Osborne, Engraved Gems, pl. 2, 20, and pl. 2, 18), in New York, in the British Museum (J. H. S. xvii, pl. 13, 9), and from Crete (Collection d'un archéologue explorateur, pl. 2, 13).

#### **MESOPOTAMIAN**

The description of numbers 6 and 7 has been written by Dr. L. W. King and revised by Dr. Stephen Langdon.

6

G. P. 323, 4. Pl. 1. Formerly in the possession of the Rev. James Beck, according to Mr. A. P. Ready.

Chalcedony. Amulet in the form of an oblong plaque, the upper end pierced horizontally and grooved below the bore. It was evidently worn on a string, and its upper end, above the groove, may have been mounted in gold.

Twin bearded Assyrian gods, wearing horned and spiked head-dresses. They are represented in precisely the same attitude, bearing a mace in the left hand as a symbol of power, and raising a double-headed axe in the right in an attitude of defence. The twin-gods here represented are invoked in the incantation on the reverse, where they are referred to under the title Mashmash-Mashtabba, 'Mashmash, the twin god'.

Hy Hy, Mashmash, is an ideogram or title of Lugalgirra, a form of Nergal, god of plagues and the lower world. The twin gods are Lugalgirra and Meslamtaéa, pest gods and minor forms of the great pest god Nergal. The incantation on the amulet refers to Lugalgirra or Mashmash only. He both sends pestilence and protects against it.

The eight-line inscription on the reverse contains a Sumerian

incantation:

'(1) O Lugalgirra, twin-god, (2) defender (?), (3-4) who turnest back the breast of the wicked, (5) by (i.e. in the name of) Marduk, (6-8) king of heaven and earth, may he be accursed. May the evil god not come nigh me. Incantation.' The sign [1-4], 'incantation', is placed at the end or beginning of magical incantations intended to be recited. As the amulet is intended for general use against malign influences, 'the evil god' is intentionally not defined. On the other hand the incantation defines the twin deities engraved upon the obverse, thus ensuring and reinforcing their assistance.

Assyrian. Second half of the seventh century.

G. P. 323, 3. Pl. 1. Formerly in the possession of the Rev. James Beck, according to Mr. A. P. Ready. W. Hayes Ward, Seal Cylinders of Western Asia, p. 207, no. 616. Ward states that the seal which he publishes is in the British Museum: but his is obviously identical with ours, and the probability is that the London seal is a copy.

Chalcedony. Neo-Babylonian cylinder-seal, pierced longitudinally.

Bearded and winged deity, wearing the horned head-dress, in conflict with two bulls which he grasps by the foreleg. This design is of very common occurrence on the seals of the later periods. On early Babylonian seals the central figure represents the Babylonian national hero Gilgamesh: but the motive was gradually conventionalized, and the Babylonian hero gives place to a winged god, and later still to the reigning Achaemenian king. On Babylonian seals the winged god is usually intended for Marduk; on Assyrian seals for Ashur. The design of the present seal is purely Assyrian, and represents the god Ashur; but the inscription is neo-Babylonian.

'(1) As for the owner of this seal (2) may his days (3) be long! With the fullness of life (4) may he be satisfied!'

Neo-Babylonian. Sixth century.

#### PERSIAN

8

G. P. 342, 1. Pl. 1. From the Boulton collection (sale catalogue number 1).

Cylinder. Sapphirine chalcedony.

Ground line. The Persian king, accompanied by a charioteer, in a two-horse chariot, shooting an arrow at a leonine griffin, which is already pierced with two arrows. Above, the disk of

the sun with eagle's wings and tail.

The monster has a lion's head, body, and forelegs, with the feet of an eagle, large recurved wings, long ringed horns like those of a wild goat, and a splayed tail. The rings on the horns are indicated by three pairs of short transverse lines. The lower part of the tail consists of three curving lines, each tipped with a pellet, bound together, as it were, by two transverse strokes. The mane is in the form of an even, striated brush. Ears erect, jaws open with the front teeth showing, wrinkled nose rendered by pellets. A row of pellets, ruff-like, borders the face below the ear. Three curved lines parallel to the outline of the buttock. The king wears a chiton with the upper part drawn over the girdle at the sides, the lower falling in one vertical and a number of transverse folds: the wear is clearer in F., pl. 1, 13. He has a crown on his head: his beard is long and rectangular, his hair rolled up into a big bunch behind. The charioteer wears a closefitting garment with an embroidered border down the side: he seems to be beardless; his hair is rolled up behind like the king's. The wheel of the chariot has eight spokes, each broadening to a pellet half-way along: the felloe rendered by a pair of circles bordered outside by a row of pellets representing the studded tire. The car is low and broad. The stallions are of Persian style and breed, with Roman nose and receding forehead: three lines, nearly vertical, on the neck; brush mane, striated; topknot.

The monster's tail is of regular Persian type: so in reliefs (Perrot and Chipiez, *Histoire de l'Art*, v, p. 545; Babelon, *Guide du Cabinet des Médailles*, p. 272, fig. 121) and in other gems (F., pl. 12, 4, and pl. 11, 19).

The wheel is also Persian (Perrot and Chipiez, v, p. 801;

Dalton, The Treasure of the Oxus, pp. 58-61): the same in the chariot of Darius on the Pompeian mosaic (Winter, Das Alexandermosaik aus Pompeji, pl. 1). The studded tire is found in Assyria as well (Nuoffer, Der Rennwagen im Altertum, pl. 7).

A similar scene, the king hunting the lion, in a less conventional style, on the chalcedony cylinder, known as the seal of

Darius, in the British Museum (F., pl. 1, 11).

Probably early fifth century.

#### PHOENICIAN AND GRECO-PHOENICIAN

9

R. 447. Pl. 2. From the Bruschi collection at Corneto. Annali, 1885, pl. G-H, 22; F., pl. 61, 12.

Scarab in golden band-setting, with globulated wires along the sides of the beetle. Sard.

The beetle summary. Slightly ridged. No winglets. Along the lower edge of the thorax, two lines. A line between the elytra.

Line border. A king, bearded and hook-nosed, holding a lion by the mane and brandishing a mace: he wears a helmet and a long gown. In front of him, a naked man, bald and snub-nosed, crawls away up a hill. Above, a flying bird of prey: behind, a cartouche with irregular markings. The hill is cross-hatched. Apparently a contamination of two motives, the slaughter of a lion and the slaughter of an enemy: see Furtwängler, iii, p. 109.

Similar cartouches on other Phoenician scarabs (F., pl. 7, 56, and pl. 15, 8; Babelon, Collection Pauvert de la Chapelle, pl. 4, 25). That the object is a cartouche and not, as Furtwängler calls it, a shield, is shown by the sard scarab formerly in the Morrison collection (Morrison Catalogue, pl. 1, 34) where it is inscribed with mock hieroglyphics.

Perhaps early sixth century.

10

R. 445. Pl. 2. From the Bruschi collection at Corneto. F., pl. 64, 4.

Scarab. Translucent sard.

The beetle rough. Carinated: falling away at the rump. No winglets or vertical border. The elytra not separated.

Hatched border. Bes, clad in a lionskin, running with a wild

goat in either hand.

The same subject on a scarab of similar style (imprint in Cades among the 'Persian subjects'), and on a green jasper scarab in the British Museum (number 228).

Mid sixth century.

ΙI

Pl. 2. From Iviza (Vives, La necrópoli de Ibiza, p. 71, number 354). Formerly in the Kennedy collection (sale catalogue, March 1918, number 213, 1). Vives, pl. 25, 10. Perez-Cabrero, Ibiza arqueológica, p. 28, number 8.

Scarab. Green jasper.

The beetle careful. No winglets or vertical border: the plinth large. The stone is scooped away on either side of the rump, as in numbers 12 and 13, and in two scarabs now in the collection of Miss Lamb (Vives, pl. 25, 22 and pl. 23, 12).

A hatched border along the lower edge of the thorax. Between the elytra a line: two short lines start from this line near the top

and form a triangle with the border of the thorax.

Hatched border. A winged and bearded monster, composed of lion's body and legs and human body and arms: the hands raised in adoration. The wings very slightly recurved, as in the Phoenician scarab in London, F., pl. 64, 3: an ancient Phoenician rendering (see Poulsen, *Der Orient und die frühgriechische Kunst*, p. 15 and *passim*). The long hair is filleted and gathered up behind: the lower edge pelleted, the rest hatched.

The same position of the hands on another scarab from Iviza, now in Miss Lamb's collection (Vives, pl. 24, 21): the posture of the worshipper (Vives, pl. 24, 2) is transferred to the deity.

Early fifth century.

12

Pl. 2. From Iviza (Vives, La necrópoli de Ibiza, p. 75, number 10). Formerly in the Kennedy collection (sale catalogue number 212, 1). Vives, pl. 25, 21. Perez-Cabrero, Ibiza arqueológica, p. 28, number 5.

Scarab. Green jasper.

The beetle as in numbers 11 and 13, except that the border

below the thorax consists of two lines.

Hatched border. Head of a youth wearing a crested helmet which is compounded of a silen's head, in front, and a lion's head behind. The hair falls in a thick mat behind, with rows, separated by grooves, of short striations. The silen has horse's ears and his beard is hatched: his head is of the usual Greco-Phoenician type.

A late Etruscan stone (F., pl. 18, 45) is engraved with a youthful head wearing a cap compounded of a silen's head and a lion's. Helmets and caps of similar make are found, no doubt under Carthaginian influence, on late Italiote and on Greco-Roman stones (F., pl. 29, 75 and 77; Furtwängler, Beschreibung, pl. 57, 7809 and 7810). A helmet with the upper part in the form of a silen's face is worn by a warrior on a late Etruscan bronze cista in the British Museum (746: Murray, Handbook of Archaeology, p. 136; this detail indistinct in the reproduction). The helmet on an archaic Greek scarab in the British Museum (F., pl. 6, 56) is stated by Furtwängler to have a mask of silenesque type attached behind; but the mask belongs to the aegis and not to the helmet.

Our head is terminated below the neck by a row of pellets. This is a very common termination for heads and foreparts on archaic Greek coins, but it is less common on gems: examples on archaic Greek scarabs in Copenhagen (F., pl. 8, 71) and in Paris (F., pl. 6, 66), and on a Greco-Phoenician scarab from Iviza with a bearded head in three-quarter profile (Vives, pl. 26, 15). In the free period, the row of pellets is ousted by the curvilinear cut.

The hair is treated in the same manner on a green jasper scarab from Tharros in the British Museum with a youthful head wearing a helmet (B. M. Catalogue, pl. C, 167; F., pl. 7, 45).

The style is almost as Greek as that of number 13.

Beginning of the fifth century.

#### 13

Pl. 2, and, enlarged, Pl. 9. From Iviza (Vives, La necrópoli de Ibiza, p.71, number 358). Formerly in the Kennedy collection (sale catalogue number 212, 2). Vives, pl. 23, 6; Perez-Cabrero, Ibiza arqueológica, p. 28, number 1.

Scarab. Green jasper.

The beetle as in number 11.

Hatched border. A naked youth running with a cock on his left arm and a bow and arrows in his right hand. The hair hatched, save over the forehead and where it is gathered up behind; fillet, with two loose ends in front, each terminating in a tiny pellet, and the like at the back. The inner marking of the body precise and hard: the arch of the ribs begins low down, and contains five bosses representing the prominences of the rectus abdominis.

For the style, compare the green jasper scarab, from Tharros, in the museum at Cagliari, F., pl. 15, 47, and another from Iviza (Pl. A, 13: Vives, pl. 23, 7): in both the arch of the ribs is low

as in ours.

The style is pure Greek of the Greco-Phoenician class. Beginning of the fifth century.

#### 13 bis.

Pl. 2. From Iviza (Vives, La necrópoli de Ibiza, p. 71, number 358). Formerly in the Kennedy collection (sale catalogue number 213, 1). Vives, pl. 23, 17; Perez-Cabrero, Ibiza arqueológica, p. 28, number 3.

Scarab. Green jasper.

The beetle as in numbers 11 and 13, but the rump only

slightly flattened.

Hatched border. Herakles holding his club in one hand and a bow with two arrows in the other. Naked, beardless: the hair short and pelleted.

More careful than the Herakles on the green jasper scarab from Tharros in the British Museum (B. M. Catalogue, pl. C, 162), but greatly inferior to numbers 12 and 13 in the present collection.

Beginning of the fifth century.

#### GREEK: ARCHAIC

14

R. 439. Pl. 2. Found at Corneto. F., pl. 6, 46. Scarab. Banded agate, black, white, and grey.

The beetle very delicately wrought. Carinated. Vertical hatched border. Recurving winglets. Hatched border right round the thorax. The clypeus goffered. Hatched border round the edge of the plates, and also on the legs. Between the elytra, three lines: from each of the outer ones a small spiral springs near the top.

Pellet border, continued by a simple line below the ground band. Ground band diagonally hatched and counter-hatched. The Struggle for the Tripod. Herakles, wearing the lionskin, holds the tripod in his left hand and his club in his right, and looks back on Apollo who is pursuing him and grasping the tripod. Apollo has plain long hair and a kind of chlamys. The knees of both figures are strongly marked: the toes, except on Apollo's right foot, are rendered by pellets. The genitals are not indicated. The legs of the tripod straddle.

The snake may be Python, introduced to locate the action. Furtwängler, however, compares the two snakes on the Etruscan

chariot from Monteleone in New York.

Pure Greek scarabs with a vertical border are rare: later examples in the Story Maskelyne collection (F., pl. 6, 52; Burlington Catalogue, pl. 108, O 49), and in the British Museum (F., pl. 9, 34). It is possible that our stone, like number 35 ter, should be called Etruscan rather than Greek.

Mid sixth century.

15

G. P. 257, 1. Bu. O 64. Pl. 2. Bought in Paris, 1902. Gemmes et médailles antiques, vente à l'hôtel Drouot 24–26 mars 1902, pl. 1, fig. 18 (number 26).

Scarab. Jasper, black and red.

The beetle moderately careful. Carinated. No vertical border: no winglets. Hatched border right round the thorax. The elytra are not separated, but there is a small palmette on the elytra half-way along the thoracic border.

Hatched border. A silen and a nymph dancing: in the field, a wreath. The silen has horse's hooves: his head is frontal: he

holds lyre and plectron. The knees and the muscles of the lower leg are faintly indicated. A vertical depression near the middle of the forehead (see number 16). The beard hatched. The nymph wears a chiton and a wrap: long hair, plain on the skull, in straight strands behind. It is suggested in the sale catalogue that she holds castanets, but more probably her hands are empty, with the thumb separate from the rest of the fingers and these combined, in early archaic fashion, into a single curved line: compare the hands of Deianeira on the London scarab, F., pl. 6, 39.

Mid sixth century.

#### 16

G. P. 342, 3. Pl. 2. Formerly in the Boulton collection (sale catalogue number 4, 1).

Scarab. Translucent sard.

The beetle rough. Slightly ridged. No vertical border: no winglets. Two lines along the lower edge of the thorax. Between the elytra, a line which ends above in a triangle inscribed with a line parallel to one of the sides.

Hatched border. Silen running with oinochoe and kantharos. Horse's hooves, no tail, head frontal, beard hatched. A vertical groove in the middle of the forehead. Little inner marking: between chest and hip merely three streak-like prominences, one

above the other.

The same subject, but the head in profile, on a contemporary scarab in the British Museum (F., pl. 8, 20; a replica, F., pl. 63, 5), and on a scarab in Corneto (Annali, 1885, pl. G-H, 33: similar, but apparently without the oinochoe, F., pl. 7, 60). The silen's tail is omitted, to prevent overcrowding of the design, on the London scarab and the replica; on a Berlin scarab which is allied to them (F., pl. 8, 2); on the Corneto scarab and its fellow; and on a rock-crystal scaraboid from Cyprus in Berlin (F., pl. 8, 1). The vertical groove on the forehead, separating the temples, reappears in our number 15, in the scarabs F., pl. 8, 33 and pl. 8, 4, and also in F., pl. 8, 61 and pl. 15, 70, and in the relief silen on the back of the pseudo-scarab signed by Syries in the British Museum. The same rendering of the kantharos in the Berlin scaraboid (F., pl. 8, 1); less summary in F., pl. 8, 20: the kind of vessel meant is shown by the scarab F., pl. 8, 19, formerly in the Beugnot, now in the Ionides collection.

In style our stone most resembles the Berlin scaraboid (F., pl. 8, 1) and the scarab F., pl. 8, 33.

Mid sixth century.

#### 17

G. P. 188, 479. Pl. 2. Bought in Athens, 1901. Formerly in the Postolakka collection. Imhoof-Blumer and Keller, *Tier- und Pflanzenbilder*, pl. 26,44; F.,pl. 63,1, and, drawn, iii,p. 102; Perrot, *Histoire de l'Art*, ix, p. 26, fig. 28, after Furtwängler's drawing.

Scarab. Sardonyx, discoloured, now dark brown with creamy

yellow patches.

The beetle summary. Carinated. No vertical border. The winglets rendered by two strokes. Along the lower edge of the thorax, a hatched border with a V-shaped dip in the middle.

The elytra not separated.

Cable border. A silen bestriding a sphinx and seizing her by the hair. The silen has horse's hooves; head frontal; hair and beard hatched, tail striated: between chest and hip, four semi-elliptical prominences, one above the other. The sphinx is wingless, and very long in the body, both no doubt for the

sake of the design: hair hatched.

If the stone were later, the representation might be interpreted as a parody of Oedipus consulting the Sphinx, like the pictures on South Italian vases (Crusius, Festschrift für Overbeck, p. 103, 3; Hartwig, Philologus, lvi, pl. 1) and, as early as the second third of the fifth century, on an Attic oinochoe in Berlin (Archäologischer Anzeiger, 1891, p. 119; Philologus, lvi, p. 4); but in the sixth century it is perhaps preferable to assume, with Furtwängler, a parallel story: it is not impossible, however, that the representation was not founded on any myth, the design being a mere contamination of two favourite figures.

A composition which bears a fundamental resemblance to ours is the group of a naked youth attacking a naked woman on a sard, presumably a cut scarab, from Cyprus in New York (Cesnola, Atlas of the Cesnola Collection, iii, pl. 28, 13; Pl. A, 1 from a new imprint). The New York stone, though less careful than ours, is so close in style that it might not unreasonably be ascribed to the same artist: common to both the modelling of breast and body, the shape of the thigh, the female head and

hair, the neglected feet.

That the form assumed by our Sphinx's hair is not due to the silen's action is shown by the hair of the woman on the New York sard, and in the youthful head, which seems almost like an excerpt from that stone, on a sard scarab of the same style in the Cabinet des Médailles (Collection Pauvert de la Chapelle, pl. 6, 75; F., iii, p. 445, fig. 224).

Mid sixth century.

18

G. P. 317, 4. Pl. 2. Bought in Athens, 1917. Scarab. Sard, streaked with white.

The beetle summary. Slightly carinated towards the rump. No vertical border: no winglets. Along the lower edge of the

thorax, two lines. A line between the elytra.

Hatched border. A bearded man running with a lyre in his left hand and a cock in his right. Long plain hair. The arch of the ribs prominent: within it four bosses one above the other. The modelling drier than in the preceding stones. Somewhat similar in style, a chalcedony scarab in the Louvre (F., pl. 6, 37).

Mid sixth century.

19

Pl. 2. Bought in Brighton. Scaraboid. Chalcedony.

Line border. A Gorgon, or possibly an Erinys, running with a snake in her hand. She has wings, not recurved, and wears a short chiton with kolpos: her hair is gathered up at the back of the neck and has a few rough striations on it.

A replica on a rock-crystal scaraboid from Corinth in the British Museum (Pl. A, 8; F., pl. 6, 61). Furtwängler is wrong in describing the London figure as bearded and as wearing a corslet.

Rude work. Second half of the sixth century.

20

G.P. 340, 3. Bu. L 54. Pl. 2. Formerly in the Evans collection. Bought in Paris from Rollin and Feuardent, 1911.

Scaraboid. Chalcedony.

Line border. A young male figure, with recurved wings on shoulders, head and heels, running with a lyre and a head fillet in his hands. The hair hatched: thick at the back of the neck.

The chest frontal, all below in profile: four bosses, two and two,

for the prominences of the rectus abdominis.

The head-wing, which is attached immediately to the head and not to a cap, might speak for Hermes, whose head is winged on an Attic bell-krater, of about 400 B.C., in the Villa Giulia (F. R., pl. 20), and occasionally later; the lyre also would not be inappropriate: but the object in the left hand is probably a fillet rather than a plectron with its cord, and lyre and head fillet point to Eros: on the early representation of this god, see number 33.

Second half of the sixth century.

21

R. 444. Bu. O 15. Pl. 2, and, enlarged, Pl. 9. From the Bruschi collection at Corneto. F., pl. 6, 47.

Scarab. Translucent sard.

The beetle very delicately wrought. No vertical border. Winglets, recurved. Round the sides and the lower edge of the thorax, a hatched border. The head, clypeus, and plates cross-hatched. On the thorax, two spirals springing from the lower part of the hatched border. Between the elytra, two lines terminating above in a triangle inscribed with a horizontal line. The

outer line of each elytrum ends in a spiral near the rump.

Pellet border. Herakles leading one of Diomedes' horses: his bow-case hangs from the border. He holds the horse's bridle with his right hand and his club in his left: lionskin: elbow, knees, and calves carefully rendered: four bosses, ranged two and two, on the body below the chest. The horse's mouth is wide open, with the upper row of teeth indicated, and the skin about the mouth is creased accordingly. The mane striated: the forepart of it distinguished from the rest, as if blown back by the wind. The tail striated, with loose ends rendered by diagonal lines against the background. The headpiece of the bridlerendered by small pellets.

The same subject, differently treated, on a sard scarab, of somewhat later style, in the British Museum (F., pl. 8, 59). Similar compositions to ours on a chalcedony scaraboid in the British Museum (F., pl. 9, 15), on a sard scarab, closely resembling the last, in the museum of Corneto, and on an archaic coin of Erythrai (Gardner, Types of Greek Coins, pl. 4, 32): less like, on coins of Ichnai (Babelon, Traité, pl. 49, 12 and 14). The matter of

horse-tamers has been discussed by A. B. Cook in J. H. S. xxxvii, pp. 123-5, with reference to an archaic Attic relief in Cambridge: see also Zahn in Jahrbuch, xxiii, p. 179. A further parallel to

our horse's gait on the scarab F., pl. 8, 64.

The hair on the horse's forehead is treated in much the same way on the archaic ivory plaques, of Ionian style, collected by Pollak (Römische Mitteilungen, xxi, pl. 15, 2 and pl. 16, 2): the ivory horses, however, have a topknot as well.

On the horse's head and dotted headpiece, see number 28.

Second half of the sixth century.

#### 22

Pl. 2. From Cyprus. Formerly in the Higgins collection (sale catalogue, 1904, number 56). Cesnola, Salamina, p. 158, fig. 162; F., pl. 10, 2.

Sard, slightly convex, set in a gold ring.

The stone is perforated, and in the two perforations are bolts ending in nail-heads which secure the stone in a setting decorated with two bands of cable pattern in wire. At either end of the setting a ring is applied into which the ends of the hoop are inserted. The present hoop is modern; and Mr. Higgins said that he had had the setting lowered because it covered too much

of the gem.

Hatched border, flattened at one end and discontinued at the other. Herakles and the Lion. Furtwängler makes the stone horizontal, and if it is so placed the version of the subject is that which is preferred by artists of the later archaic period (see Reisch in Athenische Mitteilungen, xii, pp. 118-30, and Robert, Die antiken Sarkophagenreliefs, iii, pp. 120-2). Cesnola, supposing that the flattening of the border is intended to provide a ground line, places the stone upright: if he is right, two motives are contaminated, the horizontal already mentioned, and the upright motive (Walters, History of Ancient Pottery, i, pl. 32). Furtwängler's arrangement is adopted in our plate, but the other is possible.

Herakles has his arms clasped round the lion's neck, throttling it: his beard pelleted; his hair cross-hatched, with two rows of pellets for the lower edge. The lion has one forepaw at Herakles' knee, and one hindpaw close to Herakles' forehead: his mouth is wide open, with the teeth showing: the pucker of his nose rendered by pellets: short bristling hairs all along his back as far as it is visible: two rows of short hairs arranged herring-bone fashion along his belly, one row against the body, the other

against the background.

The figure of Herakles recalls the archaic relief from Lamptrai in Attica published by Reisch, the earliest example of the horizontal motive in marble (Athenische Mitteilungen, xii, pl. 3, 1), and a red-figured cup in the manner of Oltos (Pottier, Album des vases du Louvre, pl. 73, F. 128): both these about contemporary with our gem. The lion resembles the lion on the later scaraboid from Cyprus, number 34 in the present collection, to which the reader is referred.

Last quarter of the sixth century.

23

R. 441. Pll. 2 and 8. From the Bruschi collection at Corneto. Pseudo-scarab. Black steatite, hand-engraved.

The convex part in the form of a youthful face which has the appearance of wearing a kind of cap or helmet: the rump and the hind legs of the beetle are also represented. Half-way along each side, a circle with the centre deeply incised. The fringe of hair hatched. No vertical border.

Hatched border. A man driving a biga. The wheel has four spokes. The mane is rendered by an outer arc with short trans-

verse lines. Very rough work.

For the style, compare the steatite face-scarab in the British Museum (F., pl. 8, 14): for the mane, besides the last, a sard scarab from Greece in Berlin (F., pl. 8, 62), and another, with a biga, of finer work than ours, in the British Museum (F., pl. 8, 55).

Egyptian scarabs with a face substituted for the beetle occur as early as the end of the Middle Kingdom (Hall, Catalogue of Egyptian Scarabs in the British Museum, i, p. xiv). Porcelain face-scarabs, mostly Greek or Phoenician imitations of Egyptian, have been found at Naucratis (Petrie, Naucratis, i, pl. 37, 4, compare pl. 38, 8-11; Ernest Gardner, Naucratis, ii, pl. 18, 55 and 59-61), at Olbia (Revue archéologique, xviii (1911), p. 21, fig. 2), at Delphi (Homolle, Fouilles de Delphes, v, p. 25, fig. 100), and at Carthage (see Musée Alaoui, supplement, p. 353, number 197). Greek face-scarabs, in sard, F., pl. 8, 30: in steatite, F., pl. 8, 11, where the face is a silen's, and F., pl. 8, 14, where

there are two faces. The type was known to the Etruscans also: in the Corneto sard, F., pl. 17, 49, the beetle is replaced by the face of a youth with a fillet in his hair. From a similar stone, a brown jasper fragment, found at Falerii, in the Cabinet des Médailles (Babelon, Collection Pauvert de la Chapelle, pl. 10, 161): the face is in the same style as the Corneto face. In the British Museum sard, F., pl. 8, 31, which is probably Etruscan rather than Greek, a silen's head is substituted for the beetle.

Second half of the sixth century.

24

T. L. 33, 2. Bu. O 70. Pl. 2. Scarab. Light greenish steatite.

The beetle rough. Strongly ridged. No winglets or vertical border. Along the lower edge of the thorax, a line merely. The elytra not separated.

Hatched border. A silen tuning his lyre. His action is rendered with some precision: he rests the lyre on his left thigh, steadying it with his left hand, and turns the peg with his right: his head is thrown back. He has horse's ears, human feet, and a tail which encroaches on the border and is covered with thin lines arranged, roughly, herring-bone fashion. His beard is long and bushy: lines run down it lengthwise, and shorter lines, set at an angle to the others, indicate the thinner edge of the beard. His hair falls in long locks over his shoulder, and is plain except in front, where it starts back from the forehead in a striated mass. He is ithyphallic. The toes are not indicated. Inscription, very hastily written, 0 NE 21MO 5, overupos ('Oνήσιμος).

The inscription is hard to make out, for the letters are hastily formed and the surface of the soft stone is scratched and worn. The omicrons are of irregular shape, the second one loop-like. The nu is slanting, and the second and third strokes do not touch. The epsilon is indistinct owing to an abrasion, but two cross-strokes and part of the back are visible. The sigmas are pretty clear. The iota is short and perhaps slightly curved. The first two strokes of the mu are thin and shallow, the third missing,

the fourth short, thick, and deep.

2231

For the subject, compare the scarab in Boston, of Etruscan free style, with a naked youth seated on a rock and tuning his lyre.

On a scarab of light green steatite, the same material as ours, in the Louvre (Pl. A, 5; F., pl. 6, 35), Furtwängler read one... [5, which he interpreted as 'Onfoldos, a name attested from Cyprus. The inscription, like that on our stone, and for the same reasons, is difficult to decipher. The writer reads onesimos on the imprint. The nu and the epsilon, which are both slanting, are quite clear, and the slightly curving iota. The mu is also certain: the first two strokes are long, thin, and shallow, the other two short, deep, and thick. The omicrons seem to be shaped as loops open below; the upper portion of both has almost disappeared. The form of the first sigma is doubtful, as a crack runs through the upper part: the top of the second is rubbed away.

The subject of the Louvre scarab is a young warrior testing an arrow. The style certainly resembles that of our stone, especially in the furrowed thighs, the big loose knees, the heavy upper arm, and the feet. Moreover, the letters of the inscription are produced in the same manner. Everything tends to show that the two stones are by the same hand, and that Onesimos is the name of the author and not the owner; which might be inferred, if other arguments were wanting, from the illegibility

of the inscriptions.

It may be objected, that an artist's signature is not probable on a gem of second-rate quality. This argument is always a bad one, and that it has no validity in Greek art could be shown by many instances: sufficient to cite the amphora signed by the vase-painter Polygnotos (Monumenti dei Lincei, ix, pl. 1); and, in gems, the pseudo-scarab with the signature sypies eroiese in the British Museum (F., pl. 8, 11; the inscription, Jahrbuch, iii, pp. 195-7). That stone is particularly relevant to the present case, for it is of the same, not extremely common, material, and the style, not to speak of the lettering, is clearly akin. The inscription is beyond doubt the artist's signature, since the proper name Syries is followed by  $\epsilon \pi o i \eta \sigma \epsilon$ . Syries is conjectured by Röhl and by Furtwängler to have been a Euboean, because although his name is Ionic in form, he writes it with \$ and E. On the ground of his stylistic affinity with Syries, we should be inclined to place our artist in the same quarter of Greece. Moreover, like Syries he uses E where an Ionian of Asia Minor would have used H, and two of his sigmas are three-stroked, while the other two are doubtful. The form of his name says no more than that he was not a Dorian. There is nothing to prove that

he was not an Athenian: indeed, his silen is more closely akin to Attic silens than most on gems; and his archer has many fellows on Attic vases. If one inclines to Euboea rather than to Attica, it is because of his affinity with Syries. A third stone may be attributed to Onesimos, from its resemblance, already noticed by Furtwängler, to his scarab in the Louvre: namely, the greenish steatite scarab in Berlin, with a warrior drawing his bow (F., pl. 8, 12).

Last quarter of the sixth century. Furtwängler places Syries in the middle of the sixth century (Jahrbuch, iii, p. 197), but that

is undoubtedly too early.

25

B. B. 39, 5. Bu. O 79. Pl. 2. Bought in Athens, 1898. F., pl. 64, 8.

Ring of pale gold, with engraved bezel. The hoop quadrangular and very thin.

A light-armed warrior: a bearded man, wearing boots and pointed cap with a flap in front of the ear, holding spear and wicker pelta. The right leg is frontal, with the foot seen at full length; the left leg is in profile and passes behind the right: the figure is to be thought of as moving towards you. The long hair is plaited horizontally at the back of the neck.

End of the sixth century.

26

G.P. 340, 1. Pl. 2. From the Evans collection: bought in 1911.

Scarab (or less probably scaraboid), cut. Chalcedony, rosy brown.

Hatched border. Ground line. Athena walking, with spear and shield. Crested helmet, chiton, himation passing over both arms; long aegis with the gorgoneion in profile; the serpent fringe of the aegis visible on either side of the himation: plain necklace. A row of pellets for the hair on the forehead: the hair which escapes from the neck-piece of the helmet is cross-hatched. The gorgoneion also has a row of pellets on the forehead: the mouth is wide open and the upper lip protrudes beyond the nose: the head has almost lost human semblance.

A similar Athena on three archaic Etruscan scarabs (F., pl. 16, numbers 11, 10, and 9): himation and aegis similar on another (ibid., 13). Compare also the archaic Greek scaraboid of rock-crystal, British Museum 469 (Pl. A, 6). The profile gorgoneion is paralleled on a hydria of Etrusco-Ionian style (Jahreshefte, xiii, pll. 5-6) and on an archaic scarab from Cyprus in the British Museum (F., pl. 6, 56: see on number 12).

End of the sixth century.

#### 27

R. 814. Bu. O 18. Pl. 2, and, enlarged, Pl. 9. Said to have come from Aegina. Formerly in the Prokesch-Osten and Tyszkiewicz collections. *Collection Tyszkiewicz*, pl. 24, 11; F., pl. 8, 38, and, enlarged, pl. 51, 11; Bulle, *Neue Jahrbücher*, 1900, pl. 1, 14.

Scaraboid, cut. Chalcedony.

Hatched border. An archer: a naked youth, kneeling, threequarter back view, drawing his bow. The hair cross-hatched: the edge in front pelleted: a roll at the edge behind, into which the vertical lines of the hair extend.

Compare the archer on an even finer scaraboid in the Southesk collection, which is probably by the same hand (Pl. A, 10; F., pl. 9, 23, and, enlarged, pl. 61, 14; Southesk Catalogue, pl. 2, B 8): for the attitude, the slinger on an archaic red-figured cup in Leipsic (Hartwig, Meisterschalen, pl. 18, 1; Hoppin, Euthymides and his Fellows, p. 83).

Probably by Epimenes: see number 28.

About 500.

#### 28

R. 817. Bu. O 14. Pl. 2, and, enlarged, Pl. 9. From the Tyszkiewicz collection. Count Tyszkiewicz told the present owner that it was certainly found in the Egyptian Delta and perhaps at Naucratis. F., pl. 9, 14; enlarged, pl. 51, 7; drawn, ii, p. 44. Bulle, *Neue Jahrbücher*, 1900, pl. 1, 13. Perrot, *Histoire de l'Art*, ix, p. 18, fig. 19, after Furtwängler's drawing; Fowler and Wheeler, *Greek Archaeology*, p. 387, fig. 308.

Scaraboid. Sapphirine chalcedony.

Hatched border. A naked youth holding the bridle of a restive horse. Signed by the artist, EPIMHNES EPOIE, 'Emipévis émolei. The youth is in three-quarter backview, with the right leg seen from behind: his hair cross-hatched, with the lower edge pelleted. The horse's mane and tail pelleted; pelleted topknot. The mouth open with the teeth showing; the lips puckered; three creases on the neck; single lines, studded with pellets, for the headpiece of the bridle; ornamental peytrel rendered by a long line with a series of V-shaped appendages; three short lines, each tipped with a pellet, running out from the lower extremity of each.

A fairly accurate facsimile of the inscription is given on Furtwängler's drawing. The iotas and the first stroke of the pi are long. The cross-bars of the epsilons have an upward tendency: twice, the vertical stroke projects above and below the cross-bars, and once below only. The straight lines of the omega run diagonally. Similar representation of the E and o sounds occurs on archaic inscriptions from the Cyclades and Thasos: in Attica only from about 470 to 450 B.C.; the artist

cannot have been an Athenian.

Two other works may be attributed to the engraver Epimenes. The first is a scaraboid which resembles ours in every comparable point: the Southesk archer from Naucratis (Pl. A, 10). The material of that stone is said to be white marble, but Furtwängler calls it burnt sard and John Marshall pronounced it to be discoloured chalcedony. The second is the archer scaraboid number 27 in the present collection, a less exquisite piece than the other

two, but in the same style.

All three stones have the three-quarter backview, and the signed stone presents one leg from behind. The artist, therefore, has the same conception of form in space as the Attic vase-painters of the riper archaic period, the period which is inaugurated by Phintias, Euphronios, and Euthymides (see Hartwig, Meisterschalen, pp. 154-61: Vases in America, pp. 27-8). Epimenes appears to be slightly younger than those pioneers, but older than the later archaic painters to whom the style was no innovation, the Brygos painter, for example, and his contemporaries, the degree of whose archaism may be compared to that of the Greek stones numbers 30 and 31, and the Etruscan numbers 40 and 41, in this collection.

A third stone which appears to bear some resemblance to the

work of Epimenes is the scaraboid of rock-crystal, with a seated youth making a helmet, which has recently been acquired by the Munich collection: exactly how close it stands to our stones cannot be determined from the not very clear reproduction in

Archäologischer Anzeiger, 1917, p. 35.

It is natural to begin by equating Epimenes with Attic vasepainters, because they have left more and clearer examples of this style than any other body of artists. Of course it is traceable in other classes of monuments. It has not hitherto been found on Ionian vases produced beyond doubt in the eastern part of the Greek world, in particular not on Clazomenian vases, for the three-quarter backview noted by Duemmler on the London vase from Aeolian Kyme (Römische Mitteilungen, iii, p. 161 and pl. 6) exists, as may be seen from Mansell's photograph, in the illustration only. The style is also unknown in Caeretan hydriai, which are sometimes thought to have been made by Ionians working in the West. We come upon it at last in full swing on the notable amphora in Würzburg republished not very long ago by Klein (Gerhard, Auserlesene Vasenbilder, pl. 194; Jahreshefte, xiii, pll. 5-6). This vase also was no doubt made by an Ionian in Etruria. Turning from vases to wall-painting, we find what we are looking for in the Tomba delle Bighe at Corneto, where the decoration was probably executed not merely under Ionian inspiration but by Ionian hands (Weege, Jahrbuch, xxxi, pp. 105-53). Coins offer fewer or less obvious instances than gems: examples, such designs as the discobolos on the early coins of Cos (Gardner, Types, pl. 4, 28; J. H. S. xxvii, p. 30) and the horseman on the early coins of Kelenderis (Gardner, Types, pl. 4, 26). In sculptured relief, examples are still less frequent: but the stele carved by the Ionian Alxenor of Naxos (Perrot, Histoire de l'Art, viii, p. 361) looks almost like a drawing by Douris translated into stone. The legs are similarly foreshortened on a Melian clay relief in the British Museum (B. M. Catalogue of Terracottas, pl. 19, 2). The style which we have been following up belongs essentially to the history of drawing and not to the history of sculpture; low relief or intaglio in whatever material, occupying an intermediate place between the two arts, but partaking almost more of the first than of the second. The parallel development in sculpture proper does not require illustration here.

For the peytrel, and the dotted headpiece of the bridle,

Furtwängler (ii, p. 96) has already referred to Clazomenian vases and sarcophagi. We have encountered the dotted headpiece on the stone number 21: it is also found on the sarcophagi in London (Murray, Terracotta Sarcophagi, pll. 1-7) and in Berlin (Antike Denkmäler, ii, pl. 58); on fragments of a Clazomenian hydria in Athens and Brussels (Athenische Mitteilungen, xxiii, pl. 6), on a Clazomenian vase in London (Antike Denkmäler, pl. 2, 21, 2), on a neck-amphora of the same fabric from Kertch (Izvestiva Imperatorskoi Arkheologicheskoi Kommissii, ix, 1904, p. 85), and on a Clazomenian fragment, from Naucratis, in Oxford; and as late as the ripe archaic period in a representation of Hades carrying off Persephone on Locrian clay reliefs (Bollettino d'Arte, iii, p. 467, fig. 37; Ausonia, iii, p. 171). The dots represent metal studs set in the leather straps: a more precise rendering is found on Assyrian reliefs. In the great mosaic from Pompeii, the horses of Darius and Alexander have the headpiece heavily studded (Winter, Das Alexandermosaik aus Pompeji, pl. 1; Springer, Handbuch der Kunstgeschichte, i, pl. 13).

A peytrel of the same type as ours is worn by horses on the Clazomenian sarcophagi in Berlin (Antike Denkmäler, ii, pl. 26) and in London (Murray, Terracotta Sarcophagi, pl. 5), and on the Clazomenian vase from Aeolian Kyme in the British Museum (Römische Mitteilungen, iii, pl. 9). The other peytrels cited by Furtwängler and by Rossbach (in Pauly-Wissowa, s.v. Epimenes) are not of this type. Furtwängler sees a floral motive in our example, but there is nothing floral either here or in the cases quoted above. These bands must be textile (or possibly leathern), tasselled, perhaps, but not necessarily, enriched with beads. Tasselled peytrels of the same type are worn by Assyrian horses, for instance on a relief from the Palace of Ashur-nasir-pal at Nimrud (Assyrian Sculptures in the British Museum, pl. 17, 1). In the Alexander mosaic, the horses of Darius wear a plain band, evidently of stuff, perhaps silk, with a single tassel in front on the breast (Winter, loc. cit.).

The horse on our stone has traits in common with the earlier horse on number 21, but the treatment here is far freer and more spirited. Broadly speaking, it belongs to the same family as the horses on the sarcophagi and the vases of Clazomenae (for example, Antike Denkmäler, ii, pl. 26; Murray, Terracotta Sarcophagi, pll. 1-7; Antike Denkmäler, ii, pl. 58; ibid., ii, pl. 56, 3). More closely akin, because bolder and more masterly,

the horse and the ass on the Caeretan hydria in Berlin (Antike Denkmäler, ii, pl. 28). Furtwängler compares our horse with those on the marble frieze attributed to the Treasury of the Cnidians at Delphi, and the resemblance is undeniable: see, in especial, Homolle, Fouilles de Delphes, iv, pll. 9–10. Comparable also the horses on coins of Erythrai (Babelon, Traité, pl. 12, 10 and 11), and the earlier horses on the ivory plaques, of Ionian style, published by Pollak (Römische Mitteilungen, xxi, pl. 15, 2 and pl. 16, 2: see his page 323). These Ionian horses, whether carved or painted, are distinguishable from their Attic fellows, more reticently elegant, by their emphasized points, by their fierier mettle and haughtier allure. The horse of Euphronios (Furtwängler-Reichhold, Griechische Vasenmalerei, pl. 22) is one of the few Attic works which the horse of Epimenes brings to mind.

With regard to groups of horse and man, see the reference quoted on number 21. A group painted on the wall of the Tomba delle Bighe at Corneto (Weege, Jahrbuch, xxxi, supplement to p. 138) so far resembles ours that the youth is seen in foreshortening from behind.

About 500 B.C.

29

B. B. 150, 2. Bu. O 12. Pl. 2. Formerly in the Naue collection at Munich. F., pl. 6, 30.

Scaraboid, cut. Chalcedony.

Hatched border. A griffin holding a youth, dead or overcome, between its paws. The wings of the griffin are straight. Spiny comb; long straight ears, the ends now broken away; bulging forehead without horn; short stout beak, jaws open with teeth and tongue showing; goggle eye; ruff at the throat, with curving lines on it. The youth's hair striated, combed forward in front and downwards behind: the lower edge pelleted. His left hand is open with the back showing; his right arm raised with the hand hanging behind the head, as in numbers 37 and 38.

Furtwängler speaks of this stone in his History (iii, p. 104), and points out that the representation is probably to be regarded as a variant of a common theme, a youth felled by a sphinx.

A naked youth attacked by a griffin is the subject of a bronze relief from Palestrina, Greek work of the late fifth century, in New York (*Monumenti*, ix, pl. 31, 3; Miss Richter, *Greek*,

Etruscan, and Roman Bronzes in the Metropolitan Museum, p. 62, number 94), but there the youth carries a sword and is probably therefore an Arimaspian.

Beginning of the fifth century.

#### 30

R. 820. Bu. O 24. Pl. 2, and, enlarged, Pl. 9. Bought at Castrogiovanni (Enna) in Sicily. F., pl. 61, 15.

Scarab, cut. Sard. The lower part missing: chipped on

the head and above the shield.

Hatched border. A young warrior bending over to pick up his helmet: his shield on his arm: the left leg frontal. In the field, the letter A, very large, no doubt the first of the owner's name. The hair cross-hatched: the lower edge rendered by

two rows of pellets.

The same subject and design on a sard scaraboid, with a Cypriote inscription, in the De Clercq collection (Pl. A, 7: De Ridder, Collection De Clercq, vii, pl. 19, number 2795), and also on two archaic Etruscan scarabs (F., pl. 20, 6; Burlington Catalogue, pl. 110, M 24; Wyndham Cook Catalogue, pl. 2, 40: and F., pl. 20, 7); close, a fragmentary scarab, late Etruscan or early Italiote, in Berlin (Furtwängler, Beschreibung, pl. 7, 376); a somewhat similar design on an Italiote stone (F., pl. 23, 68). Compare also the youth lifting a discos on a scarab from Cyprus in the British Museum (F., pl. 9, 6), and on an archaic Etruscan scarab in the Cabinet des Médailles (Collection Pauvert de la Chapelle, pl. 6, 87; F., iii, p. 449, fig. 232).

Beginning of the fifth century.

# 31

Pl. 2, and, enlarged, Pl. 9. From Cyprus. Bought from Mrs. W. T. Ready in 1917.

Scaraboid, cut. Sard, brownish. The stone has been pared

all round, especially at the sides.

Hatched border. Ground band of pellets between two lines. Achilles and Penthesilea. Achilles pierces the falling Amazon in the right side with his spear: with his left foot he treads on her

ankle: his right leg frontal, slightly bent at the knee. Shield on arm, Corinthian helmet, chlamys fastened below the neck with a brooch: sword suspended from a baldrick at his side. Beardless; the hair, as far as visible, pelleted; three pellets indicate a slight whisker, four the pubes. The right leg of Penthesilea is frontal, and slightly bent at the knee; the right foot is seen at full length: in her left hand she holds a bow, in her right the spear about to drop: short chiton, girdled, and drawn up so as to expose the pubes, which is rendered by four pellets: peaked cap with a thin flap in front of the ear: plain necklace and circular earring: a large quiver with arrows in it at her side. The hair over her brow rendered by a row of pellets: behind, long and striated. Her dress presents two difficulties: the first is the two short horizontal lines between her breasts, which do not fit into the system of folds: it is conceivable that they represent a clasp fastening back the short sleeves from the shoulders, but such a clasp is without analogy. The second is the two curved lines, one at either wrist: at first sight they look like bracelets, but the width, and still more the irregularity, of the curves suggest the ends of sleeves on closer scrutiny. The Amazon would be wearing a sleeved undervest, reaching not much farther than the waist, in addition to her chiton. Just such a costume is worn by the Amazon who grasps her battleaxe with both hands on a red-figured calyx-krater in New York (Furtwängler-Reichhold-Hauser, pll. 118-19).

In the field, behind Achilles, a star. A star is often placed in the field on gems (for example, F., pl. 8, 8 and 9) and on

coins, without determinable significance.

A somewhat similar Achilles and Penthesilea on a red-figured hydria in New York, the work of the Berlin painter in his early period (J. H. S. xxxi, pl. 9). The figures on the stone are somewhat more limber, thanks mainly to the bending of the frontal legs at the knee. On the stone, the collapse of Penthesilea is complete: on the vase, as in other Attic representations (fragmentary cup in the Cabinet des Médailles, Monumenti, ii, pl. 11, 2: compare the calyx-krater in the Louvre, Millingen, Peintures de vases grecs, pl. 49, and phot. Giraudon), the Amazon is still able to extend her hand in appeal.

A parallel to the position of Penthesilea's legs is not easily found: the profile leg is usually more fully flexed, as for instance in the group, akin to ours, on the hydria by the Eucharides

painter in the Vatican (Gerhard, Auserlesene Vasenbilder, pl. 202: phot. Moscioni 8602).

The same exergual line on archaic coins of Laos and of

Sybaris (Gardner, Types, pl. 1, 10 and 11).

The indication of the female pubes is very rare apart from Attic red-figured vases. There also, but hardly on gems, parallels can be found for the indication of the veins on the frontal foot.

Early fifth century.

32

R. 542. Bu. O 28. Pl. 2. Whelan reported that the ring was certainly found at Paphos. It was bought from a Dutch priest who was said to be a kinsman of the Duke of Norfolk. According to Ready, who had the first offer of it, the priest had purchased most of his antiquities at Amathus, but had added some at Larnaka. F., pl. 61, 30.

Sard scarab in a gold ring.

The beetle rough. Ridged. No winglets. Along the lower edge of the thorax, a pair of lines, interrupted in the middle of the stone. The elytra not separated. The hoop of the ring octagonal: band setting enriched with egg pattern, inlaid with white, red, and blue enamel, between a plain and a globulated border.

Hatched border. Eros flying with a sprig in either hand. Recurved wings. A wrap over both arms. The hair short and plain, with the lower edge pelleted. The arch of the ribs prominent: within it four bosses, arranged two and two.

Eros, in his earliest representations, is commonly associated with music, as in number 33, and with plants or flowers as here.

'Ωραίος καὶ 'Ερως ἐπιτέλλεται· ἡνίκα περ γῆ ἄνθεσιν εἰαρινοῖς θάλλει ἀεξομένη, τῆμος 'Έρως προλιπων Κύπρον περικαλλέα νῆσον εἰσιν ἐπ' ἀνθρώπους σπέρμα φέρων κατὰ γῆς.

Theognis, vv. 1275-9.

See number 33.
Early fifth century.

G. P. 319, 3. Pl. 2. Bought in 1907 from a Carian who said it came from Caria.

Scaraboid, probably of discoloured sard, in a gold ring. The hoop of the ring circular, with wires twisted round it at the ends and passing through the stone, which is kept in place by two eyelets in the form of a four-pointed star covered with globules.

Hatched border. Eros flying with a wreath in one hand and a lyre in the other. Recurved wings at shoulder and ankle. Long hair, striated, and at the neck cross-hatched: over the brow a row of pellets: long locks falling on the breast. The upper part of the shoulder wings pelleted: pellets for the dark

markings on the tortoise-shell body of the lyre.

A replica, on a sard scarab, was at one time in Mr. Cowper's possession (Pl. A, 4). The same design on a sard, set in a ring, which was formerly in the Newton Robinson collection (sale catalogue, pl. 1, 20) and on a stone which was once in W. T. Ready's hands. Similar, number 32 in the present collection, and a stone of somewhat different style in Dorpat (F. iii, p. 103, fig. 71). The type culminates in the sard scaraboid from Cyprus in New York (Pl. A, 3; F., pl. 9, 22; Myres, Cesnola Collection, p. 421, number 4223), where a winged youth is carrying off a naked woman who holds a lyre. Whether the youth on the New York stone can be called Eros is doubtful, for Eros is not seen following after women till the middle of the fifth century, and it is not in his original nature to do so, for he is the deification of the Eromenos, of the pursued and not the pursuer: but a better name can hardly be found.

Earlier than all these, the scaraboid number 20.

The first quite certain representations of Eros are to be found on Attic red-figured vases of the later sixth century (Vases in America, p. 7). Almost contemporary with these, Eros running with a flower and a lyre on a Greek bronze mirror in the British Museum (B. M. Catalogue of Bronzes, pl. 17, 1): his feet are winged as in number 20 and in the present stone. Later, the coins and statues mentioned by Thiersch in Jahrbuch, xxx, pp. 179-92.

Early fifth century.

R. 562. Bu. O 29. Pl. 2. From Golgoi in Cyprus. Bought from W. T. Ready in 1897. F., pl. 61, 17.

Scaraboid. Chalcedony.

Ground line. A crouching lion: above him an eagle flying with a serpent in his talons. The teeth and tongue of the lion showing: puckered nose. Short bristling hairs all along the back. The mane rendered by two rows of short lines, one along the neck, the other on the breast, with a series of longer lines between them, slightly undulating and approximately horizontal. The body of the eagle and the uppermost part of his wings pelleted: vertical lines round his neck. The snake ringed.

A lion very like the present one, though more archaic, on number 22, which also came from Cyprus. Similar also the chimaera on a rock-crystal scaraboid in London (Pl. A, 9: Imhoof-Blumer and Keller, *Tier- und Pflanzenbilder*, pl. 25, 40). The

mane is rendered in the same manner on all three stones.

A lion with a flying eagle above is found on a series of Cypriote coins which has been assigned to Amathus (Hill, B. M. Coins of Cyprus, pl. 18, 3-10, pl. 1, 6-15, and pl. 2, 1; Babelon, Traité, pl. 132, 18-23, and pl. 133, 1-7), but in these the lion is couched on his hind-legs, and the coins, even the earliest of them (Hill, pl. 18, 3), are rather later than the stone. Closer, an earlier coin attributed to the same locality, of which Hill publishes a poor specimen (pl. 18, 1) and Babelon a better (pl. 132, 11): here the mane, at any rate in the forepart on the obverse, resembles that on the scaraboid. In another group of Cypriote coins, assigned to Golgoi, the attitude of the lion is the same as on our stone: and the earliest of these lions (Hill, pl. 13, 5: a better specimen, Babelon, pl. 27, 20) bears considerable resemblance to ours: the back is bristly, and the mane appears to be rendered in the manner described. This coin is dated 'before 480' by Hill; and '450 B.C.' seems a little too late for the earliest of the Amathusian series. Another lion not unlike ours, in treatment as in pose, is that on a coin of Hyele (B. M. Coins of Italy, p. 304, number 2; Babelon, pl. 68, 11), which, from the likeness of the female head on the obverse to the Arethusa on the Syracusan Damareteion, may be dated about 480.

For the bristly back, see number 65.

About 480.

Pl. 2. According to memory from Greece.

Scarab. Clear sard.

The beetle fairly careful. Carinated. No winglets. Along the lower edge of the thorax, a hatched border. Between the elytra a line.

Hatched border. A bull rousing himself.

Bulls of this type are common on archaic and early free gems. Other examples on sard scarabs in the Wyndham Cook and De Clercq collections (Pl. A, 14; Cook Catalogue, pl. 2, 33: De Ridder, Collection De Clercq, vii, pl. 20, number 2873, from Tortosa), on a rock-crystal scaraboid in Boston (Pl. A, 15; Duffield Osborne, Engraved Gems, pl. 8, 3; fragmentary inscription, retrograde, OE. AESE..), on a sard scarab formerly in the Sarti collection (Vendita Sarti, pl. 28, number 431), and on another, of very poor work, in the British Museum; on an Etruscan sard scarab in New York; and, somewhat barbarized, on two scaraboids of black jasper in the Southesk collection (Southesk Catalogue, pl. 17, O 34 and O 28): the latest and finest member of the series is a sard scaraboid from Tanagra in Berlin (F., pl. 8, 41). A similar bull, grouped with other figures, on sard scarabs in Berlin (F., pl. 8, 58) and in the Southesk collection (F., pl. 6, 29; Southesk Catalogue, pl. 1, A 17), on a sardonyx scarab in the Story-Maskelyne collection (F., pl. 6, 52; Burlington Catalogue, pl. 108, O 49), on a sard scarab from Gela in the Evans collection (F., pl. 6, 51), and on a chalcedony scaraboid from Thebes in Boston (F., pl. 6, 44). Compare also the Acheloos on a sard scarab in London (F., pl. 9, 75). The same type on archaic coins of Cyzicus (Babelon, Traité, pl. 176, 41 and 42).

A sheep in the same attitude on number 35 bis.

On the inscribed scaraboid in Boston, the action of the bull is explained by the presence of a gadfly on his hind-quarters.

First third of the fifth century.

# 35 bis.

Pl. 2, and, enlarged, Pl. 9. From Stimnitza near Dimitzana in the Peloponnese. Formerly in the Evans collection: acquired in 1919.

Scarab or scaraboid, probably the latter, cut. Bluish chal-

cedony mottled with white.

Hatched border. A ewe getting up from the ground. Inscription, retrograde, giving the owner's name, ΕΡΜΟΤΙΜΟ ΕΜΙ, Έρμοτιμου εἰμί. The ewe is shorn save on the neck, where the wool is indicated by pellets. Long tail passing between the legs: creases on shoulder and elbow: large eye.

The attitude is common in bulls on gems: see number 35. Walking rams on two Ionian stones, both more archaic in style than ours: a plasma scarab in the British Museum (F., pl. 9, 17), and a chalcedony scaraboid in the Cabinet des Médailles (Collection Pauvert de la Chapelle, pl. 6, 67; F., pl. 9, 11): both bear owner's names, Mandronax and Bryesis.

The inscription is written in small, neat characters. The upright of the first epsilon overlaps the cross-strokes above and

below.

First half of the fifth century.

### ETRUSCAN: ARCHAIC

35 ter.

Pll. 2 and 8, and, enlarged, Pl. 9. From the Evans collection: acquired in 1919: originally bought in Rome.

Pseudo-scarab, the beetle replaced by a figure of Dionysos in relief. Clear sard.

No vertical border. The god is running in archaic posture to the left: his head is frontal: in his right hand a drinking horn, in his left a big vine branch with clusters, leaves, and tendrils, which passes above his head and hangs down as far as his right heel. Ionic chiton, with hatched borders at sleeves and ankles: mantle over both shoulders. Long even striations for the pleat-like folds: in the mantle, every other pleat is hatched. The outline of the hair above the forehead is a series of arcs convex to the face. The spade beard and the long moustache are hatched vertically. Goggle eyes: hatched eyebrows. For such pseudo-scarabs, see F. iii, pp. 79, 91, and 178-9; also our numbers 23 and 44: the figure of Dionysos is unique.

Pellet border, which stops at the ground line. Exergue filled with triangles hatched and counter-hatched. The subject is one

of Herakles' adventures. The hero moves quickly to the right: opposite him is a smaller man with knees and body bent, and right hand raised, open and in profile. Herakles' right hand grasps this person's left: the left arm of Herakles is extended, with the forearm concealed behind the other's body. Behind Herakles stands Athena, holding her spear in her left hand, and raising her right with the index finger extended upwards and the other fingers closed: behind the other man, a woman, whose right hand is raised, with the fingers spread out, holding a flower composed of a bud between two tendrils, and whose left arm is bent at the elbow with the hand open, in profile, and thumb upwards.

The figures are very short. The cheeks, except Athena's, are so modelled, that the heads seem, at first sight, to be helmeted. The limbs of Herakles are powerful, with copious inner marking; his knee-caps, ankles, and elbows are rendered by pellets. His eye is set very high. A row of pellets for the hair over his forehead: no beard indicated. He wears a short chiton, striated, the lower border vertically hatched; over the chiton, a lionskin. His opposite has a long garment passing over his right shoulder and leaving his left shoulder free: this is no doubt a himation: if he is wearing a chiton under it, it is not indicated. The chin is pointed and therefore bearded. The hair is plain: it falls in a long mass behind: it is bounded by a plain curved line in front of the ear, and by a plain straight line high on the forehead: a pellet marks the ear. Athena is clad in chiton, mantle, both striated, and long snake-fringed aegis. The crown of her head is chipped away: but it is almost certain that she wore no helmet. Her hair is striated, and falls in a mass behind: over the forehead, short locks terminating in small pellets. The other female figure wears the same costume as Athena, save the aegis: her mantle has a hatched border. The skull is plain: behind the ear, three locks of hair, the outermost pelleted, the others plain: stephane, vertically hatched in front of the ear.

The interpretation principally depends on the person with whom Herakles is engaged. It seems clear, from the attitude of this person, that the encounter is not an amicable one. The face is bearded. Moreover, the hair begins noticeably higher up on the forehead than in the other figures: this suggests incipient baldness and hence old age: the figure may therefore be Nereus,

the old man of the sea.

The contest of Herakles and Nereus is represented on a

number of monuments from the later part of the sixth century and onwards: though not elsewhere in the same scheme as on our gem. The female figure behind Nereus may be his wife Doris, but Doris might be expected to show dismay: Hera?

The style of the stone may perhaps be called Etruscan rather than Greek. If it is Etruscan, it is one of the earliest Etruscan gems.

Second half and probably third quarter of the sixth century.

# 36

R. 1916. T. L. 14, 1. Bu. O 80. Pl. 3. Bought in 1900. Scarab. Murky sard.

The beetle careful. Winglets. Vertical egg border. Round the sides and the lower edge of the thorax, a hatched border, with a rectangular space left plain half-way along the lower edge. The clypeus goffered: the plates cross-hatched. A line between the elytra.

Pellet border, which stops at the ground line. Exergue filled with triangles hatched and counter-hatched. A naked youth led off by two winged females clad in chitons. The hair plain, and rolled up at the back of the neck. Four round bosses for the rectus abdominis. Rather than encumber his composition, the artist has given the females but one wing each.

The females would seem to be death demons: a parallel representation is to seek, but a somewhat similar group on an Etruscan tombstone of free style (Grenier, *Bologna villanovienne et étrusque*, p. 447) is clearly a descent to the underworld: a youth is being hurried off by two males, one winged, one carrying a torch: see also Ducati, *Monumenti dei Lincei*, xx, pp. 607–12.

End of the sixth century.

### 37

G.P. 219, 847. Bu. O 68. Pl. 3. From Corfu. Bought from Madame Heimpel, daughter of Rhousopoulos, in 1901.

Scarab. Sard.

The winglets almost rubbed away. Triple hatched vertical border. A hatched border, now very indistinct, round the sides and the lower edge of the thorax. Between the elytra, probably three lines.

Hatched border. Ajax dead. A naked bearded man, body and right leg frontal, his right hand behind his head, has fallen on his sword, which passes through his left side: a female figure moves quickly towards him and covers him with a large cloth. She wears a chiton, girdled, with short kolpos: the general outline of the right leg is shown through the cloth. Her hair, which is plain, falls in a heavy mass behind and is tied near the end. Pellets on the upper part of the wings. The hair of Ajax reaches to his shoulders and is filleted and hatched. His left arm raised, with the hand at the crown of the head: his right foot seen at full length.

In the Ajax of Sophocles (915 ff.) Tecmessa spreads a garment

over the disfigured corpse of her husband:

. . . άλλά νιν περιπτυχεῖ φάρει καλύψω τῷδε παμπήδην, ἐπεὶ οὐδεὶς ἂννοὄστις καὶ φίλος τλαιη βλεπειν . . .

The figure on the stone is winged, and therefore cannot be Tecmessa. It is not unlikely that Sophocles took the motive, Tecmessa covering the body of Ajax, from an earlier, say an epic poem; that the representation on the stone is derived, in the long run, from the same source; and that the engraver, or a predecessor, added wings to the female figure on the analogy of kindred scenes where divine beings are busied with the dead or dying, as, for example, on the stones numbers 36 and 38 in the present collection. It is winged youths, and not mortals, holding a heavy cloth, who are painted on the walls of the Tomba della Pulcella at Corneto, one at each side of the alcove in which the inmate of the tomb reposed (Antike Denkmäler, ii, pl. 43).

Although the stone is traced to Corfu, the style is Etruscan

rather than Greek.

Beginning of the fifth century.

38

R. 816. Bu. O 17. Pl. 3. Bought by Tyszkiewicz in Naples. P. J. Meier, Annali, 1883, p. 213; Collection Tyszkiewicz, pl. 24, 8; F., pl. 16, 22. A rough sketch in F. Parkes Weber, Aspects of Death and Correlated Aspects of Life, p. 651, fig. 111, and Aspects of Death in Art and Epigram, p. 379.

Scarab. Sard.

The beetle careful. Slightly ridged. Winglets. Vertical egg border. Round the sides and the lower edge of the thorax, a hatched border, interrupted by a triangular depression half-way along the lower edge. Round the head, outside it, two rows of

dots. A line between the elytra.

Hatched border. A dead youth borne by two winged figures, one female and one male. The corpse is naked, the pose parallel to that of Ajax on number 37: the hair hatched, and the lower part of it falling vertically from the neck (compare number 37). The male bearer is naked, the female clad in chiton and himation. The hair of both filleted and hatched: in the male, done up into a little roll at the back of the neck, in the female reaching to the shoulder and worn zazzera-wise. The upper part of the wings

pelleted.

The disposal of Memnon's body is depicted in Attic vasepaintings of the early fifth century (Löwy, Zur Aithiopis, in Neue Jahrbücher, 1914, pp. 81-94: earlier literature is cited by Löwy; see also Riezler, Weissgrundige Attische Lekythen, pp. 9-10, and Wilamowitz-Moellendorff, Aischylos, Interpretationen, p. 245, note 3). The representations, as Löwy shows, divide into two classes corresponding to two different moments in the story. In one class, the winged goddess Eos is lifting her son, still dripping with blood, from the field of battle, or bearing him away in her arms (cup signed by Douris, Pottier, Douris, p. 41: pelike by the Syleus painter, Vases in America, p. 66). In the other, it is two winged youths, Hypnos and Thanatos, who are raising the body, now washed and anointed, to carry it to that remote country where Memnon is to enjoy the immortality granted him by Zeus (cup in the British Museum, Wiener Vorlegeblätter, D, pl. 3, phot. Mansell 3168; calyx-krater in the Louvre, Monumenti, vi-vii, pl. 21).

Löwy, in his brilliant article Zur Aithiopis (p. 82), conjectures that the engraver of our stone has fused the two moments, and that our female is to be called Eos. Before this interpretation is accepted, two other Etruscan scarabs must be considered. On the Morrison stone (F., pl. 16, 23; Morrison Catalogue, pl. 1, 46), one of the bearers is female as in ours, and the other male; but in the later and rougher stone in the British Museum (B. M. Catalogue, pl. E, 346) both are female. A like variation of sex is observable in another class of monument: a bronze cistahandle, of archaic Latin style (Catalogue de la Collection Ales-

sandro Castellani, Rome, 1884, pl. 8, number 282) is formed of two armed and winged male figures carrying the body of a young warrior: and on another cista-handle (Reinach, Répertoire de la statuaire, ii, p. 521, 2) the winged bearers are both female.

It may be taken that Eos does not appear on the London stone or on the last-named cista, for a pair of Dawn-goddesses is out of the question. This does not imply that our female is not Eos, for the type may have been reinterpreted and diversified later: but it makes the identification doubtful. Our female may

be a death-goddess.

We have left out of account those examples in which the bearers are wingless and therefore presumably mortal, in particular the handle-groups on Prenestine cistae (for example, Reinach, loc. cit., iv, p. 322, 2, now in New York, with male bearers: ibid., ii, p. 322, 1, one bearer female: ibid., ii, p. 521, 1, Bollettino d'Arte, iii, pp. 179, 181, and 183, two warriors bearing a woman): for by the time they were made the group had become a decorative type without mythical significance.

Beginning of the fifth century.

#### 39

R. 566. Bu. O 22. Pl. 3, and, enlarged, Pl. 9. Bought in Perugia, 1896-7. F., pl. 61, 19.

Scarab. Banded agate, bleached, now white and sky-blue.

The beetle careful. The winglets reduced to humps. Vertical cable border with pellets in the loops. Round the sides and the lower edge of the thorax a hatched border, interrupted half-way along the lower edge. The clypeus and the plates dotted.

Between the elytra two lines.

Pellet border. Small exergue, with egg pattern: the right foot of the figure passes over this and rests on the border. Achilles, beardless, bending and drawing a cloak over his shoulder with both hands. On the ground in front of him a Corinthian helmet. Inscription AVILE, Achile, retrograde. The hair hatched, worn zazzera-wise and filleted. The pubes indicated by three small pellets.

The position of the legs, one frontal with the foot foreshortened, the other crossed behind it, is particularly frequent in red-figured vases of the ripe archaic period, though it is found some decades earlier, for example on the calyx-krater by Euphronios in Berlin (Archäologische Zeitung, 1879, pl. 4; Hoppin, Euthymides and his Fellows, pll. 20–1).

Early fifth century.

40

B. B. 84, 2. R. 1261. Bu. O 4. Pl. 3, and, enlarged, Pl. 9. From Vulci. Formerly in the possession of Campanari, later in the Evans collection. F., pl. 16, 60, and, enlarged, pl. 51, 1.

Translucent sard scarab in a gold sepulchral ring. Cracked across. The hoop is hollow, oval outside and flattened inside: it is soldered to two shields, of the type shown in Marshall, B. M. Finger Rings, p. xliv, D ii, through which the pin passes: the stone is secured by two rings between stone and shields. The beetle careful. The winglets reduced to humps. Vertical

The beetle careful. The winglets reduced to humps. Vertical border of egg pattern surmounted by a thin band into which the uprights of the egg border are produced. Round the sides and the lower edge of the thorax, a hatched border with a semicircular dip half-way along the lower edge. Head, clypeus, and

plates dotted. Between the elytra, three lines.

Pellet border. An athlete pouring sand on his thigh. He kneels on a heap of sand, with left thigh frontal, left leg from knee to ankle foreshortened away, and left foot in three-quarter profile, a common attitude on red-figured vases of the ripe archaic period (cup by the Colmar painter, *Le Musée*, iii, p. 55; cup by the Panaitios painter, Hartwig, *Meisterschalen*, pl. 15, 2). The hair short and pelleted.

First quarter of the fifth century.

41

G. P. 342, 2. Pl. 3, and, enlarged, Pl. 9. From the Boulton collection (sale catalogue number 3).

Scarab. Murky sard.

The beetle careful. The winglets reduced to humps. Vertical egg border, surmounted by a hatched border. Round the sides and the lower edge of the thorax a hatched border with a triangular depression half-way along the lower edge. The head (barring the eyes), clypeus, and plates dotted. A line between the elytra.

Hatched border. Ajax falling on his sword: behind him,

the scabbard: the hilt is planted on the ground, symbolized by the hatched border, and the point directed towards the hero's ribs. The left leg frontal, and the right leg crossed behind it; as in number 39. The massive forms present a contrast to the slender elegance of the contemporary figure on number 39. The long hair, which is filleted, and the trim beard are hatched: the hair hangs down in front of the head and recalls the hair on number 38. The nipples at the corners of the pectorals: the linea alba indicated from navel to pubes. The hands more

formal than the rest of the figure.

The same subject on two Etruscan scarabs of free style, one in the British Museum (Pl. A, 19: B. M. Catalogue, pl. E, 312; F., pl. 17, 32), the other in the Wyndham Cook collection (Pl. A, 20; Burlington Catalogue, pl. 110, M 127; Wyndham Cook Catalogue, pl. 2, 41). The motive is different in all three: in our stone the figure is made frontal in the taste of the ripe archaic period. An earlier moment is represented on a scarab in Copenhagen (F., pl. 64, 38), which bears a Latin inscription and is poorly executed in the globolo style. Other versions of the suicide of Ajax are discussed by Milani in Bollettino d'Arte, ii, pp. 361-8: the excellent bronze statuette in Florence, found at Populonia, which is published by Milani (ibid., pl. 2 and p. 362: also in Notizie degli Scavi, 1908, pp. 208-9, and in American Journal of Archaeology, 1909, p. 208) is Etruscan work of the same period as our gem.

A seventh-century representation of the same subject on a lenticular gem of green serpentine in the Evans collection: it was found at Peraia near Corinth and bears the retrograde

inscription SAGINAN.

First quarter of the fifth century.

42

G. P. 348, 2. Pl. 3. Bought in Rome, 1912.

Scarab. Sard: partially translucent.

The beetle careful. Winglets. Vertical egg border, surmounted by a hatched border. Round the sides and the lower edge of the thorax, a hatched border. The parts about the head broken away. Three lines between the elytra.

Pellet border. Herakles lying on a raft, which is supported by amphorae half-submerged. With his right hand he holds the end of the sail, as well as his bow and arrows; in his left hand his club, as if he were steering with it: his left hand rests on a little doubled cushion. Beardless: short hair, full at the neck,

hatched, with faint pelleting over the forehead.

The left thigh is frontal, the rest of the left leg foreshortened away: for this motive see Jacobsthal, Göttinger Vasen-Συμποσιακα, p. 51: one of the earliest examples is on the psykter signed by Euphronios (Furtwängler-Reichhold, pl. 63), and it is common

on ripe archaic vases.

The same subject on an Etruscan mirror from Cervetri in the British Museum (627; Monumenti, viii, pl. 33), and often on Etruscan and Italiote stones. Nearest ours, the coarser scarab in Copenhagen (Pl. A, 17; F., pl. 64, 26 and ii, p. 291), where the leg, however, is not foreshortened as in ours and others. Examples and variants; F., pl. 19, 38-9; pl. 19, 36-7; pl. 20, 39; pl. 19, 35 and 40; and Gabrici, Monumenti dei Lincei, xxii, pl. 116, 10. For the craft, compare the scarab F., pl. 18, 13, and the Boeotian kotyle in Oxford (Gardner, Ashmolean Vases, pl. 26). The subject is discussed by Furtwängler (F., iii, p. 197), but his conclusion is open to doubt: the representation is probably to be connected with Herakles' western voyage (Pindar, Nemeans, iii. 38).

First quarter of the fifth century.

43

G.P. 351, 5. Pl. 3, and, enlarged, Pl. 9. From Chiusi. Bought in 1914.

Scarab. Banded agate.

The beetle careful. The winglets reduced to humps. Vertical egg border. Round the sides and the lower edge of the thorax, a hatched border. Head, clypeus, and plates dotted. Between the elytra, three lines.

Pellet border. Herakles, beardless, drawing water in a pointed amphora from a fountain, the spout of which is in the form of a lion's head: behind him, his club and his bow with the string loose. Inscription BEPCLE, Hercle, retrograde. The hair short,

and cross-hatched with the lower edge pelleted.

The subject, Herakles at the fountain, is common on gems: F., pl. 8, 39, Greek: the rest Etruscan and Italiote (F., pl. 17, 45; pl. 61, 23; pl. 19, 20; pl. 20, 25: compare also pl. 19, 19 and 22).

An agate scarab, of excellent Etruscan workmanship, in the

museum at Corneto resembles ours in style (Pl. A, 16): a naked youth, inscribed FELE, Pele, Peleus, is dropping oil from an aryballos into the palm of his hand: squatting on the ground in front of him, his little negro attendant who holds his sponge.

First quarter of the fifth century.

#### 44

G. P. 225, 1. Pll. 3 and 8. Bought in Rome, 1909.

Pseudo-scarab, the beetle replaced by a siren in relief. Banded agate, brown and white.

No vertical border. The siren is very carefully wrought. Both head and body are frontal: the fists are close together, one under each breast: the legs are also folded up symmetrically. Sleeved chiton with the border at the neck hatched. Long hair, filleted, and falling in a heavy mass on either shoulder.

Several siren-scarabs are mentioned by Furtwängler (pl. 8, 23 and iii, pp. 178-9): there are two others in the Southesk collection (Southesk Catalogue, pl. 2, A 36, and pl. 1, A 2=F., pl. 20,

11). The head is usually in profile.

Pellet border. Warrior running and looking round, with spear and shield. Short chiton, leather corslet, helmet with cheek-pieces. On the skull of the helmet, a spiral; on the forehead-piece, an eyebrow. A row of pellets where the crest is attached to the helmet: two others, between lines, across the waist of the corslet. The corslet has a border, vertically hatched, at the neck. The long hair escapes from the helmet behind.

First quarter of the fifth century.

# 45

G. P. 341, 4. Bu. L 52. Pl. 3. From Arezzo: Furtwängler says Chiusi, wrongly it seems. Formerly in the Evans collection. F., pl. 20, 12.

Scarab. Murky sard.

The beetle careful. Winglets. The vertical border reduced to a single uneven line. Round the sides and the lower edge of the thorax, a hatched border. The parts about the head broken away. A line between the elytra.

Pellet border. Eros flying down with a taenia in his hands.

The hair hatched, filleted, and worn in a long zazzera.

First quarter of the fifth century.

R. 446. Pl. 3. From the Bruschi collection at Corneto: bought in 1896. F., pl. 61, 24.

Scarab. Opaque sard.

The beetle careful. The winglets reduced to humps. Vertical egg border, surmounted by a hatched border. Along the lower edge of the thorax, a hatched border, which may have extended to the sides, but here the surface has suffered. Three lines between the elytra.

Hatched border. Jason, swallowed by the dragon, or perhaps issuing from its mouth. Beardless; petasos; sword in right,

shield in left.

A scene from the same story on a red-figured cup, painted in the later manner of Douris, in the Vatican (*Monumenti*, ii, pl. 35; phot. Moscioni): the hero's name is given as Jason.

First half of the fifth century.

## GREEK: FREE STYLE

47

B. B. 66, 286. R. 1235. Bu. O 32. Pl. 3. Furtwängler says that Dr. Töpffer acquired the stone from Sparta about 1890, but that it was known many years previously. Later in the Tyszkiewicz collection. Collection Tyszkiewicz, pl. 24, 6; F., pl. 10, 3; Tyszkiewicz Sale Catalogue, pl. 27, number 286; Perrot, Histoire de l'Art, ix, p. 28, fig. 30, from a drawing.

Sard, slightly convex; cut down at the back.

Line border, stopping at the ground line. Apollo with sceptre, hawk, and spray of laurel, accompanied by a roebuck. He stands with both feet frontal, the right knee slightly bent, and the left side of the body consequently a little higher than the right. A short cloak over his shoulders. A pellet at either end of his sceptre. The toes rendered by pellets. The eye large and in profile, with a stroke below it to model the cheek. The hair worn zazzera-fashion, with a fillet: striated, the edge pelleted.

Figures with both feet frontal do not occur so early as figures with one foot frontal and one in profile: one of the earliest instances is the woman on a cup by the Panaitios painter in

London (F. R., pl. 23). The bent knee marks a later stage, that of the marble youth from the Acropolis at Athens who has been associated with Kritias; the statues of the Olympian pediments; and the vases of the Niobid painter and the Villa Giulia painter

(see Vases in America, p. 142).

A figure of a young man, inscribed Kastor, in the same position as our Apollo, is engraved on a glass scaraboid from Spata in Attica (not Sparta, as Furtwängler says) which was formerly in the Evans collection (Pl. A, 23; F., pl. 12, 23): it is somewhat later than our stone, for the attitude is freer and the

modelling less hard.

Sceptres topped with a plain knob are less common than might be expected: the instances quoted in Daremberg and Saglio (s.v. sceptrum) do not bear examination. A golden sceptre which may be said to be of this type was found at Taranto and is preserved in the British Museum (Marshall, B. M. Catalogue of Jewellery, p. 232, number 2070, fig. 65): it is surmounted by a glass quince surrounded by leaves.

The spray, no doubt meant for laurel, characterizes the god

as Katharsios (Overbeck, Apollo, p. 309).

The hawk is associated with Apollo by Aristophanes and other writers: the references have been collected by A. B. Cook (Zeus, i, p. 241). Apollo appears with a bird on certain coins, which are cited by Froehner in Collection Tyszkiewicz, for example, on those of Themistocles (Babelon, Traité, pl. 88, 3), but where the nature of the bird can be made out, it seems to be not a hawk but a crow or raven. On the archaistic relief in Turin (Schrader, Jahreshefte, xvi, pp. 23 and 26) only the wing of the bird is preserved. On a late archaic cup in the Villa Giulia (a tiny reproduction, useless for this purpose, in Bollettino d'Arte, x, p. 337), the bird which Apollo holds is called a raven by Savignoni, but the present writer took it to be a hawk, if not an eagle, on account of its hooked beak.

The date of the stone cannot be far removed from that of the pedimental sculptures at Olympia. The gem which stands nearest to ours is perhaps the chalcedony scaraboid from Cyprus, with Hades and Persephone, in New York (F., pl. 9, 32). Ours

is somewhat harder in style.

Between 470 and 460.

R. 819. Bu. O 16. Pl. 3. Formerly in the Bourguignon collection. Bought by Bourguignon in Constantinople. F., pl. 61, 32.

Gold ring with engraved bezel. The hoop quadrangular.

Short ground line. Hermes, clad in a chlamys, resting his left elbow on an Ionic pillar: in his right hand a phiale, in his left a kerykeion. The hair short and pelleted. Volutes, echinus, fluting, torus, and plinth of the column are all indicated: the plinth in perspective.

An early example of what later became a favourite motive in gems and in other works of art: one instance out of many, the

Herakles on a scaraboid in Berlin (F., pl. 10, 41).

another in Boston (F., pl. 20, 10).

A Hermes in the same attitude and with the same attributes as ours is engraved on a sard scarab from Taranto, of free Etruscan style, in the museum at Lecce (Pl. A, 22). Hatched vertical border; a hatched border round the sides and the lower edge of the thorax; two lines between the elytra. A little dolphin is engraved on the thorax: compare the female head engraved on the back of a sard scarab in the British Museum, and the head of Bes on

It is generally considered, that the Polycleitan Narcissus and the Berlin Amazon are among the earliest sculptures in the round, in which a pillar forms an integral part of the composition; but it is not surprising that various collocations of man and pillar had been made by painters long before: so on archaic redfigured vases (amphora in Petrograd, mentioned in Vases in America, p. 57, number 1; pelike in Copenhagen, mentioned in J. H. S. xxxvi, p. 128, \(\epsilon\); cup in London, Hartwig, Meisterschalen, pl. 34; Vases in America, p. 93, fig. 61); in the free period, nearer the date of the statues, on a cup in Miss Lamb's collection (\(\frac{\gamma}{\gamma}\). H. S. xxxviii, p. 35, fig. 8); on another in the Villa Giulia (Monumenti dei Lincei, xxiv, p. 895); and on an oenochoe in the British Museum (Guide to the Exhibition illustrating Greek and Roman Life, p. 112, fig. 97).

Hauser held that our ring showed marks of Peloponnesian

style.

About the middle of the fifth century.

G. P. 323, 1. Pl. 3. Bought in 1908 from a Greek, who alleged that it came from Delphi.

Scaraboid. Yellow jasper, mottled with chalcedony.

Ground line. Apollo, naked, moving towards the tripod and extending his right hand over one of the rings: his bow in his left hand. The long hair, which is covered with thick, irregular striations, seems to be plaited behind in transverse plaits, something like that of the discobolos on the archaic relief in Athens (Conze, Die attischen Grabreliefs, pl. 4). A single lock passes in front of the ear and falls on the breast. The arrangement over the brow is hard to make out: a wreath is impossible because there is no trace of it behind the ear; a metal stephane would explain the pointed projection in front, but is objectionable on other grounds; some such effect would be produced by two long locks of hair, one in front of each ear, lifted and tied over the forehead; but locks so tied (Furtwängler, Meisterwerke der griechischen Plastik, pp. 678-81, and Intermezzi, pp. 5-6) are not found elsewhere in combination with long hair at the back of the head.

The tripod has leonine feet and stands on a ground line of its own: the bowl is rounded, with the upper edge curved, and

the two lateral rings are also in perspective.

The thick-set, heavy figure brings to mind certain early coins from North Greece (Gardner, Types, pl. 3, 1-2 and 4-6) and the Herakles on a coin of Thebes (ibid., 45). The forms of thigh, knee, and calf suggest the sixth century; but the upper part of the body is foreshortened with moderate accuracy, and the forms of it belong to a later period. The cutting is deeper and the modelling broader than in early stones. The back hair, if rightly explained above, is dressed in a sixth century fashion, but the treatment of it is not contemporary with the coiffure.

The figure is probably an imitation of an earlier Apollo, and

was probably not made before 460 or 450.

An Apollo in a somewhat similar attitude forms part of a 'Contest for the Tripod' on a sard scarab in the Cabinet des Médailles (F., pl. 10, 18), which shows, in Furtwängler's words, 'free style with old-fashioned elements purposely retained.' It is possible that our Apollo is derived from a representation of the Struggle for the Tripod: this might explain the action of the figure.

For the two ground lines, an early coin of Kaulonia may be

compared (Gardner, Types, pl. 1, 1).

# 49 bis.

Pl. 3. From Melos. Formerly in the Evans collection: acquired in 1919.

Scaraboid. Rock-crystal.

Hatched border. Uneven ground line. Two Amazons, one seated on a rock with a spear in her left hand, her right raised as if greeting the other, who rides slowly towards her, holding the reins in her left and a short goad in her right. Both Amazons wear the same costume: a sleeved and trousered garment, cross-hatched to suggest the lozenge pattern; over it a short chiton, pulled up a little to cover the girdle; soft shoes; and a high cap of soft material with two flaps and a peak. Striations for the folds of the chitons. The horse is a strong cob: the ears are pointed forward; the mouth open: the tail somewhat unevenly striated.

The seated Amazon may be compared with the figure of Paris, seated, and clad in Oriental costume, on a red-figured pyxis lid, datable to the third quarter of the fifth century, in the museum at Copenhagen (Dumont-Chaplain, Céramiques de la Grèce propre, pl. 10). Compare also the Amazons on a hydria of Lucanian style in Naples (3241; Archäologische Zeitung, 1856, pl. 89).

Second half, and probably third quarter, of the fifth century.

### 50

B. B. 150, I. Bu. O 13. Pl. 3. Said to have been found in a tomb at Kara in Attica about 1860. It passed into the hands of Admiral Soteriades, and was later in the possession of Rhousopoulos; then in the Evans collection. Stephani, Compte rendu, 1868, pl. 1, 12; a poor drawing. King, Antique Gems and Rings, i, p. 400: a mere caricature. Furtwängler, Jahrbuch, iii, pl. 8, 8; Evans, Revue Archéologique, xxxii (1898), pl. 8, 2, enlarged, but reversed; F., pl. 14, 3, and, enlarged, pl. 51, 8; Hekler, Greek and Roman Portraits, p. ix, fig. 1, enlarged; Delbrueck, Antike

Porträts, pl. 58, 1, enlarged; Fowler and Wheeler, Greek Archaeo-

logy, p. 391, fig. 318.

Detailed discussions of the stone by Furtwängler in Jahrbuch, iii, pp. 201-2, and F., iii, p. 138, and by Evans in Revue Archéologique, xxxii (1898), pp. 337-55 (The Athenian Portrait-Head by Dexamenos of Chios). On Evans's identification of the portrait as Cimon, see F., iii, p. 138, and Bernoulli, Griechische Ikonographie, i, pp. 100-1.

Scaraboid. Yellow jasper mottled with red. Line border.

Portrait head of a bearded man. Above, the artist's signature,

retrograde, in two lines, AEZAMENOS EPOIE.

Facsimiles of the inscription are given by Furtwängler (Jahrbuch, iii, p. 201) and by Evans (loc. cit., p. 344). Evans notes that the form of the xi is Chiot: but it also occurs on Attic red-figured vases. The second upright of the nu higher than the first. The upright of the epsilons tends to project beyond

the cross-bars. Broad alpha with horizontal bar.

The lips parted: the eyebrows meeting. The beard rendered by long undulating lines, the hair, which is scanty in front and worn full at the nape, by groups of the same, which produce a fleecy effect; the shorter hairs on the forepart of the skull engraved on the flat surface of the stone. The eyeball prominent; the line marking the exterior side of the iris is nearly straight; the eyebrow is rendered by slanting lines, nearly straight; on a ridge; the fold of skin above the upper eyelid indicated. Two curved lines, in a horizontal direction, starting at or near the anterior point of the upper lid, mark the upper profile lashes: three, the uppermost faint, from the lower lid, the lower profile lashes. The rest of the lashes, upper and lower, represented by short lines with a downward direction. Four very fine sharp lines for the wrinkles on the forehead, three for the creases at the back of the neck, three others between hair and eye.

Since the stone is by Dexamenos, it must have been produced within not very many decades of the signed scaraboid in Cambridge (F., pl. 14, 1), which has severe elements and can hardly be much later than 450. Our stone is generally admitted, by reason of its style, to be not earlier than the Cambridge stone. Within the limits thus set there has been some difference of opinion. Evans places it as early as 450, Delbrueck about 430,

Furtwängler and Hekler between 430 and 420. Precision is difficult on account of the scarcity of analogous representations

and the highly personal character of the style.

Evans (loc. cit., pp. 348-50) pays particular attention to the minutely careful presentment of the eyelashes, and remarks that a similar rendering of the upper profile and the lower vertical lashes is found on the Damareteion, struck in 479, and on 'transitional' coins of Syracuse, but is less pronounced on the earliest signed coins, while on the earliest of Euainetos' tetradrachms, struck about 425, the lashes have ceased to appear, although there are faint vestiges of lower eyelashes on coins signed by Eumenes, and on the decadrachm by 'the new artist' (Evans, Syracusan Medallions, p. 28). The lower lashes are also indicated in the head of Zeus on an Elean coin (Evans, pl. 8, 4), but here the upper profile lashes are lacking, and the exact date of the coin is uncertain, although it is generally placed about 450. The upper profile lashes alone are still indicated on one of Cimon's decadrachms (Evans, Syracusan Medallions, pl. 2, 8), therefore after 413.

A somewhat similar rendering of lower vertical and upper profile lashes is prevalent on Attic vases of about 460 to 450 (for example, Vases in America, p. 163; Riezler, Weissgrundige attische Lekythen, pl. 36; F. R. H., ii, p. 264, fig. 44A), but is also found later, for instance, on a nuptial lebes in New York which cannot be earlier than 430 (Bulletin of the Metropolitan

Museum, xi, p. 255).

These coins and vases, however, supply no counterpart to the peculiar treatment of the upper lashes, carried over on to the surface of the eye itself so as to point downwards and not upwards. The same, accompanied by upper profile lashes and lower vertical lashes, both as in the coins and the vases, on a white lekythos in Athens (Riezler, op. cit., pl. 90); but this vase cannot be much earlier than the end of the fifth century. Both sets of vertical lashes as in our head, on an Etruscan mirror, of still later date, in the Vatican (Gerhard, Etruskische Spiegel, pl. 287, 3) and on an oinochoe of barbaric Campanian style in the British Museum (F. 526; Walters, B. M. Catalogue of Vases, iv, p. 222). It must be admitted that the treatment of the eye affords no conclusive evidence for a date as high as 450. It should also be remembered that Dexamenos, with his passion for minute finish, might well insert details which the art of his time, with its eye

on the whole rather than the parts, was tending to chasten away: further, that it is probable, from his interciliary hairiness, that the sitter had prodigiously thick eyelashes as well, which led the artist to pay special attention to that feature, and to produce a rendering of it which surprised his contemporaries and which he himself would not have thought credible before he took the portrait in hand.

For the present it seems best to date the stone in the third

quarter of the fifth century.

The existence of strongly individualized portraits at so early a date in Greek history would not have seemed probable from the Cresilaan Perikles, but might have been divined from the heads of Charon on Attic white lekythoi and from the head of an elderly warrior on the krater, already mentioned, in New York (F. R. H., ii, p. 264, fig. 44A; Buschor, Griechische Vasenmalerei, p. 183). Another portrait head, not much later if at all than ours, on a gold ring in Berlin (F., pl. 10, 35). A third, of much slighter workmanship, on a gold ring found in a tomb at Kertch and now in Oxford (Pl. A, 29; Ernest Gardner, J. H. S. v, pl. 47, 6): the objects supposed to have been found with it would allow a fifth-century date; but Professor Rostovtsev states that the apportionment of the objects from Kertch in Oxford rests on highly untrustworthy information. The rough scaraboid, number 51 in the present collection, also seems to have the character of a portrait. Evans makes the attractive suggestion, that such portrait gems as ours, preserved as family treasures, may have sometimes been consulted by later Greek sculptors for their presentations of long-dead worthies.

This may be thought an appropriate place to put together those stones which stand a fair chance of being by Dexamenos. The ascriptions have all been made by Furtwängler, with the exception of the Bowdoin stone; but not all his ascriptions have

been included.

Chalcedony scaraboids:

Cambridge, from Greece. A seated woman and her maid.

Signed. F., pl. 14, 1.

Petrograd, from Kertch. Flying heron. Signed. Pl. B, 3; F., pl. 14, 4.

Lewes House, probably from Greece. Heron. Pl. 5.

Lewes House, from Messenia. Horse. Pl. 4.

Cabinet des Médailles. Bolting horse. F., pl. 14, 15.

Scaraboids of yellow jasper mottled with red:

Petrograd, from South Russia. Heron and grasshopper. Signed. Evans, Revue Archéologique, xxxii, 1898, pl. 8, 3; F. iii, p. 137.

Lewes House, from Attica. Portrait head. Signed.

Petrograd, from Kertch. Griffin attacking horse. F., pl. 31, 3.

Rock-crystal scaraboid:

Mrs. Cockerell, from Greece. Seated woman playing the harp. F., pl. 14, 20.

Sardonyx scarab:

British Museum. Flying goose. F., pl. 14, 2.

Barrel of banded agate:

Bowdoin College. Heron. Pl. B, 4: see number 66.

51

G. P. 342, 4. Pl. 3. From the Boulton collection, 1911 (sale catalogue number 4, 3).

Scaraboid. Cloudy sapphirine chalcedony, discoloured at the

back.

Line border. A woman's head. Sakkos, plain necklace. Apparently a portrait, but the roughness of the work makes this rather uncertain. The mark near the neck in the imprint is due to damage in the stone.

Probably late fifth century.

52

G. P. 244, 2. R. 2609. Bu. O 23. Pl. 3. Bought from Charles Newton-Robinson in 1901. F., pl. 12, 23.

Scarab. Sard. A chip has destroyed part of the eye and forehead, another the lower part of the head behind the ear.

The beetle careful. Slightly ridged towards the hump. No winglets or vertical border. A hatched border all round the thorax. The elytra separated by two lines which curve apart before they reach the border of the thorax; two short lines start from these near the top and meet at the thoracic border.

Head of a negress. She wears a headdress consisting of an ample kerchief wound tightly round the head turban-wise; the

tip of the securing end visible; the frizzled hair showing in front and behind. Pendant earring in the general form of a lotus-bud terminating in a pellet. Necklace of pellets, representing beads, with a pendant in front, part of which is now missing. The Venus rings indicated.

Warm, rich modelling, recalling the decadrachms of Kimon.

End of the fifth century.

#### 53

G. P. 272, 5. Pl. 3. Bought from Lambros in 1902. Gold ring with engraved bezel. The hoop nearly circular.

Short ground line. Erotostasia: Aphrodite weighing two Erotes; a third Eros at her feet. She stands with her right leg frontal and bent at the knee. Ionic chiton, low-necked, bordered above by two lines: dotted himation, in which the left arm is concealed.

The attitude of the minute Erotes on the scales is not easy to establish: the left-hand one seems to be sitting with his right shin frontal, his right thigh foreshortened away, and his left leg doubled and in profile: the right-hand one nearly frontal and on hands and knees, something like the Eros on an Attic pelike of the fourth century in Petrograd (F. R., pl. 70). All three have the long thin wings which came into fashion in the third quarter of the fifth century.

A similar representation, on a Campanian hydria in London, has been published, after Mansell's photograph, by Studniczka (Jahrbuch, xxvi, p. 140). The vase-painting shows that the concealed arm of our Aphrodite is resting on her hip and holding up the gathered folds of her himation. So also on a gold ring from Syracuse in the British Museum with a female figure, shown to be Aphrodite by the dove which flies to her, and Eros kneeling at her feet, busy with her sandal (B. M. Finger Rings, pl. 2, 56).

Another Erotostasia, on a krater in Athens, is mentioned by Nicole in his supplement to the Catalogue des vases peints du

Musée National d'Athènes, p. 246, number 1105.

Subjects like ours have been collected and discussed by Studniczka (loc. cit., pp. 139-41).

Later fifth century.

G. P. 297, 1. Pl. 4. Bought in Athens, 1903.

Gold ring with engraved bezel. The hoop quadrangular.

A rider striking with a lance at a spotted fallow deer. The deer is also attacked by a hound; in front of the horse's head, a flying bird of prey. The rider wears a short chiton, girdled, and a chlamys: hair and chlamys blown back. The horse's mane rendered by short strokes on a ridge, with a longer fore-

lock: the lines on the tail arranged V-wise.

The rider seems, from the breast, to be female: if so, the choice lies between an Amazon and a heroine, for Artemis does not ride on horseback. Stephani gives two instances of Artemis mounted on a horse (Compte rendu, 1860, pp. 45-9); but the figure on the Attic bell-krater is Selene or rather Nyx, not Artemis, and that on the coins of Pherai Hecate (Percy Gardner, B.M. Coins of Thessaly, pp. 47-9).

End of the fifth century.

55

Bu. O 7. Pl. 4. Bought in Athens. F., pl. 65, 4. Scaraboid. Chalcedony.

Ground line. A two-horse chariot wheeling round: the action is described by Furtwängler (ii, p. 297). The charioteer is beardless, and has shortish hair with free striations: the lower part of his long chiton is blown back. The horses are of the same general type as those on the coins of Syracuse from the later fifth century onwards: small heads with hogged manes, powerful cylindrical bodies, solid hindquarters. Ours are somewhat longer in the barrel, possibly owing to the shape of the stone. Horses of similar breed on a chalcedony scaraboid in the Cabinet des Médailles (F., pl. 9, 54).

The manes are rendered by short strokes set on a ridge and

projecting a little beyond it.

The head of the hither horse is in perspective, the upper part being more prominent than the lower, and the orbit of the off eye visible. This foreshortening of the horse's head occurred in painting of the Miconian period, for it is found on the Amazon krater in Bologna (F. R., pll. 75-6), but it was probably not used in sculptured relief till rather later. The Echelos relief in Athens

has it (Kekulé, 65tes Winckelmannsprogramm, pl. 2), but not the Berlin relief of like subject (ibid., pl. 1), which Kekulé considers somewhat earlier than the other and nearly contemporary with the Parthenon frieze. It appears on Syracusan and Tarentine coins towards the end of the century (Evans, Horsemen of Tarentum, pl. 2, 6), and probably, less pronounced, on an earlier gem than ours, the scaraboid in Petrograd attributed to Dexamenos (F., pl. 14, 15).

The hither horse has all four feet lifted and advanced, while the off horse has its hind legs thrown back with its hind feet on the ground. This motive occurs on decadrachms by Kimon and Euainetos (Evans, Syracusan Medallions, pll. 8-9) and also on subsequent Syracusan issues, but not apparently earlier. This would suggest that our stone is not older than 413: considering

its over-refinement, it might be a decade or two later.

# 56

B. B. 87, 3. R. 1262. Bu. O 1. Pl. 4. Said to be from Asia Minor. Bought in London, 1898. F., pl. 64, 5.

Scaraboid. Amethystine chalcedony.

The child Eros seated on the ground playing with a goose, which lifts its wings. Below, a pair of knucklebones, with which he was playing until the goose came to look. Eros has short hair: an amulet is slung round his shoulder on a string. The sole of the right foot is visible, but the artist has not ventured

to foreshorten the lower leg away.

A somewhat similar Eros, more compactly rendered, on the sard signed by Phrygillos (F., pl. 14, 6). Kindred studies of child life on a sard conoid in the British Museum (F., pl. 10, 30), on a convex sard (F., pl. 61, 29), and on a sard pendant, from Athens, in the British Museum (F., pl. 13, 17); on Attic toy oinochoai; and in the marble statuette of a girl with a duck, from Tanagra, in Berlin (Furtwängler, Collection Sabouroff, i, pl. 35).

For the sole of the foot, compare the convex stone mentioned above, and a Theban coin with the infant Herakles (Gardner,

Types, pl. 7, 23).

Eros is playing with a goose on a bronze repoussé relief, of Greek work, in the British Museum (number 308).

End of the fifth century or beginning of the fourth.

T. L. 11, 1. R. 1914. Bu. O 77. Pl. 3. Bought in Naples, 1899–1900. Roscher, *Lexikon*, s.v. Palladion, p. 1330, fig. 5. Scaraboid. Blood sard.

Palladion. In the field, a bucranium, denoting the sanctuary. Ionic chiton, Ionic himation from the right shoulder; helmet with three crests; plain necklace. The spear in false perspective; the device a wheel. A knotted and tasselled fillet hangs from the spear, and another from the inside of the shield. The base on which the image stands is circular or oval, and bears the letters AA, no doubt the beginning of the owner's name. A long lock of hair, rendered by pellets, escapes from the helmet on either side of the face. The knees are emphasized in the archaic manner. The figure is to be taken as striding towards the spectator, in the attitude of the Athena from Herculaneum, for part of the right leg disappears behind the left, and the hatched paryphe ends at the knees.

The figure is comparable with the Athene Polias of Pergamon on a Pergamene coin (Jahrbuch, iii, p. 46; Roscher, loc. cit., fig. 6). That it does not reproduce a real archaic statue is shown by the triple crest. It may or may not have been inspired by

a particular archaistic image.

An analogous image on a sard of the free period (F., pl. 13, 16). Fourth century.

# 58

B. B. 86, 2. R. 1302. Bu. O 38. Pl. 4. From Cythera. Bought in 1898. Formerly in the possession of Rhousopoulos. Scaraboid. Smoky chalcedony.

Ground line. Diomed carrying off the Palladion. The youth steals forward with the little statue in his left hand and his sword in his right: a cloak on his left arm. The hair short with free striations.

A similar design on coins of Argos (Gardner, Types, pl. 8, 35), which are placed in the first half of the fourth century: a date which will fit our stone. Another version of the same subject on a glass scaraboid (F., pl. 13, 8). A modification of our type is a favourite subject on Greco-Roman gems (see number 125).

G. P. 313, 5. Pl. 3. Bought in Sicily, 1907.

Bronze ring with engraved bezel. The hoop slightly ridged inside. The surface corroded.

Ground line. Eros dog-bodied. The combination is centauric, that is to say, the creature has two pairs of shoulders; but the bestial part seems canine rather than equine: leonine is possible, for ancient representations of lions were often modelled on the dog (Schröder, text to Brunn-Bruckmann, numbers 641-5). That the upper part is a demi-Eros is shown by the wings in conjunction with the plump childish body.

The action is difficult to interpret owing to the condition of the ring: both arms are extended, the right hand apparently bent down with the fingers together as if sprinkling or the like: there seems to be a tall slender object under the left hand, but

the corrosion makes certainty impossible.

A kindred figure on a convex sard formerly in the Evans collection (F., pl. 66, 3): here the creature holds a stick, and wears wrap, pilos, and sword: Furtwängler recalls the bearded daemon on a sard which was once in the Morrison collection (F., pl. 10, 52).

The canine Eros might seem to be a symbol of love without shame; but the attributes on the Evans stone make such an

interpretation of ours improbable.

Fourth century.

60

R. 70. Bought from W. T. Ready, who wrote as follows: 'The stone was bought at Damanhour, and the Arab from whom it was bought said that it was found at this same place a few days before my client's visit there.' Ready vouched for the 'absolute straightforwardness' of his client, whose collection was moreover mainly Egyptian; but not for the Arab. F., pl. 61, 34.

Scaraboid. Sapphirine chalcedony. A big chip missing on

the left of the engraving.

Coitus. See Ovid's Ars Amatoria, iii. 775-6. The man's hair is short, with free striations. The woman wears a necklace, rendered by pellets, a bracelet, a circular earring, thin shoes, and a kerchief wound round the head with the hair escaping at the

forehead and at the crown. Pellets for the hair, except in front of the ears.

Kindred motives in the Hellenistic clay relief found at Pergamon and published by Siegfried Loeschke in Athenische Mitteilungen, xxxvii, pl. 30, 4; and on an incised bronze mirror, of fine early fourth-century style, in the museum at Boston (Six, Jahrbuch, xx, pp. 165-6, figs. 5 and 6). Compare also number 63. Earlier fourth century. Probably Ionian: for the style, com-

pare such stones as F., pl. 63, 10 and pl. 14, 30.

61

R. 815. Bu. O 30. Pl. 4. From the Tyszkiewicz collection. Tyszkiewicz said that he obtained it from Greece: it is further known that he had it from Rhousopoulos. Collection Tyszkiewicz, pl. 24, 14; F., pl. 21, 11.

Sard, slightly convex. The lower part missing.

Hatched border. Ground line. Theseus and the sow of Krommyon. The young hero, naked, his petasos slung behind his neck, presses his left knee on the back of the sow, while his right foot is on the ground. He appears to be passing a noose about the sow; but the details of the action are obscure. It seems clear that Theseus has slipped the cord round his body like the end-man in a tug-of-war, and that he has also attached the upper part of the cord to, say, the trunk of a tree: for the cord is seen under the right arm, following the modelling of the body, and again, drawn taut, to the left of the petasos. The lower part of the cord is held in the right hand: below the sow's mane it presents the appearance of a fork with three prongs which cease at the bristles of the ear. Below this the cord no longer appears.

Short hair in demi-crescent-shaped curls.

Fourth century, hardly earlier than the middle.

62

B. B. 36, 105. R. 1303. Bu. O 33. Pl. 3, and, enlarged, Pl. 10. From Granitza in Doris. Bought from Rhousopoulos in 1898. F., pl. 14, 26.

Discoloured sard, now yellow: slightly convex.

Ground line. Cassandra clasping the image of Athena. She has just reached the image. Her garment, snatched up in haste, has fallen on to her legs, and she is trying to fling it round her again. Her rippling hair falls loose down her back. A bracelet on the left wrist. The archaistic statue wears a tight chiton, and an Ionic himation passing over the left shoulder and peaked at its lower edge; gorgoneion on the breast, so faint as to be barely distinguishable; crested helmet with three locks of hair escaping under the neck-piece; bracelet; shield on the arm; spear passing behind the head instead of in front, the artist having been unwilling to let it cross the face. The statue stands on a base of two degrees, the upper one round or oval, surmounted by a thin slab which projects on either side of the upper degree.

A Cassandra with body half-bared like ours, but without the motive of the hand holding the drapery, on a Campanian hydria in the British Museum (*Archäologische Zeitung*, 1848, pl. 14, 1).

Fourth century.

63

G. P. 338, 2. Pl. 4. Bought in 1911 from a Greek who said it came from Tripolitza in Peloponnese.

Scaraboid. Discoloured chalcedony. Engraved on both sides.

On the flat: ground line; coitus. On the convex: an eagle

standing on a thunderbolt.

The hair of the youth hatched, combed forward in front of the ear, and backwards behind it: the lower edge, back and front, pelleted. The woman's hair is worn in a long pigtail, ending in a pellet, down her back; the pigtail faintly striated, the rest of the hair faintly hatched, with a row of pellets on the forehead. She wears thin shoes.

The technique resembles that of Greco-Persian stones, and the pigtail points to the same quarter. There is a Greco-Persian stone with the same kind of subject in the Cabinet des Médailles

(F., pl. 12, 15–16).

The eagle of Zeus standing on the thunderbolt does not seem to occur before the time of Alexander. There is no reason to suppose that the engraving on the back of our stone is not by the same hand as that on the front, though such cases occur, for instance, in a chalcedony scaraboid in Oxford (Duffield Osborne, Engraved Gems, pl. 8, 20 and pl. 22, 9), where the Aphrodite on the flat is of late fourth-century work, while the heads of Isis and Sarapis on the convex are an addition of imperial date. The date of our stone will be the later part of the fourth century.

Scaraboids engraved on both sides are rare. One of the earliest, a fifth-century piece, is a sard in Berlin (Furtwängler, Beschreibung, pl. 4, 173), in which the sides also are decorated. Another, of black stone, found in a fifth-century grave at Kertch, is described by Furtwängler (iii, p. 128) and figured by Stephani (Compte rendu, 1877, pl. 3, 7 and 8): the convex subject is Persian. A sard from Macedonia, now in New York (F., pl. 12, 38-9, and ii, p. 60), resembles ours in having a bird on one side and a feminine scene on the other, and the style suggests the same region. A chalcedony in Boston (Duffield Osborne, pl. 6, 19) is Greco-Persian. A yellow stone, apparently a discoloured chalcedony, in the British Museum (B. M. Catalogue, pl. B, 112), is perhaps the earliest of all, but is hardly pure Greek.

# 64

Bu. O 44. Pl. 4. Stated by Froehner to have been found in Greece. From the Tyszkiewicz collection (sale catalogue, number 264). Collection Tyszkiewicz, pl. 24, 18; F., pl. 12, 6.

Scaraboid. Banded agate.

Ground line. A zebu walking. In front of him a hoop-shaped mark. Froehner interprets this as the Phoenician symbol for the figure 10, but it is difficult to see the object of inscribing 10 on a gem: Mr. Hill points out that the mark resembles the

Cypriote symbol for ko.

A bull of very similar build and style on a sard scaraboid from Greece in Berlin (F., pl. 8, 47). Furtwängler classes the zebu as Greco-Persian, and the bull as Greek: but no oriental traits are discernible in either. Even if the hoop were a Phoenician symbol, it would not constitute a stylistic orientalism. The vertical marking on the hind-quarter might be considered Persian, but it is an old Greek as well as a Persian convention.

A plunging bull of kindred though coarser style on a scaraboid

in the possession of Comm. Fausto Benedetti.

The zebu engraved on the convex surface of a chalcedony scaraboid in the Wyndham Cook collection (Burlington Catalogue, pl. 112, O 96; Wyndham Cook Catalogue, pl. 3, 57) is said by Furtwängler to be the oldest representation of the animal in Greek art. Our stone, however, is distinctly earlier.

Second half of the fifth century.

B. B. 86. R. 1301. Bu. O 45. Pl. 5. Bought about 1895. Formerly in the possession of a priest at Taranto. F., pl. 7, 59. Sliced barrel. Banded agate; for the shape and material, see number 77.

A lioness crouching for the spring. The mouth open with teeth and tongue showing: the nose puckered. The mane in lanceolations; short lines, representing bristly hair, all along the

back; a tuft behind the elbow.

Lionesses are maneless: Rossbach therefore suggests (in Pauly-Wissowa, s.v. Gemmen, p. 1077) that what seems to be a mane in our lioness is only the fur ruffled in anger. But if the artist had intended to represent this, he would have chosen some other rendering: what we see is indistinguishable from a mane, and indeed, but for the dugs, no one would suppose the animal to be female. The artist had probably never seen the animal he depicts: his lion is essentially the old heraldic lion of the archaic stones numbers 22 and 34, uncorrupted by studies from nature. A lioness with a mane like ours on a scaraboid of

lapis lazuli formerly in the Boulton collection.

The short bristle-lines along the back have already been remarked in the archaic lions from Cyprus, numbers 22 and 34. They also appear on a scarab from Pergamon (F., pl. 8, 43), the scarab F., pl. 10, 59, a scarab from South Italy in the Cabinet des Médailles (Collection Pauvert de la Chapelle, pl. 5, 52), a scaraboid from Cyprus in the British Museum (B. M. Finger Rings, pl. 8, 295), a scarab from Gela in the collection of Sir Arthur Evans (F., pl. 6, 51), and a small scarab which was formerly in the Roger de Sivry collection. Further, on coins of Cyzicus (Babelon, Traité, pl. 176, 23), of Amathus (B. M. Coins of Cyprus, pll. 1 and 18), of Kition (Babelon, Traité, pl. 130, 25), and of Akanthos (Gardner, Types, pl. 3, 13); also in the griffin on certain coins of Teos (B. M. Coins of Ionia, pl. 30, 7); on an Etruscan mirror, of early Ionian style, in the Cabinet des Médailles (Gerhard, Etruskische Spiegel, pl. 292), and on an Etrusco-Ionian amphora, of the so-called Pontic style, at Corneto (phot. Moscioni, 8646).

From the instances given, the short bristle-lines would seem to be an Ionian characteristic and a mark of comparatively early

date: in sculpture, however, the back-mane has a wider extension both in time and in locality.

Second half of the fifth century.

66

B. B. 163, 30. Bu. O 76. Pl. 5, and, enlarged, Pl. 10. Bought in Athens, 1900. F., iii, p. 446, fig. 228; Bulle, Neue Jahrbücher, 1900, pl. 1, 20.

Scaraboid. Chalcedony.

Line border. Ground line. A heron standing on one leg.

Assigned to Dexamenos, with great plausibility, by Furtwängler, on account of its resemblance to the heron stones with his signature in Petrograd: the scaraboid from South Russia, of yellow jasper mottled with red (Evans, Revue Archéologique, xxxii (1898), pl. 8, 3, reversed, and F., iii, p. 137); and the chalcedony scaraboid from Kertch (Evans, loc. cit., pl. 8, 1, and

F., pl. 14, 4).

A replica of our heron, less fine, on a barrel, not sliced, of banded agate, presented to Bowdoin College by Mr. Warren (Pl. B, 4). The Bowdoin heron might be a slighter work by the artist of ours, although the joints of the legs are not rendered in the same way. The same design, by different hands, on a sliced barrel of banded agate, from Athens, in Berlin (F., pl. 14, 11), and on a sliced cylinder of the same material in Boston, which likewise came from Greece (F., pl. 9, 29); also on two rougher scaraboids, one of chalcedony, from the Peloponnese, in Berlin (F., pl. 14, 17), the other, of mottled jasper, in the Southesk collection (Pl. A, 27; Southesk Catalogue, pl. 2, B 5).

All these birds have been taken here for herons, though some of them have been called cranes or even storks. Ours and the Bowdoin bird are beyond doubt herons: the Boston bird and its Berlin companion have no aigrette on the head and no plume on the breast: the Southesk bird and its fellow in Berlin have the aigrette, but are longer in the neck than the others. The aigrette is not essential for an έρωδιός: Dionysius says (de Avibus, ii, p. 18, quoted by D'Arcy Thomson, Glossary of Greek Birds, s.v.): ἴστιν αὐτῶν γενη μυρία . . . καὶ τοῖς μὲν οὐκ ἔστιν ἐπὶ τῆς κεφαλῆς πλόκαμος, ἄλλοις δὲ ὥσπερ τις βόστρυχος ἀπηώρηται.

The heron, and birds which may be mistaken for it, are frequently found on gems of the later fifth and the fourth cen-

turies. A heron, with aigrette, preening itself, on a fragmentary scaraboid of rock-crystal in Oxford: a chalcedony scaraboid of the same type in Petrograd (Antiquités du Bosphore cimmérien, pl. 12A, 8): a standing heron or crane, with aigrette, on a sliced barrel of banded agate, in Mr. Warren's possession (Pl. B, 2); the uncommon elongation of the stone, not to speak of its style, would seem to place it in the fourth century. To the same period belongs the chalcedony scaraboid from the Forman and Newton-Robinson collections, which is now in Munich (Burlington Catalogue, pl. 110, O 83; Newton-Robinson Catalogue, pl. 1, 15; Münchener Jahrbuch, v, pl. B, 7) with a bird drawing a bow: possibly a crane rather than a heron, the aigrette being very short. Probably somewhat earlier, a chalcedony scaraboid, from Cameiros, in the British Museum (F., pl. 11, 30), with a bird feeding: a red-deer's antler is substituted for the aigrette to fill the space above the head: the bird may well be a heron. Three stones may perhaps be grouped together: the sard scaraboid from Kastoria in Macedonia, now in New York (F., pl. 12, 38-9, and ii, p. 60); the pink quartz in Munich (Münchener Jahrbuch. iv, pl. 2, 14); and the chalcedony scaraboid, from Ithome, in Boston (F., pl. 61, 39). There remain the sard scarab in the Cabinet des Médailles (F., pl. 12, 46: perhaps a crane), the chalcedony cube in the Wyndham Cook collection (Burlington Catalogue, pl. 112, O 95; Wyndham Cook Catalogue, pl. 3, 61), and a rectangular stone, of banded agate, in New York.

Rossbach thinks that the popularity of the crane with gemengravers is due to its usefulness as a weather prophet (in Pauly-Wissowa, s.v. Gemmen, p. 1074). The heron was similarly esteemed (Keller, Die antike Tierwelt, ii, pp. 205-6). Moreover, it was sacred to Aphrodite (Collignon, Revue Archéologique, 1875, p. 2). But the real reason for the appearance of the heron and similar birds is that they were domestic pets, cherished by the engraver's patrons, and admired and studied by the engraver. That they should be rare on gems before the middle of the fifth century, may be due to the increasing interest in woman and woman's life, which is a feature of that and the subsequent period (see the well-chosen remarks of Pottier, Catalogue des Vases du Louvre, pp. 1041-6). The birds were naturally the woman's familiars rather than the man's, since she stayed at home; and it is in scenes from the home life of women that they chiefly occur on vases. So, for example, on the Lecce pelike with Polyneikes offering the necklace to Eriphyle (F. R., pl. 66: for the artist, see Vases in America, p. 155), where the crane standing between the two figures serves to show that it is in or near the lady's private quarters that the action takes place. So on the white alabastron, in the British Museum, with the signature of the manufacturer Pasiades ( $\mathcal{J}.H.S.$  vii, pl. 81; Perrot, Histoire de l'Art, x, pl. 19). The representation is in the manner of the Euergides painter ( $\mathcal{J}.H.S.$  xxxiii, pp. 347-55) and belongs to the later part of the sixth century, and is therefore an early specimen, painted on a woman's scent-bottle, of those scenes from the home life of women which became much commoner in later times. The bird standing between the two women seems to be a heron: Perrot, following Murray, is not of this opinion: 'a bird recognizable, by the aigrette on its head, as a crane.' Similarly in gems: on a chalcedony scaraboid, of the later fifth century, in the British Museum (F., pl. 13, 20), a woman, resting on a warm day, is stroking the beak of a bird, which from its aigrette would seem to be a heron, but from its untidy appearance a crane; on a stone in Petrograd (Compte rendu, 1862, pl. 1, 12), a naked woman is standing at a laver caressing a long-legged bird; on a mottled jasper scaraboid of somewhat later style, in the Museum at Syracuse, a naked woman is offering an insect to a heron, and on a sard cylinder, of the later fourth century, in Oxford, a woman is engaged with a bird of the same sort.

The popularity of the heron, in real life, may or may not have been partly due to its value as a weather prophet or as an associate of Aphrodite: its popularity in art is not due to either

of these functions, but to its popularity in real life.

Third quarter of the fifth century.

# 67

R. 215. Bu. O 26. Pl. 4, and, enlarged, Pl. 10. Bought in 1895 from Hartwig. Formerly in the Postolakka collection at Athens, according to Imhoof-Blumer. Hartwig had it from Rhousopoulos, who said that it came from Messenia. Imhoof-Blumer and Keller, *Tier- und Pflanzenbilder*, pl. 16, 37; F., pl. 14, 5, pl. 9, 31, and, enlarged, pl. 51, 9; Bulle, *Neue Jahrbücher*, 1900, pl. 1, 21.

Scaraboid, cut. Smoky chalcedony. Chipped about the head.

Hatched border. A thin hatched band for the ground line. A race-horse walking, with broken reins. Both off-legs advanced in a correct walking attitude. Creases on the breast, on the elbow, behind the elbow, and near the top of the right fore-leg. The ribs very faintly indicated. The mane striated, the ends of the striations being on the flat surface of the stone: longer on the shoulder than on the neck. The tail long, and rendered by long undulating lines. Veins indicated on the belly and the hind-legs. The eye large: the head nervous. The hind-quarters extraordinarily delicate. A high-bred riding horse and not a chariot racer. English judges pronounce it herring-gutted and rather long in the back.

Inscription, in large letters, above, POTA; below, NEA. The omicron a trifle smaller than the rest of the letters. The first stroke of the pi curves slightly inwards. The first and third strokes of pi and nu are not parallel. The cross-bar of the tau comparatively short. The nu oblique; the first stroke the longest. The alphas broad, especially the second; the bar horizontal. The cross-strokes of the epsilon at right angles to the vertical stroke, which projects a little above them. The inscription would seem to be the genitive of the owner's name, but the name

Potaneas is unexampled.

Furtwängler compares the horses on two other scaraboids. One of the two was found at Kertch and is now in Petrograd (F., pl. 14, 15): the horse has flung his rider and is bolting towards the post; the material is the same yellow jasper, mottled with red, which Dexamenos used for two of his four signed stones (see number 50). To judge from the reproduction, the horse is very like ours and might be by the same hand.

The other scaraboid, of chalcedony, is in the Cabinet des Médailles (F., pl. 31, 3), and represents a horse attacked by a griffin. Here also the resemblance is great, and the stone is

quite possibly by the same artist as ours.

Furtwängler considers that our stone 'if not by Dexamenos, is by a greater master of the same time and group'. The lettering

would not conflict with the ascription to Dexamenos.

Hatched ground lines are uncommon: earlier, on coins of Kelenderis (B. M. Coins of Lycaonia, Isauria, and Cilicia, pl. 9, 2 and 3).

Second half, and perhaps third quarter, of the fifth century.

G. P. 217, 832. Bu. O 72. Pl. 5. Bought in Athens, 1901. Scaraboid. Chalcedony, bleached.

Hatched border. A hazel nut.

Realistic representations of vegetable life are known to be extremely rare in antiquity. A nature study so happy and so unaffected is most readily intelligible in a period not very far removed from that of Dexamenos.

Probably later fifth century.

69

Pl. 4.

Scaraboid. Streaked sard.

Line border. A mule walking. Short strokes for the mane and the hair on the tail.

Later fifth century.

70

G. P. 338, 1. Pl. 5. Bought in Athens, 1911. Scaraboid. Chalcedony.

Hatched border. Ground line; the surface of the exergue slopes in towards the border. A wild sow with two young. The mane terminates on the shoulder with a regular curve; a row of short bristles follows; then the long bristles of the rump. This rendering of the mane and back-bristles may be considered a development of that which Furtwängler maintained to be characteristically Ionian (Goldfund von Vetterfelde, pp. 23-4), but which also occurs on Attic vases, for instance, on an archaic redfigured cup in the Louvre (Hartwig, Meisterschalen, pl. 3, 2). A treatment resembling that on our stone, but with the termination of the rump-bristles not convex to the short hairs but concave in the earlier manner, on the Theseus cup by Douris in the British Museum: this detail is not given correctly in Gerhard, Auserlesene Vasenbilder, pl. 234: see Mansell's photograph 617.

A sard scarab with the same subject, of rather earlier style, is figured in F., pl. 7, 63: in his history (iii, p. 105) Furtwängler

mentions other wild sows, mostly earlier than ours.

Second half of the fifth century.

G. P. 349, 5. Pl. 5. Bought from W. T. Ready in 1913. Cylinder. Chalcedony.

A boar walking. The hair between mane and rump-bristles forms a thick striated roll.

Somewhat similar, but probably earlier, a wild sow on a sard scarab in the Wyndham Cook collection (F., pl. 63, 6; Wyndham Cook Catalogue, pl. 2, 29): less like, a boar on a scaraboid of discoloured chalcedony in the Museum at Lecce (Pl. B, 1).

Other stones with representations of boars are mentioned by Furtwängler: add the sardonyx scarab figured by Marshall, B. M. Finger Rings, pl. 10, 346, a Greek stone set in a much later Etruscan ring; and a sardonyx scarab of similar style in Oxford.

Late fifth century.

## 72

B. B. 156, 4. Bu. O 75. Pl. 5. Bought from W. T. Ready in 1899.

Scaraboid, cut. Chalcedony.

Hatched border. Ground line. A goat walking. Hair indicated on breast and buttocks.

Almost contemporary, the walking goat on a rock-crystal scaraboid in the British Museum (Pl. A, 28; Collection d'un archéologue explorateur, pl. 2, 28). Later and broader in treatment, a grandly free and spirited goat on another scaraboid of the same material in the same collection (Pl. B, 6). The goats on the coins of Ainos (Nomisma, iv, pll. 4-5) are of stouter build.

Later fifth century.

## 73

G. P. 347, 5. Pl. 5. Bought in Athens about 1912. Scaraboid. Agate.

Ground line. A goat standing. In the field,  $\Gamma$ , no doubt the initial letter of the owner's name. The goat is of heavier build than in number 72, and is probably of somewhat later date.

Late fifth century.

Pl. 5, and, enlarged, Pl. 10. Formerly in the Boulton collection (part of number 42 in the sale catalogue), but not bought till 1917.

Sard, no doubt a cut scaraboid.

Ground line. A fallow deer browsing.

A replica on a cut scaraboid of pale brown sard in Berlin (F., pl. 14, 13): closely similar, a pale golden sard in Boston, formerly in the Morrison collection (Pl. A, 30): similar also, but rougher, a sapphirine chalcedony which was at one time in the Athenian market (Pl. B, 8); a stone which belonged to Dr. Arndt in 1905; both presumably scaraboids: a discoloured scaraboid in Oxford; and a discoloured stone in Petrograd (Compte rendu, 1865, pl. 3, 28). See also number 75 in the present collection.

Late fifth century.

## 75

G. P. 336, 2. Pl. 5, and, enlarged, Pl. 10. Bought from a Greek in 1909.

Scaraboid. Rock-crystal.

Ground line, mostly covered by the representation of the terrain. The lower part of the stone has been routed out to produce the appearance of a grassy lawn. A fallow deer browsing: he is about to nibble one of the plants which grow round him.

See number 74: the present deer is shorter in the body.

For the terrain concealing most of the ground line, compare the chalcedony scaraboid, from Greece, in Boston, with a griffin attacking a fallow deer (F., pl. 31, 4).

Late fifth century.

## 76

B. B. 65, 269. R. 1231. Bu. O 43. Pl. 4. Sent from Constantinople according to Froehner. From the Tyszkiewicz collection (sale catalogue number 269).

Scaraboid. Black agate streaked with grey.

Line border. A bull-calf. His head is lowered and his tail a little raised as if he were slightly aggressive.

Calves of rougher workmanship, and in different attitudes, on chalcedony scaraboids in Lecce, in Bowdoin College (Pl. B, 5), and in Berlin (F., pl. 11, 16).

Late fifth century.

## 77

G. P. 265, 10. Bu. O 71. Pl. 5. Bought in 1902. Sliced barrel. Banded agate, black streaked with grey.

A sandal seen from above. The subject possibly suggested by the shape of the stone.

A similar sandal, with an insect beside it, on a chalcedony

scaraboid which was once in German private hands.

The vogue of the sliced barrel in Greek lands seems to have been a brief one: most of the Greek examples must be dated to the second half of the fifth century: the latest are probably not much older than the early years of the fourth. The stone given in Pl. B, 2 stands apart from other sliced barrels by reason of its elongated shape. The earliest sliced barrel appears to be Berlin 331 (F., pl. 10, 32), which is still archaic. Far the commonest material is banded agate: other stones are very rare. The Greek eye must have considered the material appropriate to the shape.

# 78

G. P. 328, 7. Pl. 4. Bought in 1911. Scaraboid. Sard.

Hatched border. A coiled snake raising its head. The mouth closed with the tongue extended.

Later fifth, or fourth century.

# 79

B. B. 131, 6. Bu. O 3. Pl. 4. Bought in Ruvo, 1898-9. This is the stone mentioned by Evans, *Syracusan Medallions*, p. 120, note 86, and after him by Sambon in *Corolla Numismatica*, p. 279.

Scaraboid, cut. Sapphirine chalcedony.

Ground line. A plunging bull. The off fore-leg raised. The head in perspective, with the off ear and the orbit of the off eye

showing.

A similar bull on a scaraboid of banded chalcedony in the Wyndham Cook collection (Pl. A, 26; Burlington Catalogue, pl. 110, M 122; Wyndham Cook Catalogue, pl. 3, 62); a similar also on a scaraboid in Petrograd (Compte rendu, 1860, pl. 4, 9), and on a stone, presumably a scaraboid, published by Cades. Of different style, a scaraboid of mottled chalcedony in Berlin (F., pl. 11, 31) and the stone compared with number 64. A pseudoscarab with this bull on it in Petrograd (Compte rendu, 1870–1, pl. 6, 21): a zebu in the same position on the convex side of a chalcedony scaraboid in the Wyndham Cook collection (Wyndham Cook Catalogue, pl. 3, 57). There are several Greco-Roman examples, the finest the chalcedony in the Cabinet des Médailles (F., pl. 45, 11). This bull is very common on Greek coins from the later part of the fifth century onwards.

The three-quartered head is already found in the bull on one of the metopes from the Temple of Zeus at Olympia (Olympia,

iii, pl. 36). About 400.

80

B. B. 64, 263. R. 1232. Bu. O 46. Pl. 5. From Sicily according to Froehner. Formerly in the Tyszkiewicz collection (sale catalogue number 263). Collection Tyszkiewicz, pl. 24, 16; F., pl. 9, 60.

Scaraboid. Yellow jasper mottled with chalcedony.

A pantheress crouching for an upward spring. The head raised, the mouth open with the tongue and the upper front teeth showing: the claws bared. The eye indicated by a pellet.

Froehner calls the animal a lioness; Furtwängler calls it a lioness in his description (ii, p. 48), but a pantheress in his

history (iii, p. 145).

In style, our pantheress resembles the goat on a rock-crystal scaraboid from Lecce in the British Museum (Pl. B, 6) and the walking bull on a rock-crystal scaraboid in the same collection (F., pl. 11, 32).

Late fifth century, or early fourth.

B. B. 66, 284. R. 911. Bu. L 59. Pl. 5. Found in Egypt according to Froehner. Formerly in the Tyszkiewicz (sale catalogue number 284) and Evans collections. *Collection Tyszkiewicz*, pl. 24, 3; F., pl. 9, 28.

Scaraboid. Hyacinthine sard. The side low.

Carrier pigeon.

A dove of the same period on a convex sard, set in a gold ring, from Beyrut, in the British Museum (B. M. Finger Rings, pl. 10, number 350): Marshall compares it with coins of Paphos. A flying dove on a rock-crystal scaraboid formerly in the Tyszkiewicz collection (sale catalogue number 260) and now in Boston.

Earlier fourth century.

## 82

Pl. 5. Given by Mrs. John Marshall.

Silver ring with engraved bezel. The hoop quadrangular.

Ground line. The Nemean lion: a lion, mouth open, at bay, with a club above him. Part of the mane forms a ruff, rendered by a series of short thick close-set arcs: the rest is in long flame-like tufts. The looser skin on the belly is grooved off from the rest of the body. Short bristling hairs on the rump near the tail. The ribs pronounced.

Somewhat similar lions on fourth-century coins of Hyele and

of Sicyon.

A couched lion, with a club above him, on an onyx, set in a ring, published in the *Dactyliotheca* of Abraham Gorlaeus (ii, number 115), where Gronovius compares coins of Macedon, Messana, and Syracuse: the coins of Messana are bronze issues dated 357–288 (Head, *Historia Numorum*, p. 155), those of Syracuse Agathoclean bronze dated 310–304 (ibid., p. 182; Head, *Numismatic Chronicle*, 1874, pl. 9, 3): the Macedonian coin is no doubt one of Archelaos I (413–399) with a lion's head and a club (Head, *Historia Numorum*, p. 221).

Fourth century.

T. L. 57, 1. Bu. O 74. Pl. 4. Bought in Sicily, 1901. Gold ring with engraved bezel. The hoop quadrangular.

A poor old donkey. His body is emaciated (with ribs, shoulder-blade, hips, and vertebrae protruding); except his belly, which is inflated, with swollen veins. The mane straggling and perhaps mangy: a sore on the neck. A study of decrepitude difficult to parallel among Greek representations of animals.

Earlier fourth century.

84

G. P. 326, 5. Pl. 5. Bought in Athens, 1910.

Scaraboid. Mottled jasper, red, black, and yellowish brown.

Ground line, swelling towards the middle. A tripod with a spiked cover on it: the lateral rings foreshortened: leonine feet.

A rather earlier scaraboid with a tripod, from Tanagra, in

Berlin (Furtwängler, Beschreibung, pl. 6, number 306).

For the style, perhaps compare the scaraboid, of dark red jasper mottled with chalcedony, in Berlin (Beschreibung, pl. 6, 320), which is shown to be of the fourth century by the shape of the amphora represented.

Fourth century.

85

G.P. 340, 5. Bu. L 62. Pl. 5. Said to be from Athens. Formerly in the Evans collection. Bought in 1911.

Scaraboid. Bronze.

A griffin sitting on a club: in front of the griffin, starting from its forelegs, a horse's head, bridled. The griffin is of uncommonly massive build: the mouth open: the ears very slightly advanced: a sharp spiny comb on the neck: no ruff and no horn: the beak short: two folds on the neck below the beak.

A griffin with a club below its feet is found on a group of Abderite coins, both copper and silver (*Die antiken Münzen Nord-Griechenlands*, ii, *Thrakien*, pp. 33-4); here, however, the griffin is not seated as in our scaraboid, but either lying down or crouching to spring: this device is accompanied by the name or monogram of the magistrate, and sometimes by his symbol.

A seated griffin is found on a copper coin of the period, but without the club (Nomisma, iii, pl. 3, 12), and is very common on earlier coins of Abdera, often with a symbol added; and although the griffin usually has one paw raised, in one coin he has all four on the ground (ibid., pl. 2, 40). The Abderite griffins tend to be massive like ours, and the comb is similarly short. The club coins belong to the latest group in the continuous series of Abderite issues. The continuous series is generally supposed to have ceased with the absorption of Abdera into the Macedonian Empire about 350 B.C.: the club coins would therefore date from the first half of the fourth century (Head, Historia Numorum, pp. 255-6; von Fritze, Die autonomen Münzen von Abdera, in Nomisma, iii, pp. 22 and 25-6). Strack, however, believes that Philip II must have granted Abdera the privilege of continuing to issue coinage, and would therefore date the coins in question between 352 and about 323 (Die antiken Münzen Nord-Griechenlands, loc. cit.). He adduces two arguments: first, that the standard on which the silver is struck is the Macedonian standard, slightly lowered in the interest of the royal mint; and, secondly, that the club is the badge of the Heraclid kings of Macedon, long employed on their own coins and now placed as a sign of suzerainty on those of a subject city. The fact on which the first argument is based must be left to the numismatist: with regard to the second, the suggestion that the club comes from Macedon is an attractive one; and if it is admitted, the inference as to date seems valid.

There are other instances of the ground line being replaced by a club, but only in Heraclean representations; for instance, on a coin of Tarsos, with Herakles and the lion (Evans, Syracusan Medallions, pl. 5, 6), on a late Etruscan gem with Herakles shooting the birds (F., pl. 18, 69), and on an Italiote gem of Hellenistic style with Herakles pestered by Eros (F., pl. 27, 8). But the griffin has no connexion with Herakles. It can hardly therefore be a mere coincidence that the same design occurs on our scaraboid and on the club coins of Abdera: our scaraboid must be related in some way to the coins; dependent on them, for in the coins the club is explicable; and contemporary with them. The horse's head remains to be explained: it corresponds to the magistrate's symbol on Abderite coins, although this actual device does not occur on any of them.

It is conceivable that the scaraboid was the official or semi-

official seal of an Abderite magistrate: but to assert this would be unwise, for here as elsewhere individual caprice must be taken into account. Whatever the exact explanation may be, it seems probable that the person who ordered the seal had the coinage, if no particular coin, of Abdera in his mind.

It must be admitted that the griffin is not of characteristic fourth-century type: if it is later than the fifth century, it must

be archaistic.

A seated griffin, with all four paws on the ground, is engraved on a scaraboid which was at one time in German private hands.

Bronze scaraboids are rare: another in Berlin (Furtwängler,

Beschreibung, pl. 4, number 146).

# ETRUSCAN; FREE STYLE: AND ITALIOTE

86

B. B. 64, 256. R. 1228. Bu. O 20. Pl. 3. Sent from Constantinople according to Froehner. From the Tyszkiewicz collection (sale catalogue number 256). F., pl. 61, 20.

Scarab. Sard, translucent.

The beetle rather careless. Ridged, especially towards the rump. No winglets or vertical border. A hatched border right round the thorax. Between the elytra a line, with two short lines starting from it near the top and forming a triangle with the thoracic border.

Hatched border. Herakles and the lion. Herakles, naked, bearded, his left foot raised, his right tiptoe, has folded his arms round the lion's throat. The lion has one of his hind-legs raised with the paw pressing against Herakles' shin: his mouth is open with the teeth showing: his nose puckered: his mane rendered by short rippling lines, his shoulder by two quasi-circles each enclosing a boss, the whole resembling two units of a cablepattern. The hair of Herakles short and pelleted, the beard in short thick strokes.

Similar though not identical designs on an Etruscan scarab (F., pl. 17, 57), and on three Greco-Phoenician scarabs, two from Iviza (Pl. A, 11–12; Vives, La Necrópoli de Ibiza, pl. 22, 24; and pl. 23, 15=Perez Cabrero, Ibiza Arqueológica, p. 39, fig. 28), and one, in Cagliari, from Sardinia (F., pl. 15, 75).

Similar also a bronze ornament in Berlin (Furtwängler, Collec-

tion Sabouroff, pl. 148).

Furtwängler has compared our Herakles and the lion with the Herakles and the boar on a sard scarab, found at Chiusi, in the British Museum (Pl. A, 25; F., pl. 18, 30), a brilliant comparison, for the style of the engraving is the same in every respect and the stones are very likely by one hand. The beetles also are similar, though the London beetle is more careful than the other and has the plates and clypeus hatched and three lines instead of one between the elytra: both lack winglets and vertical border: both have flat backs and a ridge towards the rump: in both the hatched border passes right round the thorax, and a short straight line runs to the thoracic border on either side of the elytric division: moreover, the elongation of the engraved side is common to both.

The absence of winglets and vertical border in large and careful scarabs like these would point to a non-Etruscan origin: perhaps also the presumed provenance of our stone. Moreover, the treatment of the lion's shoulder has no parallel in Etruscan work: it is Persian, as Furtwängler points out, and, outside of Oriental monuments (for example, Perrot and Chipiez, *Histoire de l'Art*, v, p. 834), is confined to the Eastern part of the Greek

world (F., pl. 11, 26, and iii, p. 447).

These details, and the masculine compactness of design and modelling, make one hesitate to pronounce the stones Etruscan. They are placed here on account of their general analogy with Etruscan work: but it is possible that they are Greek of about

450 B.C. If Etruscan, they will hardly be much later.

# 87

R. 440. Bu. O 20. Pl. 3. From the Bruschi collection at Corneto. F., pl. 61, 51.

Scarab. Murky sard.

The beetle careful. The winglets reduced to humps. Hatched vertical border. Round the sides and the lower part of the thorax, a hatched border, with a triangular space left plain half-way along the lower side. Two lines between the elytra.

Hatched border. A youth, with a cloak over his left arm, bends forward, holding a staff in his right hand with which he

# ETRUSCAN; FREE STYLE: AND ITALIOTE 73

touches an open-mouthed grotesque head set on a rock. Short

hair, striated. The modelling of the body soft and free.

The grotesque head is oracular: by touching it, the youth invites it to speak. Similar subjects are common on Etruscan and Italiote stones of free style, and are discussed by Furtwängler (iii, pp. 245-52 and 451-2). Compare particularly F., pl. 22, 2, and for the touching of the head with a stick, F., pl. 22, 7 and 8.

Not earlier than the late fifth century.

88

G. P. 338, 3. Pl. 3. Bought in Rome, 1911. Scarab. Sard.

The beetle careful. The winglets roughly indicated. Vertical border of crossing lines, one set of lines twice as numerous as the other. A hatched border round the lower edge of the thorax.

Between the elytra, two lines.

Hatched border. Herakles standing on rocky ground and shouldering the firmament. On one side of him, the Hesperian tree: on the other, a rock with his club stuck in it and his quiver tied to the club. A little plant grows from the rock between his legs. Inscription BEPCLE, retrograde. Herakles is beardless: his short hair is in pellets. Big eye. Thick-set figure, powerful modelling, tighter than in number 89. The same conception of form as in the cups of the vase-painter Aristophanes. The right leg is frontal, and bent at the knee. The firmament is represented by a curving mass set with the crescent moon, two big stars, one at either tip of the moon, and a number of lesser stars rendered by pellets.

The same subject, differently treated, on a sard scarab in Boston (Pl. A, 21): Herakles with body and one leg frontal, his lionskin over his shoulders, supporting the firmament with one hand and holding his club in his left, while Atlas (ADIL, Aril) plucks the Hesperian apple from the tree: the firmament is set with sun as well as with moon and pellet stars: the engraving is in the free Etruscan style, but the original of the design is earlier than in our stone. A third rendering in one of the metopes

from the Temple of Zeus at Olympia (Olympia, iii, pl. 40).

Early fourth century.

R. 843. Bu. O 37. Pl. 3. Bought from an Italian about 1899. F., pl. 63, 23.

Scarab, cut. Murky sard. The outline of the lion's back

missing and restored in gold.

Hatched border. Herakles throttling the lion: bow and club in the field: inscription BEPCLE, Hercle, retrograde. Herakles is beardless, and has short hair rendered with great freedom. Small pellets for the pubes. Heavy forms, massive modelling in the free style. The left legs of the lion press against the hero's thigh, the raised right fore-paw tugs at his arm. The mane is rendered by short lines: short lines for the hair along the belly.

The same design on a sard scarab in the British Museum (Pl. A, 18; B. M. Catalogue, pl. E, 356; F., iii, p. 188, fig. 126). Two smaller versions have been in the Roman market: in one, the club and bow are placed as in our stone; in the other, the club is between the legs. The former bears the inscription CALANIC., Calanic(e), the last letter being doubtful: it is the Greek  $\kappa \alpha \lambda \lambda l \nu \iota \kappa \sigma s$ , and Calanice is used instead of Hercle on an Etruscan mirror (Gerhard, Etruskische Spiegel, pl. 137).

The design has been discussed by Evans (Horsemen of Tarentum, p. 53) and by Furtwängler (iii, p. 188): it is borrowed from the Herakles and the Lion which makes its appearance, towards the end of the fifth century, on coins of Herakleia in Lucania

and other cities.

Early fourth century.

90

G. P. 362, 3. Pl. 3. Bought in London, 1916. Slightly convex. Sard.

Hatched border. Uneven ground line. Maschalismos: a man and a youth dismembering the trunk of a youth: the head lies on the ground, chin to right: the arms are still connected with the body, but one of the men is about to strike with a chopper. The youth wears a chlamys. The hair is short, with loose striations: the man's beard rendered by a row of pellets. Heavy but constricted forms.

Replicas, with slight variations, on a sardonyx scarab (F., pl. 21, 50) and a sard in the Southesk collection (Pl. A, 24;

Southesk Catalogue, pl. 2, A 30). A third version was in the Boulton collection and may be identical with ours. The subject of maschalismoi is discussed by Furtwängler (ii, p. 209): a mythical prototype probably existed but is still to seek.

Italiote. Third century.

91

G. P. 343, 3. Pl. 3. From the Boulton collection, 1911 (sale catalogue number 26, 4).

Sard, translucent. Chipped at the sides and pared round.

A centaur about to hurl a krater. He is of the primitive type composed of a complete human body joined to an equine barrel and hind-quarters. The human body is powerful and heavy, with big pectorals and a large depression for the navel: the penis small, the legs in pure profile: the right ankle rendered by a pellet. The cheek-bone very prominent: the lower part of the face set back from the upper. A row of pellets for the lower edge of the hair, another for the beard: the hair on the skull is covered with lines nearly parallel to the contour of the head; three of these lines run out from above the nape to represent long loose hair. The lower part of the calyx-krater is broken away: round the mouth, a row of pellets, with a line below it: another row of pellets on the cul of the krater near the top. The right hand of the centaur is seen half-way along the upper side of the vessel: his left arm is bent and the fingers of the left hand are pressing against his side. The action of his legs is difficult to determine owing to the fragmentation of the stone: but he seems to be stooping in order to hurl the crater.

The centaur with human fore-legs, common in early Greek art (see Pl. A, 2, an agate scaraboid in the British Museum), is rare in the ripe archaic period and rarer afterwards. On redfigured vases, the cultivated Chiron sometimes has human fore-legs: as late as 460 B.C., on the volute-krater, by the Niobid painter, in Naples (Schultz, Die Amazonen-Vase von Ruvo, pl. 3). Still later examples, the centauress on a Greek scaraboid, of early fourth-century work, in the Cabinet des Médailles (F., pl. 12, 41), and the opponent of Theseus on a Greco-Roman gem of slightly archaistic style (Gori, Museum Florentinum, ii, pl. 59, 1; Reinach, Pierres gravées, pl. 57: a pink paste of the same type, probably ancient, in the British Museum, number 1338). It is clear that

the human fore-legs do not prove our centaur to be of very

early date.

The body, powerful to heaviness, yet very fleshy, is not in the manner of the fifth century. Such bodies may be found in Italiote gems of the Hellenistic period, for instance, F., pl. 24, 41; pl. 27, 61; and pl. 23, 55. These three gems, and others of the class, have the same huge sunken navel as ours. The head of our centaur looks drier and more archaic than his body: this is also true of the Zeus and the giant on the Florence stone just mentioned, F., pl. 24, 41: and the haggard face, with its hollow cheeks, is characteristic of Italiote stones (F., pl. 18, 63 and 65; pl. 25, 3). The ends of the centaur's fingers are pelleted: and so are the ends of the giant's fingers on the Florence stone. The long bunch of hair at the nape of the centaur's neck recalls, though it does not reproduce, a fashion which is very frequently found on late Etruscan and Italiote gems (F. iii, pp. 195 and 223).

#### 92

B. B. 66, 291. R. 1054. Bu. O 5. Pl. 3. From Salonica according to Froehner. *Collection Tyszkiewicz*, pl. 24, 15; F., pl. 20, 70; *Tyszkiewicz Sale Catalogue*, pl. 27, number 291.

Sard, translucent. Chipped below and pared round below

and at the sides.

Uneven ground line. There was possibly a pattern, egg or

the like, in the exergue.

Silen and goat. The silen, bald, bearded, wreathed with ivy, kneels with head and body frontal, the body being slightly tilted towards the spectator's right, his left arm round the neck of the goat, his right raised. The beard covered with vertical strokes ending in pellets. The tail, which looks somewhat like a goat's tail, flourished. The goat is kneeling on its fore-legs and one of its hind-legs is seen below the silen's foot: head frontal: heavy eyelids: pellets for the hair on the forehead: ringed horns: the coat rendered by thin diagonal lines.

The action of the right hand is made obscure by the paring of the stone. Furtwängler supposes that the silen is adjusting his wreath, but as far as can be seen, the palm of the hand, with the thumb in front of it, is turned towards the spectator, which is not the gesture required. The position of the thumb makes it a little unlikely that he is going to pat or smack the

goat.

Froehner attributed the stone to a Greek artist of the fifth century, Furtwängler to an Italian of the third. The silen's tail if a goat's and not a horse's, is an argument, as Furtwängler observes, against an early date. Another is the position of the silen's legs: the left leg below the knee is invisible; the right is seen, somewhat foreshortened, in its whole length, and the foot is so far above the ground, on which the knees rest, that there is room for the goat's foot to appear between the toes and the ground line. This position, with the raised foot, is common on Italiote or very late Etruscan stones (F., pl. 21, 30, 31, and 49; pl. 23, 7: similar, but with the off leg in profile, F., pl. 23, 30, and pl. 64, 47: compare the Hellenistic stone F., pl. 34, 36). It does not seem to occur in the fifth century. There is something a little like it on a Greek relief which is ascribed by Lippold to the early years of the Peloponnesian war (Brunn-Bruckmann, number 646, 1); but there the raised foot of the falling warrior is not resting on space, as in our silen, but on a dead body. The whole figure may be compared with that of Orestes on the fourth century Paestan bell-krater formerly in the Deepdene collection and now in the British Museum (Millin, Peintures de vases grecs, ii, pl. 68: the drawing reversed): Orestes' legs are so drawn that he seems to be floating in front of the omphalos.

A third argument, of a more general kind, is the nature of the relief in the imprint, for it lacks those quiet passages, formed by planes parallel to the original surface, which characterize Greek and especially earlier Greek relief: the frontal head of the silen, and the glimpse of the goat's hind-quarters, are not

sufficient to rest the eye.

The rendering of the bodily forms recalls the centaur on number 91: and here, as there, the head is drier than the body.

Somewhat similar subjects are to be found on two Italiote stones (F., pl. 24, 29 and 30).

# **GREEK: HELLENISTIC**

93

G. P. 322, 5. Pl. 7, and, enlarged, Pl. 10. Found at Chalkis in Euboea. Bought from Lambros in 1908.

Convex sard.

Ground line. Cassandra at the image of Athena. She kneels with bowed head, a sprig of laurel in her right hand, her left hand clasping the lower part of the image, which stands with left leg advanced on a rectangular pedestal set upon a plinth: the goddess wears a crested Corinthian helmet, and a long chiton, somewhat full about the ankles: a spear across her right shoulder; a shield on her arm, emblazoned with a gorgoneion. Cassandra's hair, wreathed with laurel, falls loose on her shoulders. She is naked save for a thin garment covering her left leg and passing behind her left shoulder and over the upper part of her arm.

The same figure, with the same drapery, is frequently used in Roman times: not, however, for Cassandra, but for Nike sacrificing a bull. In clay, on decorative plaques (Von Rohden and Winnefeld, Architektonische römische Tonreliefs der Kaiserzeit, pp. 82-9, the first type, left-hand plaques; Walters, B. M. Catalogue of Terra-cottas, pl. 14, 1 and 2); in silver, on one of the jugs from Boscoreale in the Louvre (Monuments Piot, v, pl. 4: Reinach, Répertoire des reliefs, i, p. 85, 3); in gems, on four pastes in the British Museum (Pl. B, 9; Cecil Smith, J. H. S. vii, pl. E, 6 (=F., pl. 36, 29), 4, 5, and 7 (=F., pl. 36, 31: the composition reversed), and on stones published by Agostini (Gemme antiche figurate (1686), ii, pl. 32: rock-crystal: compared by him, on p. 18 of his text, with the clay reliefs mentioned above), by Gravelle (ii, 77; Reinach, Pierres gravées, pl. 80), by Furtwängler (pl. 30, 16), and in the Southesk Catalogue (pl. 5, Do, sard, and Dio, red jasper).

The oldest of these monuments date from the first century B.C. That the Nike and the Cassandra have a common origin cannot be doubted. The kneeling attitude with one arm drooping behind the body naturally occurs elsewhere; for instance, in a wounded Amazon on the Phigaleian frieze (slab 531) and in the Apollo on fourth-century coins of Sicyon (B. M. Coins of Peloponnesus, pl. 8, 4): what distinguishes the Nike and the Cassandra from all such figures is, first, the position and arrangement of the drapery, and secondly the idea embodied in the form, which is the motionless moment immediately following extreme physical effort.

The numerous Greco-Roman, in the absence of earlier, parallels seem to place our stone in that epoch. The great warmth, vigour, and expressiveness of the modelling might speak for an earlier time: John Marshall considers it Hellenistic of about 300 B.C.: and it is placed here, provisionally, among the Hellenistic stones. It must be observed, however, that the big London pastes are admittedly Greco-Roman: and the lost originals, of which they are, after all, poor copies, cannot, for execution, have fallen far short of the present stone. True, they would have lacked its depth and majesty of feeling: but let it be borne in mind, that the type may very likely have been created, not by a gem-engraver, but by an artist in some other material, say a painter. If the original figure was a Cassandra, the engraver who copies it as a Cassandra may be able to preserve the spirit of the original: the engraver who copies it for a Nike, or rather copies a work in which the original figure was adapted to make a Nike, will forfeit the original spirit.

The original figure may have been either a Cassandra, or a Nike, or something else. That it was not a Nike, may possibly be inferred from its greater impressiveness as used for Cassandra: moreover, it is perhaps rather more likely that an alien figure would be used for a Nike, considering the great demand for figures of Victory, than that a Nike would be used for a Cassandra. There are faint indications that the original figure was a Cassandra, but no reliance can be placed upon them. First, the upper part of the body, the drooping arm with the laurel sprig, the bent head and flowing hair, all reappear in the Cassandra or Pythia on the Medici krater (Hauser, Jahreshefte, xvi, p. 38). The resemblance is probably not accidental. Secondly, the head of Cassandra may be compared with a laurelled bust, very likely of the same, which occurs on several Greco-Roman gems (F., pl. 38, 40 and 41; pl. 40, 10 and 14): but these are draped and filleted.

See number 94.

94

G.P.359,2. Pl.7, and, enlarged, Pl. 10. Bought in Athens, 1915. Double convex. Glaucous beryl of the kind called aquamarine.

Ground line. Cassandra clasping the image of Athena: a replica of number 92. The spear is lacking, and the shield plain. The engraving is not so deep or so precise as in number 103, but no less masterly and of more delicate charm.

The beryl is not used by gem-engravers until Hellenistic times. Double convex beryls, of Greco-Roman date, are in the Wyndham Cook collection (F., pl. 40, 3) and in the Cabinet des Médailles (F., pl. 48, 8).

95

B. B. 67, 292. R. 1240. Bu. O 41. Pl. 6. From the Tyszkiewicz collection. Said by Froehner to have been found in Phoenicia; but Naoum Mitri of Rhodes told John Marshall in 1905 that he had sold it to Tyszkiewicz and had bought it from a peasant at Adana near Tarsos. Furtwängler, Jahrbuch, iv, pl. 2, 2; Froehner, Collection Tyszkiewicz, pl. 24, 17; F., pl. 32, 31; Tyszkiewicz Sale Catalogue, pl. 27, number 292; Fowler and Wheeler, Greek Archaeology, p. 399, fig. 327; Lamer, Griechische Kultur im Bilde, p. 61, fig. 7.

Chalcedony, strongly convex.

Portrait of a Ptolemaic queen as Isis: a female head with the beginning of the chiton and himation indicated. Egyptian coiffure: the hair tightly coiled, with corkscrew locks, short over the forehead, long behind the ear: diadem, and in front of it the symbol of Isis, the sun cradled in a pair of cow's horns. Full chin and neck: the pupil, and the outer line of the iris, indicated by faint prominences. To the left, downwards, the inscription AYK·MHAHS, perhaps the artist's name: no end-dots; the omikron reduced to a dot: a facsimile is given by Furtwängler (Jahrbuch, iv, p. 81).

The features are idealized, but less than appears from the reproduction, in which the projecting chin and the characteristic nose, being engraved on the curve of the stone, are seen in foreshortening. The queen represented must be either Berenike I or Arsinoe Philadelphos: Furtwängler considers Berenike I the

more likely (loc. cit., pp. 80-4).

First half of the third century.

96

B. B. 66, 285. R. 1234. Bu. O 34. Pl. 6. Formerly in the Ludovisi, later in the Tyszkiewicz collection. *Collection Tyszkiewicz*, pl. 24, 4; F., pl. 32, 36; *Tyszkiewicz Sale Catalogue*, pl. 27, number 285.

Hyacinth. The back convex.

Portrait of a Ptolemaic queen: female head with clothing shown on the neck. Chin and neck full, with the Venus rings noticeable. Prominent eyeball; the pupil, and the outer line of the iris, in relief. The irregular nose is of the same type as in number 95. Earring, consisting of a ring with a wire hanging from it strung with three drops, a larger between two smaller. Metal stephane with a diadem passing round the lower part of it. The hair elaborately dressed, apparently by the following process. The hair is parted from ear to ear so as to form a fringe: the fringe is turned back from the brow in even curls, the ends of which are covered with the stephane: the rest of the hair is taken back from the parting, a small coil formed at the back of the head, and the hair which remains brought forward again in the curls which are seen to the right of the coil. In contrast with this formality, the hair on the nape of the neck is lightly combed forward with a natural wave. A lady on a gold ring in Petrograd (F., pl. 32, 33) has dressed her hair on the same principle, but she lacks the formal Ptolemaic curls over the brow.

The type of stephane and diadem, not to speak of the hairdress, is that worn by Ptolemaic queens on their coins. The features resemble those of Arsinoe Philadelphos, and Froehner is no doubt right in identifying the portrait as hers. The head is that of a woman who is still young, and the stone may therefore be attributed to the earlier part of the third century.

## 97

B. B. 66, 289. R. 1238. Pl. 6. Said by Froehner to have been found at Suleimanieh in Turkish Kurdistan. From the Tyszkiewicz collection. Collection Tyszkiewicz, pl. 24, 12; F., pl. 31, 24, and, drawn, iii, p. 169; Tyszkiewicz Sale Catalogue, pl. 27, number 289.

Syriam garnet. The back convex.

Portrait of a middle-aged man: head and shoulders of a bearded man wearing a fez-like cap and a chlamys fastened with a bow. The lips parted, the eye salient, the pupil and the outer line of the iris marked by slight prominences.

With the fez, Furtwängler compares the headgear of certain barbarians on the columns of Trajan and of Marcus Aurelius. The headgear of the Trajanic figures, supposed by Cichorius to

be Iazyges (*Die Trajanssäule*, iii, pp. 143 and 151, and pl. 73), seems to differ from ours in having a lower rim, and is probably a helmet, whereas ours is a cap of felt or the like: the Aurelian headgear, which is taken to be Scythian (Petersen, *Die Marcus-*

säule, pl. 56, 2), is flattened at the top.

A rougher but forcible replica of our head, in pale brownish chalcedony, was formerly in the Ionides collection and is now in the British Museum (Pl. B, 10; Burlington Catalogue, pl. 112, M 136): it is said to have been brought to England from Constantinople about sixty years ago. A. S. Murray considered ours to be a modern copy of the Ionides stone, which he wrongly described as a scaraboid (Quarterly Review, 1901, p. 434); but ours is in good Hellenistic style.

Third century.

98

B. B. 110, 3. R. 1612. Bu. O 8. Pl. 6. Bought in 1899 from W. T. Ready, who reported it to have been found on the Euphrates. Furtwängler says that it came from the East, and was at one time in the possession of Mr. Lau. F., pl. 31, 23, and, drawn, ii, p. 154.

Clear sard.

Portrait of a man in Eastern costume: head of a clean-shaven elderly man, wearing a club-shaped torc and an Oriental head-dress: the collar of his garment indicated, the eyeball prominent, the forehead wrinkled. There is a circle in front of the ear, as if some one had begun to bore a hole.

The pupil is not marked: herein Furtwängler's drawing is

misleading.

The head-dress is a conical cap of felt or leather, running down to a peak on the forehead, and furnished with three flaps. The central flap hangs down at the back of the neck and is seen in profile. The other two are folded together in front of the head. These tapering side-flaps, if they were not gathered up, would not fall smoothly in a vertical direction, as in many Eastern head-dresses, but, to remain smooth, would have to be brought diagonally forward towards the chin, where they might be tied together.

Experiment, kindly conducted by a friend, proves that the head-dress is accurately rendered. Its shape before, during,





Fig. 1



Fig. 2



Fig. 3

and after manipulation is shown in the accompanying figures. The directions for use are as follows:

(1) Place the object on the head, take the flaps and fold them back above the ears with the insides outwards, at the same time folding down the upper edges of the flaps.

(2) Cross the flaps above the forehead peak, concealing the

left-hand flap under the edging of the right-hand one.

(3) Bring the left-hand flap out again over the edging and

tuck it in under the flap, leaving the tip curling out.

The head-dress has been compared by Furtwängler with that worn by Samos and other kings of Commagene on their coins (Imhoof-Blumer, Hellenistische Porträtköpfe, pl. 6, 9, and 10; Macdonald, Catalogue of Greek Coins in the Hunterian Collection, iii, pl. 70, 20–2): but the resemblance, so far as can be made out from the poor specimens preserved, is limited to the conical caul, the flaps being differently shaped and differently disposed. A king of Persis gathers his side-flaps up over his forehead (Imhoof-Blumer, Hellenistische Porträtköpfe, pl. 7, 27; Allotte de la Fuÿe, Corolla Numismatica, pl. 3, 3; Head, Historia Numorum, p. 824), but his whole head-dress is quite different from ours both in shape and in arrangement.

It can easily be understood, that the loose flaps of the various Eastern head-dresses were sometimes found troublesome, and were fastened either under the chin, or in front of the head, or behind it as in the archer from the western pediment of the temple at Aegina (Furtwängler, Aigina, pp. 210–11), or into an encircling band as on a sixth-century Attic cup (Pottier, Album

des vases du Louvre, pl. 73, F 126): see also number 99.

# 99

G. P. 349, 4. Pl. 6. Bought from W. T. Ready in 1913. Mottled sard. Roughly rectangular. The sides of the stone slightly convex. A very rare shape.

Portrait of an Eastern ruler: head of a clean-shaven old man

wearing a chlamys and an Oriental head-dress.

The head-dress bears a certain resemblance to that on number 98, but it is worn farther back on the head, so that the fringe of hair on the temple is exposed; the peak in front is longer; and the side-flaps are differently arranged. The horizontal line on

the forehead below the hair is a fillet or diadem tied round the head before the head-gear is put on, and not afterwards, as in the coin of Persis referred to on number 98 (Imhoof-Blumer, Hellenistische Porträtköpfe, pl. 7, 27) or on Armenian and Parthian coins. The right-hand side-flap is lifted up and slung over to the left side of the head: the left-hand side-flap is similarly slung over to the right side of the head, where it appears in our stone as a broad sock-shaped projection above the ear.

Save for the flaps, the hood-like head-dress is somewhat analogous to that worn on coins attributed to Persis (Corolla

Numismatica, pl. 3, numbers 4, 6, &c.).

#### 100

B. B. 67, 296. Bu. O 2. Pl. 6. Formerly in the Ludovisi, later in the Tyszkiewicz collection (sale catalogue, number 296). Collection Tyszkiewicz, pl. 24, 5; F., pl. 33, 24.

Slightly convex. Clear sard. The crown of the head missing

and restored in gold.

Portrait, perhaps of a Roman: a clean-shaven man with short hair and wrinkled forehead: the clothing shown at the back of the neck. The eyebrow rendered by short diagonal lines, the outer line of the iris by a raised arc; the pupil incised. Misshapen ear.

A paste after this stone, in the Stosch collection (fourth class, number 323), was wrongly described by Winckelmann as antique

(Description des pierres gravées, p. 450).

#### IOI

B. B. 66, 288. R. 1237. Bu. O 42. Pl. 6. From the Ludovisi and Tyszkiewicz collections. Collection Tyszkiewicz, pl. 24, 10; F., pl. 33, 16, and, enlarged, pl. 51, 25; Tyszkiewicz Sale Catalogue, pl. 27, number 288; Hekler, Greek and Roman Portraits, p. xviii, fig. 7; Delbrueck, Antike Porträts, pl. 59, 2 (misprinted 1); Lamer, Griechische Kultur im Bilde, p. 61, fig. 6.

Black jasper.

Portrait head of an elderly Roman. The pupil and the outline of the iris in relief: thick eyebrow rendered by irregular, roughly





Fig. 4



Fig. 5, No. 134



Fig. 6, No. 135

vertical strokes: wrinkled forehead: misshapen ear: the hair

somewhat woolly.

This is one of those gems which Furtwängler separates from the mass of Roman portrait gems and assigns to the Hellenistic period, and it is true that such heads as ours and the even finer one on the Carlisle chalcedony in the British Museum (F., pl. 33, 14, and pl. 51, 24) are different from and superior to even such excellent Greco-Roman heads as that on number 116 in the present collection. The superiority is not due to the stronger personality of the men represented, but to a combination of varied realism in the treatment of substance with the strength and understanding which charge the forms with compact and characteristic life.

The group of gems in question is studied by Furtwängler on F., pl. 33, 9, 14, 15, and 16; see also iii, p. 165, and Jahrbuch, iii, pp. 108-9.

#### 102

G. P. 340, 4. Bu. L 90. Pl. 7. Found in a tomb at Eretria (Ephemeris Archaiologike, 1899, p. 228). Formerly in the Evans collection. F., pl. 66, 4. At present on loan in the museum at Boston, where the other objects found in the tomb are preserved (Museum of Fine Arts, Boston, Annual Report, 1914, p. 96). The accompanying picture shows one of the clay figures from the tomb.

Convex garnet in a golden ring. Inside the hoop, XAIPE. The same inscription on a scaraboid and two gold rings in the British Museum (Pl. A, 9; Imhoof-Blumer and Keller, Tier- und Pflanzenbilder, pl. 25, 40; B. M. Finger Rings, numbers 85 and 102):  $\chi a \hat{i} \rho \epsilon \kappa a \hat{i} \sigma \hat{v}$  on a sard scarab in the same collection (F., pl. 9, 34). The ring is of the general type shown in Marshall, B. M. Finger Rings, p. xlii, C xxvii.

Ground line. Aphrodite arming. The goddess stoops with both arms bent and the left one advanced and passes her left arm through the grip of the shield, holding the rim with her right hand. The spear rests against her left shoulder. She is naked from the thighs upwards, and her legs are nonchalantly draped: she has picked up her himation, placed an end against her flank, wound the garment round her legs from right to left,

and passed the remainder in front of her breast and over her left shoulder. The hair is parted in the middle and twisted up into a knot behind. The artist's signature, in two lines, ΓΕΛΩΝ ΕΠΟΕΙ, Γέλων ἐπόει: see F., ii, p. 305.

An unsigned replica on a convex sard from Amrit in the De Clercq collection (Pl. B, 7; De Ridder, Collection De Clercq,

vii, pl. 20, number 2841).

The tomb from which the stone came is dated, on the evidence of the other finds, to the end of the third century (Kourouniotis,

Eph. Arch., 1899, pp. 233-4).

For the style of the stone, Rossbach (in Pauly-Wissowa, s.v. Gelon (8)) compares a sard, set in a gold ring, from a tomb belonging to the cemetery of the ancient Trichonion in Aetolia (Eph. Arch., 1906, pl. 4, 47). The design on the sard is a female figure, half naked, and seen in three-quarter view from behind, leaning on a column and holding a comic mask in her hand; across her shoulder, a streamered thyrsus, corresponding to the spear on our stone: Thalia according to Soteriades. Soteriades dates the Aetolian tomb to the beginning of the second century (loc. cit., p. 74).

Another kindred design on a convex garnet in Petrograd (F., pl. 34, 17): a maenad with oinochoe and phiale, a thyrsus against her shoulder. Also akin, Aphrodite with the eagle on a sard in the Chatsworth collection (F., pl. 38, 9), and Nike writing upon a shield on a paste in the British Museum (7. H. S. vii, pl. E 8).

About 200 B.C.

# 103

R. 595. Bu. O 27. Pl. 5. Bought from W. T. Ready in 1897. From Athens according to the sender. F., pl. 61, 53.

Bluish chalcedony flecked with white. The shape approaches the rectangular, but all four sides are curved and the corners rounded off.

Border of diagonal strokes. A sea-pantheress attacking a polypus, which she grasps with mouth and paws. The polypus has three plain and two pelleted tentacles. The monster shows flippers at the right elbow and on the left shoulder.

Stones of this shape are not found before the Hellenistic age (F., pl. 22, 67; pl. 20, 71; pl. 25, 4; pl. 65, 39). The shape

is derived, in the long run, from the scarab and scaraboid. The border of diagonal strokes, a degenerate variant of the hatched border, appears on Italiote stones of the Hellenistic period (F., pl. 23, 5, and pl. 20, 63) and on a very late scarab, of Hellenistic date, in the British Museum (F., pl. 65, 10): not, it seems, later.

## 104

G. P. 322, 4. Pl. 7. Brought from Athens, 1908, and said by the dealer, a trustworthy man, to be from Lesbos. A replica of, if not identical with, the stone published by Pietro Vivenzio (Gemme antiche per la più parte inedite, Rome, 1809, pl. 17), and after Vivenzio in a small anonymous work of which there is a copy in the library of Sir Arthur Evans (Raccolta di trenta scelte incisioni in pietre dure appartenenti alcune al Real Museo Borbonico ed altre a private collezioni, Naples, 1845, pl. 17). Vivenzio describes the stone as a jasper in his plate, and as an agate in his text.

Moss agate.

Ground line. Marsyas and Olympos. Marsyas seated on a rock: in front of him Olympos, a slender boy with short hair, holding a flute in either hand. Marsyas lays his left hand on Olympos' shoulder and extends his right arm as if to bring him nearer. His hair and beard are rough and his features rugged: a beast's skin on his lap and over his left arm. Olympos looks at Marsyas for guidance: a cloak over his right shoulder.

The representation of the same subject on a late Italiote stone (F., pl. 30, 36) must go back to the same original. Compare also the Pompeian painting, Herrmann, Denkmäler der Malerei des Altertums, pl. 87. Marsyas teaching Olympos the flute is a pendant to the Chiron teaching Achilles the lyre, which is known from a Herculanean painting (Herrmann, pl. 82) and from engraved gems (F., pl. 24, 65; pl. 43, 16; pl. 43, 10). Perhaps late Hellenistic.

## **GRECO-ROMAN**

105

B. B. 66, 290. R. 1239. Bu. O 36. Pl. 7, and, enlarged, Pl. 10. From Hadrumetum in Tunis according to Froehner. Formerly in the Tyszkiewicz collection. *Collection Tyszkiewicz*, pl. 24, 13; F., pl. 50, 19, and, drawn, ii, p. 242; Bulle, *Neue Jahrbücher*, 1900, pl. 2, 53; *Tyszkiewicz Sale Catalogue*, pl. 27, number 290; Reinach, *Apollo*, p. 81, fig. 117; Stuart Jones, *Companion to Roman History*, p. 426, fig. 61, after Furtwängler's drawing.

Slightly convex. Sard, now milky in parts.

Augustus, as Neptune, mounting a chariot drawn by four sea-horses over a troubled sea: he is escorted by a young Triton and a dolphin. Above, the inscription nonly amban, giving the owner's name, Popilius Albanus.

The letters are end-dotted, the omikron rather large, the nu slanting, the beta thin with the upper loop smaller than the lower.

The chariot, conceived as emerging from the waves, is invisible save for a glimpse of the felloe, of one spoke, and of the upper edge of the car. The sea-horses have distended nostrils and tossing manes: they are finned at the elbow, and a girdle of weed, as commonly in sea-creatures, masks the commencement of the spinous tail. The Triton, seen to below the nipples, is shown to be swimming by his raised right shoulder: he seems to have big bestial ears like the marble Triton in the Vatican (Bulle, *Der schöne Mensch*, pl. 219). The driver is naked save for a wrap which passes over the right shoulder and behind the back and is wound round the left arm: the left leg frontal; the hair short; a trident in the left hand.

In a general way, the representation may be compared with the Poseidon driving a pair of sea-horses on a paste in Berlin (F., pl. 37, 3), of which there is a smaller replica in the British Museum (B. M. Catalogue, pl. G, number 614). On the pastes, the chariot is not indicated at all: as in our gem, the rigid geometrical lines of the chariot would have marred the furia of the representation.

One of the few chariot-pieces comparable with ours for its

fiery vigour is the Nike flying with a team of horses which is preserved in several examples, on a cameo in Petrograd signed by Rufus (F., pl. 57, 6) and on several intaglios (for instance, F., pl. 42, 5), and which was conjectured by Panofka, not without plausibility, to be the 'Victoria quadrigam in sublime rapiens' of Nikomachos (see Furtwängler, Jahrbuch, iv, pp. 60-2).

The short hair and beardless face of the driver, perhaps also

The short hair and beardless face of the driver, perhaps also his youthful body, show that he is not Poseidon. The features are portrait-like and therefore mortal. At the period to which the gem belongs, no one but Augustus could have been figured as Poseidon: and the features, in fact, bear an unmistakeable

resemblance to those of Augustus.

The gem most likely belongs to approximately the same period as those Augustan coins which display naval emblems in honour

of the battle of Actium: that is, between 31 and 27 B.C.

Another monument of the same kind, though of vastly inferior quality, is the cameo in Vienna published by Rossbach (Aus der Anomia, pl. 3), on which Augustus, or his genius (F., iii, p. 318), stands in a chariot drawn by four tritons.

#### 106

R. 823. Bu. O 25. Pl. 6. Bought from Rhousopoulos, who said it came from Asia Minor. F., pl. 61, 68; Bulle, Neue Jahrbücher, 1900, pl. 2, 51.

Sard.

Head of a boy satyr smiling. A skin tied round the shoulders. Tousled hair, half concealing the bestial ear: the lower lashes rendered by short strokes pointing vertically downwards: the iris prominent, in relief: bushy eyebrows represented by pellets

disposed on a line.

The character is more pronounced than in the somewhat similar head on Hyllos' cameo in Berlin (F., pl. 52, 2), and ours consequently recalls more vividly the bronze head of a satyr in Munich (Wolters, *Illustrierter Katalog der K. Glyptothek* (1912), pl. 70): compare also the young satyr who offers a hare to a dog on a relief in the Louvre (Schreiber, *Hellenistische Reliefbilder*, pl. 22).

#### 107

B. B. 67. R. 1244. Bu. O 431. Pl. 7. From the Tyszkiewicz collection (sale catalogue, number 300). F., pl. 61, 71.

Clear sard.

Ground line, swelling towards the middle. Theseus examining his father's sword. On the ground the shield: the device

a gorgoneion framed in petals.

This design was extremely popular in Imperial times: further examples on a sard in the Cabinet des Médailles (Collection Pauvert de la Chapelle, pl. 7, 100; F., pl. 38, 18) and on a lost stone (F., pl. 43, 31); on a yellow paste in the British Museum; on a red jasper in Berlin (Furtwängler, Beschreibung, pl. 60, number 8481); on the nicolo, number 123 in this collection; on another, set in a third-century ring, in the British Museum (Henkel, Römische Fingerringe, p. 114, fig. 65); on an onyx set in a silver ring found at Treves (Bonner Jahrbücher, vii, pll. 1-2, figs. 4 and 5; Henkel, p. 114, fig. 66); on a paste, set in a thirdcentury bronze ring, found at Augsburg, in Munich (ibid., pl. 78, 348, and pl. 48, number 1254); and on an onyx, set in a gold ring of about the same period, published by Abraham Gorlaeus in his Dactyliotheca (i, number 96). Others, the antiquity of which cannot be vouched for from the illustrations, are figured by Agostini (Gemme antiche figurate, ii, pl. 100), by King (Antique Gems and Rings (1872), ii, pl. 43, 5), by Gori (ii, pl. 17, 1; Reinach, Pierres gravées, pl. 51), and in the description of the Orleans collection (ii, 52; Reinach, op. cit., pl. 130). It is easy to understand the popularity of the design: a ring with Theseus examining his sword would make an excellent present for a young man beginning his military career.

The original was no doubt a work in the style of the fifth

century, possibly in the manner of Polykleitos.

The petal frame on the shield recurs on the Berlin jasper and in the stone published by Gorlaeus. A shield like ours, emblazoned with a gorgoneion surrounded by petals, on an Italiote sard (F., pl. 22, 48). The petals also on a stone reproduced by Agostini (ii, pl. 46) with a Venus Victrix of the same type as F., pl. 44, 78, on a late bronze relief with the same subject in Berlin (Jahrbuch, ii, p. 203), and on a marble relief in Turin published by Rizzo (Römische Mitteilungen, xxv, pl. 8).

The figure of Theseus is grouped with another on a stone

published by Furtwängler (pl. 42, 7).

#### то8

G. P. 348, 4. Pl. 7. Bought in Rome (?), 1912-13. Golden sard.

Ground line, swelling towards the feet. A comic actor, masked, in the part of an old gentleman, holding a long knotted stick and stroking his beard. The left leg frontal. The hair hatched with the lower edge pelleted: the beard in rows of

pellets. Sleeved under-garment, himation. Paunch.

A favourite design in Greco-Roman gems. Two examples are figured, and others mentioned, by Furtwängler (pl. 41, 48, and 50, and ii, p. 198). Another was recently in the Paris market (Gemmes et médailles antiques, 24-26 mars 1902, pl. 2, 3; Collection Jules Sambon, pl. 24, 570). A similar design on a stone in Munich (Münchener Jahrbuch, iv, pl. 2, 24).

# 109

G. P. 348, 1. Pl. 7. Bought in Naples, 1912–13. Slightly convex. Sard.

Ground line, swelling towards the hither foot. An archaic Apollo: he holds bow and arrows in one hand and in the other the fore-foot of a fawn which stands on its hind-legs in front of him. The head of the god is slightly bent. The body archaic: high chest, bulging calf, long feet, tight knees. The skull high. The long hair is hatched, and edged with pellets behind as well as before: two series of pellets represent loose locks falling on the breast: the fillet indicated.

The same design on a number of Greco-Roman stones (F., pl. 40, 1 and 2; Furtwängler, Beschreibung, pl. 21, 2308; Millin, Pierres gravées, pl. 6 = Reinach, Pierres gravées, pl. 120; B. M. Catalogue, pl. G, number 720): facing left instead of right, on a chalcedony in the possession of Sir Edward Sieveking, considered by Cecil Smith, who published it, to be a cut scaraboid (Proceedings of the Royal Society of Antiquaries, 1887, plate at p. 253, 1). The archaic statue reproduced has been supposed to be the bronze Apollo Philesios by Kanachos at Miletus, but it is presumably that statue which is reproduced on Milesian coins (B. M. Coins of Ionia, pl. 22, 9 and 10; Gardner, Types, pl. 15, 15 and 16), and in these the fawn is not standing, as in our gem,

but sitting on Apollo's hand. Cecil Smith (loc. cit., pp. 251-5) conjectures that the original fawn was lost during the sojourn of the statue at Susa, and that the statue was restored, on its return, after the similar Apollo of Kanachos at Thebes, the gems reproducing its first, the coins its second state.

The stone which most resembles ours is F., pl. 40, 2. The British Museum sard is a poor, watery work of later Imperial

date.

#### IIO

G. P. 256, 7. Bu. O 73. Pl. 7. An imprint in Cades, sixth century, 41; described in *Bullettino*, 1839, p. 110, as 'replica accuratissima dalla pietra posseduta dal duca di Blacas col nome di heioy. Corniola già degli eredi dell' avvocato Isola in Roma ora nella collezione Vannuttelli'. The Blacas stone is now in the British Museum (number 1394; Pl. B, 13; Inghirami, *Galleria Omerica*, i, 107; Choiseul-Gouffier, *Voyage pittoresque*, ii, p. 177; Tischbein, *Homer nach Antiken*, iii, 3; Overbeck, *Galerie heroischer Bildwerke*, pl. 16, 19). The inscription heioy is false, and Furtwängler condemns the stone as well (*Jahrbuch*, iv, p. 71). If the Blacas stone is modern, so is ours, for the technique is exactly the same: but both stones appear to be ancient.

Slightly convex. Translucent sard.

Irregular ground line. The death of Dolon. Dolon, beardless, has sunk at the feet of Odysseus, and is begging for his life: with his right hand he clasps the hero's knee, and he stretches his left upwards as if towards the beard. Odysseus stands looking down at him, his sword, sheathed, held at his side in his left hand, for it is not he who is to slay Dolon, and his right hand raised with a gesture of detachment. At the other side of Dolon stands the youthful Diomede, his left leg planted on Dolon's thigh, his left hand at the Trojan's head, as if grasping it, and his naked sword ready in his right. Dolon wears a sleeved undergarment with a short chiton over it, a wolfskin cap, and a skin tied round his shoulders. Odysseus wears pilos and chlamys: Diomede has a cloak fastened at the neck, and his scabbard is suspended from a baldrick slung round his shoulder. The hair of Diomede is short and unkempt: the hair of Odysseus escapes

from under the pilos above the ear; his beard is pelleted; and

the pellet is used freely throughout the engraving.

The same subject, differently treated, on a stone published in Annali, 1875, pl. Q, 4: whether antique or modern is uncertain from the drawing. The two figures on an Italiote paste in Berlin (F., pl. 33, 32) have been interpreted as Odysseus and Dolon. A brown sard in the collection of Mr. Henry Oppenheimer is a modern variant of the Heiou type: Odysseus holds Dolon's head and grasps his sword in his right hand: Diomede is wearing chlamys and helmet, and raises his sword point downwards. A variant on a sard from Cadiz in the British Museum.

#### III

G. P. 343, 5. Pl. 7. From the Boulton collection (sale catalogue, number 28, 1). An imprint in the Impronte dell' Instituto. Sard. Fragment.

A centaur carrying a maenad on his back. His left arm passes behind the maenad, supporting her: in his right hand he holds a thyrsus, head downwards, the foot of which is lanceolate and the shaft tied with a streamer near the head which is now broken away. His hair is ruffled, his beard formally neat. The maenad's head is thrown back: her arm follows it, with the hand half open as if holding some object, now missing, between her fingers. The parted lips and the wrinkle in the forehead show her excitement. She wears a chiton with cross-bands on the breast: for this fashion, see Stephani, Compte rendu, 1860, pp. 80-2, and 1870-1, pl. 2, 4, and p. 53.

A kindred theme on two pastes, perhaps from a single stone, in Boston (F., pl. 63, 45) and in Berlin (Furtwängler, Beschreibung, pl. 31, number 4084). A centaur has overtaken a maenad and caught her up on to his back: he holds a streamered thyrsus, the maenad a tympanum: our maenad may have held the same.

Another representation from the same cycle is preserved in a Pompeian painting and on an engraved stone: the maenad has leapt on to the centaur's back (Herrmann, Denkmäler der Malerei des Altertums, pl. 93 and pp. 139-40).

#### 112

G. P. 322. Pl. 7.

Paste, amethystine. Perhaps an ancient paste re-polished.

Ground line, partly broken away. A maenad, seen in three-quarter view from behind, rushing with head thrown back, in her right hand a thyrsus with a streamer round it, in her left a kantharos, and something else which is indistinct. Her chiton is fastened on the right shoulder and leaves her left shoulder free: the left-hand portion of the chiton is blown aside, so that her back, left leg, and right thigh are exposed, and between her legs, so that the lower part of the right leg is covered. A long wrap passes over her left arm, in front of the body, and over her right arm.

The same figure is found in bacchic reliefs on sarcophagi (Reinach, *Répertoire des reliefs*, iii, p. 359, 2; iii, p. 326, 5; ii, p. 61, 3). The motive of the drapery blown between the legs recurs in another type of maenad, that used by the new-Attic sculptor Salpion on his marble krater in Naples (Hauser, *Neu-*

attische Reliefs, pl. 2, number 24).

A somewhat similar figure on a paste in Berlin (F., pl. 36, 37), and on another in the British Museum.

# 113

B. B. 66, 287. R. 1236. Bu. O 9. Pl. 6. From Chalcedon according to Froehner. Formerly in the Tyszkiewicz collection. Froehner, *Collection Tyszkiewicz*, pl. 24, 9; *Tyszkiewicz Sale Catalogue*, pl. 27, number 287.

Sard. Very deeply cut.

Head of Io, almost frontal. The hair filleted, parted in the middle, turned back from the face and falling loose behind. Necklace rendered by two rows of pellets joined by strokes and terminated below by lines tapering downwards. The nose somewhat aquiline. The lips parted: pathetic expression.

A similar head on a sard signed by Dioskourides (F., pl. 49, 9, and pl. 51, 17) is identifiable as Io from the little horns in the hair. Furtwängler condemns the present stone as a copy of the other (ii, p. 234), first, because the workmanship is coarse and bad, secondly, because the horns are absent: the engraver

did not understand them in his original, and therefore omitted

them in his copy.

With regard to the first argument, most critics will consider the engraving good, not bad: the head has not the restrained perfection of Dioskourides' work, but the execution is masterly and the expression just. With regard to the second: the horns are clearly indicated, by bosses half-way between the parting and the sides of the head.

Ancient pastes of somewhat similar types in Berlin (Furtwängler, Beschreibung, pl. 35, numbers 4928-32): another in

Mr. Warren's possession.

#### 114

B. B. 105, 9. R. 1561. Bu. O 11. Pl. 5, and, enlarged, Pl. 10. Formerly in the Chesterfield, Bessborough, and Marlborough collections (Story-Maskelyne, The Marlborough Gems, p. 46, number 270). Natter, Traité de la méthode antique de graver en pierres fines (1754), pl. 16; Natter, Catalogue des pierres gravées tant en relief qu'en creux, de Mylord Comte de Bessborough (1761), pl. 16, number 40; Worlidge (A select Collection of Drawings from curious antique Gems; most of them in the possession of the Nobility and Gentry of this Kingdom; etched after the manner of Rembrandt. By T. Worlidge, Ptr. London, 1768), number 1; Bracci, Commentaria de antiquis scalptoribus (1784), pl. 45; Gemmarum antiquarum Delectus ex praestantioribus descriptus quae in dactyliothecis ducis Marlburiensis conservantur (1845), ii, pl. 34 = Reinach, Pierres gravées, pl. 115; F., pl. 50, 4. See also Furtwängler, Jahrbuch, iv, p. 57.

Strongly convex. Syriam garnet.

Sirius. The head and shoulders of a dog, frontal, with rays round the head. The mouth open; showing the tongue, the teeth complete, and the corrugated palate. Coarse hair in striated tufts. Shaggy pointed ears. The body smooth, save for light tufts on the breast. Round the body, a collar, inscribed with the artist's signature, raioc enoist, with small end-dots: the cross-bar of the alpha was not noticed by Furtwängler. The deep red stone has a livid bluish hue where it is hollowed thin, which makes the dog's muzzle look pale and moist.

A somewhat similar design on a chalcedony, said to be ancient, in Berlin (Imhoof-Blumer and Keller, Tier- und Pflanzenbilder, pl. 14, 3; Furtwängler, Beschreibung, pl. 52, 7043). Natter copied our stone, which he greatly admired, and his copy is believed to be in Petrograd (see Story-Maskelyne, The Marlborough Gems, p. 46). A copy by Lorenzo Masini, of rock-crystal, is in Berlin (9243: Jahrbuch, iii, pl. 3, 27). A modern sard in the British Museum (Dalton, Catalogue of the Engraved Gems in the British Museum: Post-classical Period, pl. 30, 774) is not

a copy, but a free imitation.

The dog seems to belong to the class called by Keller 'pseudo-Molossian' (fahreshefte, viii, pp. 258-69; Die antike Tierwelt, i, pp. 112-13), reproduced by a grave-statue in the Ceramicus at Athens (Collignon, Sculpture grecque, ii, p. 383, and Statues funéraires dans l'art grec, p. 241), by statues in the Uffizi (Jahreshefte, viii, p. 267: see Amelung, Führer durch die Antiken in Florenz, p. 15), and in a bronze head at Geneva (Deonna, Catalogue des bronzes figurés antiques, Ville de Genève, pl. 3, number 108); compare also the gem F., pl. 45, 20. The same type is used for Cerberus in a stone in the Wyndham Cook collection (Wyndham Cook Catalogue, pl. 8, number 199): and in a small bronze figure of Cerberus belonging to Mr. Henry Oppenheimer, the main head is pseudo-Molossian, while the two lateral heads are of long-nosed greyhound-like form.

The treatment of the hair recalls the Hyperechios stone,

number 115.

# 115

B. B. 15. R. 845. Bu. O 40. Pl. 5. Said to have been found in Macedonia, in a porus sarcophagus. Bought from Rhousopoulos in 1897. Rhousopoulos had known it for twenty years and before it was mounted; thought it genuine, and had made many efforts to buy it. The owner, who lived at Salonica, took it 'to Europe', where it was condemned by Chabouillet (the same who condemned the flying heron by Dexamenos) and by A. S. Murray. In 1889, Furtwängler saw no sufficient reason for doubting the genuineness of engraving or inscription, but was inclined to think that the inscription was not the artist's signature, but the owner's name added subsequently (Jahrbuch, iv, p. 647).

In 1900 he said that the engraving and the inscription, 'which doubtless designated the artist', seemed to be genuine (F., ii, p. 241). Since 1900 a second stone with the name of Hyperechios has appeared, but has not been published, and is known to the writer from Sieveking's description only (in Pauly-Wissowa, s.v.

Hyperechios (5)):

'The Berlin Antiquarium has recently acquired another work by Hyperechios, a red jasper, found in Egypt, with the head and shoulders of a bearded philosopher wrapped in a cloak. Both stones, which unmistakably exhibit the same style, are distinguished by remarkably deep cutting. The character of the inscription, the name, and the use of yellow jasper, point to a late period, perhaps the Antonine epoch.'

Furtwängler, Jahrbuch, iii, pl. 11, 24; F., pl. 50, 6, and

pl. 63, 34.

Yellow jasper.

Ground line, swelling to provide pedestals for the hither paws. A lion walking, wheeling round, with the head, which is undercut, nearly frontal. In the exergue, YNEPEXIOY, the letters end-dotted. The mouth open; the claws showing; the end of the tail raised. The off fore-paw presses less heavily on the ground than the others. Massive forms, thick legs and big paws; beetling brow and scowling expression; the ribs faintly indicated; a fringe of hair along the belly and in the hinder crutch, and a tuft on the elbow; the mane freely rendered in coarse striated tufts; outlying tufts, longer and finer, on the body near the mane.

A similar lion on another Greco-Roman stone (F., pl. 45, 25). Both animals are of the same type as the Barberini lion (Brunn-Bruckmann, number 645), the later type based, unlike the earlier (see the stone number 65), on study of the animal itself. Pliny states that Pasiteles made studies from living captive lions, no doubt circus animals. The subject of antique representations of the lion has been attended to by Schröder (text to Brunn-Bruckmann, numbers 641-5).

The outlying hair seems not to occur before the Greco-Roman

period.

#### 116

G. P. 341, 1. Bu. L 148. Pl. 6. Said to be from Athens. Formerly in the Evans collection. Bought in 1911.

Translucent sard. The lower right-hand part missing.

A portrait head of an elderly Roman wearing corslet and cloak. Close-cropped hair rendered by very short strokes. Crow's feet. The ear small. The brow drawn down, the lips tightly pressed together and the lower one protruding. Between the neck and the curving fold of the cloak behind it, a straight line, running

diagonally, with a short transverse line at the top.

The portrait head on a lost sardonyx (F., pl. 48, 1) bears a certain resemblance to ours: in the field behind the head a nail point downwards. This suggests that the object on our gem between neck and cloak is the upper part of a nail. A third portrait, with similar features, though the shape of the head is different, is engraved on a sard in the British Museum (Pl. B, 11; F., pl. 47, 64), a replica of which, in chalcedony, was once in the Montigny collection (Pl. B, 12; Collection de M. de Montigny, Pierres gravées, vente 23-25 mai 1887, pl. 3, 325): in these, as in our stone, only the upper part of the nail is seen, the point being concealed behind the neck. The Stosch collection contained a modern paste (fourth class, number 175), which Winckelmann described as a copy of a gem in the collection of Dr. Gavi at Florence (Description des pierres gravées, ii, p. 435): the Gavi stone seems to have been the one which is now in the British Museum. Winckelmann calls the head a portrait of Atilius Regulus, adding a reference to the *Imagines* of Fulvius Ursinus, number 38. There is no Regulus, however, in the 1570 edition of Fulvius Ursinus: the figure on page 38—there is no other numbering--is taken from a Mytilenean coin with the supposed head of Sappho. But in the Illustrium Imagines ex antiquis marmoribus nomismatibus et gemmis expressae quae extant Romae maior pars apud Fulvium Ursinum, published by Plantin for Theodorus Gallaeus in 1598, number 38 is a head called 'M. Atilius Regulus, apud Fulvium Ursinum in nomismate argenteo', which is presumably what Winckelmann meant, although it bears no resemblance whatever to the Gavi stone and lacks the identifying nail.

The London and Montigny stones are not above suspicion, but the sardonyx and our sard are beyond doubt genuine. The

nail is hard to explain. It may be a gentile emblem such as are found on Roman coins: conceivably, but by no means probably, that of the Atilian gens.

That the four stones, or the two, represent the same person cannot be said with assurance. That the great Regulus is figured on any or all of them is most improbable: the heads do not look

like that of a long-dead hero.

It remains to account for Gallaeus's identification of the published head. Mr. Hill writes: 'I have no doubt that one of the coins of L. Livineius Regulus is responsible for the engraving in Gallaeus. See Grueber, B. M. Roman Republican Coins, iii, pl. 57, 12–17. Some of these (15–17) have an unnamed head on the obverse, which Gallaeus or Ursinus has assumed to be the hero of the barrel story. But on others what seems to be the same head is labelled L. Regulus Pr.'

#### 117

Pl. 6. Bought in England between 1914 and 1917. Sard.

A portrait head of Julius Caesar wearing a laurel wreath tied with a fillet.

Comparable with certain coins figured by Bernoulli (Römische Ikonographie, i, Coin plate 3, 57, and 62). The portrait may be posthumous, but seems to be ancient.

#### 118

G. P. 363, 1. Pl. 6. Bought in London, 1916.

Slightly convex. Translucent sard. The eye chipped and the top of the head missing.

A portrait head of a middle-aged Roman, with the clothing indicated. Inscription, perhaps ancient, GNTS.

# 119

G. P. 347, 4. Pl. 6. Said to have been found in or near Rome. Bought in Rome about 1912.

Sard, set in a massive gold ring. The hoop circular. The type of ring is early imperial (Marshall, B. M. Finger Rings,

p. xlvi, E xvi). It is not quite certain that the stone belongs to the ring.

A portrait head of an elderly Roman. Close-cropped hair rendered by short strokes.

#### 120

G. P. 359, 7. Pl. 6. Said to have belonged to a Bishop of Winchester. Bought in Edinburgh, 1915.

Brown chalcedony. Mounted in an eighteenth-century gold

ring.

Portrait of an aged Roman.

#### 121

B. B. 125, 2. R. 1053. Bu. O 10. Pl. 6. From the Morrison collection: formerly in the possession of Saulini at Rome. *Morrison Sale Catalogue*, pl. 2, number 201; F., pl. 49, 24.

Black jasper.

Portrait of a young man: head, shoulders, and part of the chest, with the clothing indicated. His hair is combed down over his forehead, and he is allowing his beard to grow. Inscription,  $\pi \cdot \pi \lambda i \tau i n$ , and below it septime. The letters end-dotted. The last letter is doubtful owing to the break in the stone. The vertical stroke is certain, but there seems to be a diagonal stroke starting from the upper dot, as if the letter were mu or nu. The third letter of the first line looks more like a lambda than an alpha, but it must be either a form or a miswriting of alpha. The upper and lower strokes of the sigma are parallel and the alphas seem to lack the cross-bar.

The second line presents difficulty. Furtwängler says that the lettering of the whole inscription, and the arrangement of it in two straight lines, connect it with the signatures of artists, and he supposes that our inscription, in which he read Septikiai, gives the name of the artist and not that of the owner. But there seems to be no instance of an artist signing with two names, and there is no reason why the owner's name should not sometimes have been written in the lettering here used: indeed, Furtwängler assumes this in the case of number 105 in the present collection: and on the stone in the Evans collection signed by Felix, the

name of the owner, Calpurnius Severus, is written in the same fashion as on our stone. Finally it may be asked what Furtwängler conceived the artist's name to be: speaking precisely, what nominative he formed from Septikiai.

#### 122

Pl. 6. Bought in England, 1917.

Amethyst. Slightly convex. Convex behind.

Portrait of Lucius Verus: head, shoulder, and part of chest.

# 123

B. B. 49. R. 1264. Pl. 7. Bought in Naples, 1898. Nicolo. Bevelled edge.

Short ground line. Theseus examining his sword. A coarse late version of the type number 107.

# 124

Pl. 7. Formerly in the possession of Charles Dawson at Lewes.

Plasma, strongly convex, in a gold ring. An open space in the bezel below the stone. The hoop rounded outside, flattened inside, and thickened and thrice compressed on either side of the bezel. Rings of this shape, in metal, jet, or glass, are datable to the third and fourth centuries A.D.: examples are figured by Henkel (Römische Fingerringe, pl. 49, numbers 1287-9; pl. 11, numbers 218 ff.; pl. 22, numbers 432 ff.; pll. 60-1 (jet), and pl. 64, number 1736 (black glass imitating jet). There is a glass specimen in the British Museum (Marshall, B. M. Finger Rings, p. 233, fig. 159, and pl. 34, number 5914); bronze specimens in this collection (number 125), and, with engraved bezel, in Carlsruhe (Schumacher, Beschreibung de antiken Bronzen, p. 22, number 17).

Ground line. A woman dancing and playing the flutes:

round her shoulders, a swirling wrap: back view, the head turned to the left.

The same design on two sards in the British Museum, one slightly, the other strongly convex (numbers 1073 and 1074), on a convex plasma in Berlin (Furtwängler, Beschreibung, pl. 22, 2424), on a sardonyx in the same collection (ibid., pl. 49, 6829), and on two other stones (King, Antique Gems and Rings, ii, pl. 17, 16; Gravelle, Recueil de pierres gravées antiques, ii, pl. 98 = Reinach, Pierres gravées, pl. 81). In the second and in the last the head is turned to the left, in the others to the right.

A kindred figure in the wall paintings of the Villa Item at Pompeii (Journal of Roman Studies, iii, pl. 13; Pottier, Revue Archéologique, 1915, ii, p. 19) and on the Berlin relief with which Miss Mudie Cooke compares the painting (J. R. S. iii, pl. 14, p. 166). Comparable also, figures on a sarcophagus in Rome (Reinach, Répertoire des reliefs, iii, p. 326, 5), and in another Pompeian painting (Zeitschrift für Bildende Kunst, 1901, p. 289).

The ring no doubt belongs to the third century A.D., and that the stone is of the same period may be inferred from the analogous workmanship of the stones in the other rings of the same type, and perhaps from the excellent harmony of stone and setting.

# 125

Pl. 7. Formerly in the possession of Charles Dawson at Lewes.

Plasma, slightly convex, in a bronze ring of the same type as number 124.

Ground line. Diomede with the Palladion. Diomede, naked, holding the image in his left and his sword in his right, steps over an altar, the side of which is rounded: in front of him,

a pillar with a statue on it.

A small, rough, late version of a design which was extremely popular with gem-engravers in the Greco-Roman period (see Furtwängler, Jahrbuch, iii, pp. 213–14; F. ii, pp. 205 and 233), and which also occurs on a sarcophagus and in a painting (see Robert, Die antiken Sarkophagenreliefs, ii, pp. 150–1). A fragmentary stone, with a Diomede of the usual type, has recently been acquired for the Munich collection (Münchener Jahrbuch, v, pl. B, 9).

Third century A.D.

# RENAISSANCE

#### 126

G. P. 341, 6. Bu. L 120. Pl. B, 14. Formerly in the Arundel, Marlborough (Story-Maskelyne, *The Marlborough Gems*, p. 6, number 32), and Evans collections; F., pl. 66, 12.

Chalcedony, almost colourless.

Triton and Nereid. The Triton, who wears, on his head and back, the skin of an animal, perhaps an antelope, with long horns and big ears, clasps the waist of the Nereid, who holds a ship's standard  $(\sigma\tau\nu\lambda is)$  in her left hand and grasps the Triton's throat with her right: his tail is wound round her legs: one of her feet shows the sole. A little naked boy, with wind-blown hair, sits on the Triton's tail and holds it with both arms.

The type seems to be an antique one: it occurs, reversed, on a sard, formerly in the collection of Lorenzo de' Medici, which is published by Imhoof-Blumer and Keller (*Tier- und Pflanzen-bilder*, pl. 26, 50; also Raspe, pl. 31, number 2633), and which seems to be ancient, although the authors express a doubt; on a gem of which there is an imprint in the Impronte dell' Instituto: further, on a fragmentary cameo in Berlin, which Furtwängler counts antique (*Beschreibung*, pl. 66, number 11082), and on an intaglio figured in the *Dactyliotheca* of Gorlaeus (ii, 488).

Furtwängler accepts our stone as antique: against its antiquity, the obscurity of the Triton's torso, his curious costume, the treatment of the water, the athletic form of the Nereid, and

the Raphaelesque putto.

Arundel died in 1646. The stone is probably sixteenth-

century work.

Story-Maskelyne says (loc. cit.) that 'the somewhat floriated

tail, as well as the material, betrays a Renaissance hand'.

A paste after this stone in the Stosch collection (second class, number 461).

# CAMEOS

# 127

R. 813. Bu. O 21. Pl. 8. From the Tyszkiewicz collection. Tyszkiewicz said that an Oriental brought it to Sambon of Naples. Collection Tyszkiewicz, pl. 33, 5; F., pl. 61, 47.

Fragment of a sardonyx cameo: the background is lost: the

upper layer is watered grey.

Head of a Ptolemaic queen, wearing the cap of vulture's feathers and the diadem: formal curls, of corkscrew type, on the brow. The pupil and the outer line of the iris incised. The

nose somewhat irregular. Egyptianizing style.

A cameo with the portrait of an Egyptian queen, wearing feather cap and horned disk, was formerly in the Marlborough collection (Gemmarum Delectus Ducis Marlburiensis, ii, pl. 17=Reinach, Pierres gravées, pl. 114) and was assigned by Story-Maskelyne (Marlborough Gems, number 366) to the Hellenistic period.

Hellenistic.

#### 128

B. B. 150, 4. R. 1663. Bu. M 6. Pl. 8. Bought in 1899 from Dr. W. Hayes Ward of New York, who acquired it in or near Bagdad while a missionary in those parts. Mentioned by A. S. Murray, *Handbook of Greek Archaeology*, p. 172, and by Babelon, *Catalogue des camées antiques*, p. xl. F., iii, p. 447, fig. 230, enlarged.

Sardonyx cameo, white on brown, mounted in a Turkish gold

ring.

Ground line. Aphrodite and Eros. The goddess stands with left knee bent and left foot nearly frontal, the head inclined towards her left shoulder, the right arm falling along her side, the left bent up from the elbow. She wears a transparent chiton which has slipped down so as to bare her right shoulder and breast, and a himation the upper line of which repeats the upper line of the chiton. The back of the head is veiled. Eros, a little child, flutters at her left shoulder. Below, the stump of a tree. The artist's signature, in two straight lines, engraved downwards,

The letters, which have no end-dots, are ΠΡΩΤΑΡΧΟΣ ΕΠΟΙΕΙ. not remarkably neat. The iotas are large, the omega and the omicron small: the horizontal strokes of the om ga are rather long. In the first pi, the cross-bar overlaps on both sides; in the second, only on the right, while the first vertical stroke projects beyond the cross-bar. The alpha has a V-shaped cross-

bar, in which the left-hand stroke is the stronger.

The drapery of our goddess, the thin chiton leaving breast and shoulder bare, and the himation starting below the hip on the stiff leg and curving up towards the shoulder with a line which repeats the upper line of the chiton, may be compared with that of the Epidaurian Aphrodite (Brunn-Bruckmann, number 14), the original of which has been dated about 400. Here the position of the legs is much the same as on the stone, but the head is turned in the other direction and the body is supported by the sceptre which was held in the left hand, whereas our goddess seems to lack support on her right side, as if her elbow had been resting on a tree of which only the stump is represented.

Figures which offer a general resemblance to ours are not uncommon on fourth-century vases. A lady on a lekanis in Petrograd (Compte rendu, 1860, pl. 1; F. R., pl. 68) stands in the same way and has her clothing similarly disposed: her left elbow rests on a slender sapling. A woman on an Italian vase (Millin, Peintures de vases grecs, ii, pl. 52; Elite des monuments céramographiques, iv, pl. 23) also rests her elbow on a sapling, and her legs are in the same position. Another lady in the same attitude is to be seen on an Attic vase belonging to the middle of the fourth century, the bell-krater F 68 in the British Museum (Panofka, Cabinet Pourtalès, pl. 16; phot. Mansell, 3280): the upper part of her chiton is differently rendered, but her left elbow, like that of our Aphrodite, seems to rest on space.

Figures which show more or less kinship with ours are found on statues and reliefs belonging to the end of the fifth and the fourth century (Brunn-Bruckmann, pl. 673, pl. 338; Conze, Attische Grabreliefs, pll. 150, 186, 187, and 418; Bulletin de correspondance hellénique, 1901, p. 263), and in later works derived from older models, such as a Roman clay relief (von Rohden and Winnefeld, Architektonische Reliefs der Kaiserzeit, pl. 17) and even a Byzantine ivory diptych (Reinach, Répertoire de reliefs,

ii, p. 455, 4).

The type used by Protarchos seems to have been developed in the course of the fourth century: one of the fourth-century versions may conceivably have been a painting of Aphrodite resting her elbow on a tree. Protarchos himself lived later: the lettering of his signature points, as Furtwängler notices, to the

second century B.C.

Another gem with the signature Protarchos is preserved in Florence, a cameo with Eros, mounted on a lion, playing the lyre (Jahrbuch, iii, pl. 26, 20; F., pl. 57, 1). The signature on the Florentine Protarchos is in relief, not engraved as in ours, and the spelling is  $\epsilon \pi o \epsilon \iota$ : yet the two signatures seem to be by one hand, for the lettering is similar in both; in particular, the first diagonal of the chi is the dominant one in the Florentine cameo as in ours, and the horizontal bar of the tau is no less vigorous.

# 129

R. 514. Bu. O 19. Pl. 8. Bought from W. T. Ready in 1897. Formerly in the Montigny collection. This is probably the gem figured by Raspe (Descriptive Catalogue of a general Collection of Gems cast by James Tassie, Modeller (1791), pl. 21, number 1199). Collection de M. de Montigny, vente à l'hôtel Drouot 23-25 mai 1887, pl. 5, number 650.

Cameo in three layers, the upper transparent, the middle one milky white and in part discoloured, the ground translucent with

a milky patch at the bottom of the stone.

Ground line. Leda, her left leg bare, her right knee resting on an altar, submits herself to the embraces of the swan, whose neck encircles hers.

The stone was condemned by A. S. Murray, and considered genuine by Tyszkiewicz and Furtwängler.

# 130

G. P. 317, 7. Pl. 8. From the Saulini collection (Catalogue des objets antiques recueillis par M. le Chev. Louis Saulini, Rome, 24-26 avril 1899, number 97).

Fragment of a sardonyx cameo, white on pale brown.

Ground line. A young satyr, seated on a rock, which is covered with a lionskin, draws a boy towards him. The satyr

has a skin over his loins. The decenza did not deter Hauser

from regarding the stone as antique.

A similar scene on a fragmentary cameo with the signature of Dioskourides (F., pl. 57, 8). Dioskourides' cameo probably represents a hermaphrodite tempting a young satyr: for the design, as far as it is preserved, is the same as that of a Calene clay relief, a paste cameo in Brunswick, and several marble statues (Paul Herrmann in Roscher's *Lexikon*, s.v. Hermaphroditus, pp. 2339-40): the original group probably formed a kind of pendant to the group of a bearded satyr tempting a hermaphrodite which is described by Arndt in *La Glyptothèque Ny-Carlsberg*, text to pl. 139.

In our stone, the seated figure is certainly a satyr, though described as a 'fauness' in the Saulini catalogue: the other is

probably a young boy, though the breast is a trifle full.

For the action, slab 520 of the Phigaleian frieze may also be compared.

Early imperial.

# 131

G. P. 327, 1. Pl. 8. Formerly in the Arundel, Marlborough, and Schröder collections (Story-Maskelyne, *The Marlborough Gems*, p. 35, number 206; *Schröder Sale Catalogue*, 1910, number 63).

Fragment of a sardonyx cameo, white on brown.

The subject obscure: a young satyr pushes or supports the shoulder of a bearded Silenus who wears a short garment about his loins. This Silenus seems to be pulling something or somebody: another figure is needed to explain the thyrsus which passes behind both figures.

Early imperial.

# 132

G. P. 320, 1. Pl. 8. Bought from Rollin and Feuardent in 1907. The previous history is given by Babelon (*Histoire de la gravure sur gemmes en France*, pp. 156–7). According to a tradition which Babelon calls apocryphal, it was found by a peasant from the Roman Campagna, and purchased for a small sum by Cardinal Albani. The Cardinal presented it to Countess Cherof-

fini, in whose possession it was when Winckelmann published it. The stone soon became famous under the title of 'the Tears of Achilles'. The family of the countess sold it to Monsignor Ferretti, and the King of Naples, Joachim Murat, made unsuccessful attempts to acquire it. About 1820 it was in the possession of a collector named Vincenzo Natti, who sold it to a Frenchman, M. de S., in whose family it remained till lately.

There is a cast in the Impronte dell' Instituto.

Fragmentary sardonyx cameo in two layers, the upper milky white, the lower dark brown and almost opaque.

Uneven exergual space representing the ground. Orestes and Pylades in Tauri. Orestes seated, resting his bowed head on his right hand, his left arm dropped on his left thigh with the halfclosed hand hanging listlessly by his knee. To the left of his legs, part of a stone structure in courses, with faint horizontal striations: possibly an altar. Orestes seems not to be sitting on this, but on something else, perhaps a stone, only a small part of which is visible: between this seat and his thigh, a piece of drapery can be made out. In front of Orestes, Pylades looking down at him, his right hand resting on a high pillar, his head on the hand, his left arm lowered with the hand open. A garment falls in front of his right leg and is held between ham and knee: higher, it is seen in front of his chest and under his armpit. Behind, part of a doorway, with a fillet hanging from the lintel: the architectural fragments above the lintel are hard to interpret. Behind Orestes, and in front of the doorway, a guard, cleanshaven, with Roman helmet and shield; also the hand and bent sleeved arm of a fourth figure, the elbow as if resting on a ledge concealed by the head of Orestes.

The cameo has often been copied. An imprint in the Stosch collection is thus described by Winckelmann (Description despierres gravées, pl. 373-4): 'sard engraved by le Sieur Barnabé Florentin [Felice Bernabè]. Antilochus, son of Nestor, announcing the death of Patroclus to Achilles. This engraving is made after a fragment of a cameo belonging to the Countess Cheroffini in Rome: the missing part of the cameo has been supplied on our stone, including the two maidens, Achilles' companions, who, according to Homer's account, mourned the death of Patroclus.'

A sard intaglio in Berlin, of the same type, is attributed by

Furtwängler to the Renaissance (Beschreibung, pl. 63, number

8859).

Ín Winckelmann's Monumenti antichi inediti (1767), fig. 129, the missing part of our cameo is supplied, in summary fashion, by completing the figure of Orestes. In most modern versions a fourth figure is added, the owner of the sleeved arm on the left of the fragment: so in the sard intaglio, signed by Marchant, in the British Museum (Dalton, Catalogue of the Engraved Gems in the British Museum: Post-Classical Period, pl. 31, 817); on the intaglio of red jasper, signed by Louis Siriès, in the Cabinet des Médailles (Babelon, Histoire de la gravure sur gemmes en France, pl. 12, fig. 8); on the stone attributed to one of the Pichlers (Inghirami, Galleria omerica, i, pl. 31; Overbeck, Gallerie heroischer Bildwerke, pl. 30, 5), which is said to have been in the Blacas collection, but which does not appear in the manuscript catalogue of the Blacas gems which is preserved in the British Museum; and on a cameo belonging to Mr. Warren. A second cameo, also in this collection, adds the fourth figure, but does not complete the Orestes. The paste in Munich published by Furtwängler (F., pl. 67, 24) is a copy, by Tassie according to Dalton, of Marchant's stone in London. Dalton mentions, without particulars, two modern stones in Petrograd: there are many others.

A variant of the design, with the same Orestes and Pylades, but different watchman and background, on a sard, from the Pulsky collection, in the British Museum (number 1476): the stone is counted ancient in the British Museum catalogue, but seems to be poor modern work. There is a figure somewhat resembling our Pylades in the 'Sacrifice to Diana' on a small Italian plaquette, of the sixteenth century, in the British Museum.

A similar composition forms part of the Oresteia on three sarcophagus reliefs (Robert, Die antiken Sarkophagenreliefs, ii, pl. 59). On the Berlin sarcophagus, Orestes is seated, head muffled, on a rock: in front of him, Pylades, leaning on a pillar, with his stick in his hand: behind Orestes, a bearded guard, in Roman armour, with spear and sword; in the background, a bearded man wearing chlamys and Phrygian cap and holding a spear. The Weimar sarcophagus presents certain variations: the legs of the friends are differently posed, the person with the cap is youthful, and the fourth figure is characterized as a Scythian by his untrimmed beard and hair, by his shoes, and by the sleeved

and trousered garment which he wears with his Roman corslet. The third example is the fragment, described and figured by Winckelmann (Monumenti antichi inediti, fig. 130), which is embedded in the wall of the Palazzo Mattei at Rome. In general it resembles the Berlin version, but it shares with the Weimar sarcophagus the Scythian costume of the soldier and the youthfulness of the figure in the background: to the right is part of an additional figure, another youth wearing a Phrygian cap. The Berlin sarcophagus was discovered in 1828: the Weimar came from the Palazzo Grimani at Venice and is first mentioned in 1789. The Mattei relief is conjectured to have been attached to the Palazzo Mattei when it was built in 1616.

Robert supposes that the subject of these reliefs is taken from lines 657-724 of Euripides' *Iphigeneia in Tauris*: Pylades has consented to take home the letter from Iphigeneia, while Orestes is to remain and be sacrificed. Other less satisfactory interpretations are mentioned by Höfer in Roscher's *Lexikon*, s.v. *Orestes*.

The original reproduced by the reliefs is naturally much older than they. The figure of Orestes occurs in reliefs on Etruscan cinerary urns of the third or second century B.C. (Brunn, I rilievi delle urne etrusche, pl. 84 and pl. 85, 3, and pp. 106–12). The urns represent a different moment in the story, and the place of Pylades is taken by Iphigeneia, resting her head and hands on a pillar. The scene may be a modification of the original from which the Roman reliefs are derived. The motive of the drapery caught between the knees, as in Pylades, does not occur before the very end of the fifth century, but is frequent in the fourth; for the two figures of Pylades and Orestes, compare the first and fourth figures on an Attic bell-krater in Vienna (Laborde, Vases de Lamberg, i, pl. 16), which belongs to the early fourth century.

Babelon (op. cit., p. 157) considers our cameo to be a renaissance copy of the Mattei relief. The cameo differs from the relief in many points, the head of Orestes unveiled, the left hand of Pylades empty, his right hand placed differently on a higher pillar, the supernumeraries changed. These variations cannot be used as an argument either for or against a modern origin: but at least one detail suggests that the cameo is not an imitation of the Mattei relief. The hand of Orestes lies half open beside his knee: on the relief, it is wrapped in his drapery: but on the Weimar sarcophagus it is placed as on the cameo. The cameo is copied, it may be urged, from the Weimar and not from the

Mattei version: that is impossible, for the Weimar Pylades differs from both the Mattei and the cameo. The Berlin sarcophagus is out of the question, as it was not discovered till the nineteenth century. It is unlikely that a modern artist would have contaminated the Mattei and the Weimar versions. Either the cameo is ancient or it is copied from a fourth sarcophagus which has disappeared.

There is nothing, however, in the style of the cameo which would prevent it from being antique: and it is well known that the engravers of gems and the sculptors of sarcophagi often drew

their compositions from the same source.

It may be added that Furtwängler saw the cameo and thought it antique.

# 133

G. P. 344, 11. Pl. 8. From the Boulton collection (sale catalogue, number 92).

Fragmentary sardonyx cameo, white on brown.

A concert in the open air. A faun, wreathed with ivy, seated on a lionskin under a tree with a nymph on his lap, and smiling at a bearded satyr of rough appearance who is dancing

the oklasma. Herbage: rocky ground to the left.

The scene may be completed with the help of a cameo in the Beverley collection (F., pl. 57, 18), where the nymph is perhaps clapping her hands to accompany the dancer, who is, however, omitted and replaced by an urn, while an aegipan holds his syrinx ready, and the faun conducts. A fragment of another cameo in the same collection, of which there is a cast in the Impronte dell' Instituto, contains the dancer and the head of the faun, and part of the tree with an oscillum dangling from it. A fourth cameo of the same type belonged to the Mantua and Worsley collections (Museum Worsleianum, ii, p. 37; Visconti, Museo Worslejano, pl. 30, 16): here the aegipan is replaced by a little boy, who plays the flutes, and the nymph appears to be holding a bowl.

The cut published by Aeneas Vicus (Ex gemmis et cameis antiquorum aliquot monumenta, pl. 8) represents a cameo of this type; possibly the former of the Beverley stones, with the urn transformed into an aegipan standing on a rock in the distance and playing the double flute. Vicus has added the motto suggested by the cup in the nymph's hand: 'Libidinis fomes. | Si

vina tollas et Venus statim perit | nec dulce quidquam restat hinc mortalibus.'

The figure of the nymph occurs in other compositions: so

on another cameo in the Beverley collection (F., pl. 57, 20).

For the gesture of the faun, a fragmentary cameo in the British Museum (number 993) may be compared: an old Silenus seated playing the lyre, and a hand with the index and middle fingers extended, the first vertically and the second diagonally, and the rest closed.

# SUPPLEMENT

# **INTAGLIOS**

134

G. P. 341, 3. Fig. 5 at p. 85, magnified 1½ diameters. Formerly in the Evans collection. Published in a Paris sale catalogue.

Chalcedony, slightly convex. The lower left-hand part lost. Ground line, swelling towards the middle. A woman with a vessel at a fountain. Thin chiton, undergirt; the mantle has slipped

back from the shoulders. Coiled hair.

The same design on several Greco-Roman gems (B. M. Catalogue, pl. F, 562; F., pl. 39, 26-7; F., Beschreibung, pl. 7, no. 345) and on a convex sard in New York which is probably Hellenistic like ours. The vessel has been called a hydria, but as no side-handles are indicated in any of the versions it is probably an oinochoe.

The upper part of the chiton is treated in the moist 'Ionian' manner; similarly on the stone F., pl. 39, 6; in the other versions

the treatment is more severe.

The original may have been a picture, or a marble relief, of the fifth century. The severer versions recall the Persephone on the Triptolemos relief from Eleusis.

Hellenistic.

135

Fig. 6 at p. 85, magnified 2 diameters. Acquired in Rome, 1919. The stone was found in 1918 by a man working in a vigna at Rome. He sold it to an old Roman dealer, who sold it to another dealer for a trifle ('una sciocchezza'). The inscription was read by a third dealer, a Greek, who seems to have urged the second dealer to buy it.

Sard, fragmentary: the upper half missing, and the lower right-hand portion fractured.

Thick, irregular ground line. Bellerophon mastering Pegasos. The hero is naked save for a chlamys: his right foot frontal and his right leg bent at the knee; the outer part of the right foot broken away. The horse's body foreshortened. Inscription, in the exergue, ... ΥΡΙΔΟΥ, [Διοσκο]υριδου, the signature of the artist Dioskourides. The letters are end-dotted: the lines of the delta concave inwards. Six letters remain: the dealer who sold the stone to its present owner stated that a seventh, presumably the second omikron of the name, was broken away in mounting the stone. Mr. A. P. Ready observes that the end-dots of the letters are not bored perpendicularly, but slightly undercut, so that the stone is liable to fracture in sealing. The imprint is misleading in one point: by smoothing away the traces of the break the maker of the imprint has produced the semblance of a seventh letter before the first upsilon: there is no such letter in the original.

Mr. John Marshall points out that the sard is of the same colour, kind, and excellence as that used by Dioskourides for his Achilles in Naples (F., iii, p. 356); the quality of the fracturing

is the same in both.

The missing part of the design can be restored by comparison with the Bellerophon gem published by Beger in his Spicilegium Antiquitatis (1692), p. 68. The hero's head is turned away from the horse, and appears in three-quarter profile; his right arm is not visible; his left is extended beyond the animal's forehead as if he were grasping its forelock. The position of Pegasus is not quite the same in Beger's gem: the right wing is lower, both forelegs are raised, and the hind quarters seem to be on the

ground. Beger notices that the engraver differs from Pausanias, but agrees with Strabo, p. 379, who says of Pirene, ἐνταῦθά φασι πίνοντα τὸν Πήγασον ἀλῶναι ὑπὸ Βελλεροφόντου.

In Annali, 1874, p. 9, Engelmann mentions a fragment of a relief in the Villa Carpegna which has the same design as

Beger's gem.

A variant on an ancient paste cameo in Berlin (F., Beschreibung, p. 351, number 11272): here Bellerophon faces to the right and his right arm is bent at the elbow; and Pegasos is almost in profile. Compare also Herakles and the Bull on a sard in the British Museum (F., pl. 35, 29).

On Dioskourides, Augustus' favourite engraver, see F. iii, pp. 355-7, and Furtwängler's earlier essay in *Jahrbuch*, iii, pp. 211-25. The portrait of Demosthenes in amethyst (F., pl. 49,

7) is now in the collection of Sir Arthur Evans.

# ADDENDA

- P. 7, number 11, at the end. Mr. A. S. F. Gow points out that the monster need not be a deity but may be in the nature of a cherub or the like.
- P. 13, number 18. A naked youth running with cock and lyre is the subject of a green jasper scarab, more archaic in style than numbers 11–13 bis, which is at present in the market.
- P. 23. Studded headpiece: also in an architectural clay group in the Villa Giulia, from an archaic temple at Falerii.
- P. 23. The nearest Attic peytrel: Attic calyx-krater of free style in Corneto (phot. Alinari 26041, 1).
- P. 33, number 35 ter. For the style, compare the sard scarab number 15260 in the Museo Archeologico at Florence (young warrior holding helmet).
- P. 39, number 42. There are two sard scarabs with Herakles on the raft in the Castellani collection at Rome.
- P. 55, number 61. Mr. Gow objects that Theseus would be cut in two if the rope were as described.

For the motive, he compares Pisanello's Venator Intrepidus.

- P. 58. Another lion with bristly back on a chalcedony scaraboid from Larnaca in the British Museum.
- P. 58. Maned lionesses. Mr. A. S. F. Gow writes: 'The artist of the button [our number 3] knows more about lionesses than the artist of the sliced barrel [our number 65], for he provides them with abdominal and not inguinal mammae, yet his lioness too is maned. I inquire therefore whether the mane may not have been regarded as common to the sexes. For instance Aristotle, H. A. ii. I (498, b. 27), seems to class the lion as a maned animal without reference to sex. I add also that it is conceivable that lionesses were maned in Greece. Lions tend to lose their manes in exceptionally hot districts, and Selous believes them to have

been a northern animal which moved southward; so that when they extended farther north they were certainly hairier (as at the Zoological Gardens in London) and may all have had manes.

See F. C. Selous, African Nature Notes, pp. 80 ff.

'The upshot is, it seems, that if there are unmaned lionesses in Greek art all this is perhaps of no importance. If there are not, a suspension of judgment would perhaps be wiser. In any case the barrel artist ought not to be rated too much, for apparently Aristotle makes worse mistakes (for instance, gives them two mammae), and seems never to have seen one (De partibus animalium, tr. Ogle, p. 236), though they existed in Thrace in the fourth century at least. A different line of argument in a letter herewith from a zoologist.'

The zoologist (Mr. M. D. Hill) writes: 'I can find no allusion to maned lionesses in any of the books I have looked at. The only suggestion I can make is that in the hotter parts of Africa lions often develop only the scrubbiest of manes, and thus the idea may have arisen that they were really lionesses and not lions at all. The confusion is not at all impossible as the genitalia are

inconspicuous in both sexes as often as not.'

P. 67, number 80. Mr. Gow considers the hind quarters wrong for a spring and supposes the animal to be stretching itself.

If the animal were canine we might compare the dog 'in a humble and affectionate frame of mind' shown in fig. 6 of Darwin's Expression of the Emotions.

- P. 70, bottom. 'It is conceivable . . .' Mr. Gow writes: 'The material helps, I think. A magistrate wanting a seal which he could only use during his term of office might well have it of bronze and not of more costly and durable material.'
- P. 87. The stone published by Vivenzio is also figured by Gargiulo in his Recueil des monuments du Musée National et de plusieurs autres collections particulières, Naples, 1861, iii, pl. 7, 1.
- P. 95. The Chesterfield collection. Lord Chesterfield delivered the following admonition to his son in Rome (Letter cx): 'No piping nor fiddling, I beseech you; no days lost in poring upon almost imperceptible *Intaglios* and *Cameos*; and do not become a Virtuoso of small wares. Form a taste of painting, sculpture, and architecture, if you please, by a careful examination of the works of the best ancient and modern artists; those are

liberal arts, and a real taste and knowledge of them becomes a man of fashion very well. But beyond certain bounds, the man of taste ends, and the frivolous Virtuoso begins.'

- P. 98. Other versions of the man with the nail: Naples 25182, sard; Uffizi 3556, circular sard of Renaissance work.
- P. 99, number 119. Naples 25224, a sard set in a gold ring, seemed to be a replica.
  - P. 103. The Medici stone is now in Naples, number 225.



# INDEX

The reference is to the page.

Abdera, coins of, 69-71. Achilles, 25, 36; 'Tears of Achilles,' 108. Actor, 91. Aegina, gem from, 20; pedimental figure, Africa, gem from Hadrumetum in, 88. Ainos, coins of, 64. Ajax, dead, 34; death of, 37–8. Akanthos, coins of, 58. Amathus, coins of, 29, 58. Amazons, 45, 51. Aphrodite, 85, 104. Apollo, 10, 41, 44, 91. Archer, 20. Argos, coins of, 53. Aristotle, 115, 116. Arndt collection, gems in the, 2, 65. Arsinoe Philadelphos, 80, 81. Artemis, 51. Ashur, 4. Asia, gems from, 28 (Caria), 52 and 89 (Asia Minor), 80 (Adana), 81 (Suleimanieh), 82 (Euphrates), 94 (Chalcedon), 104 (Bagdad). Athena, 19, 32; image of, see Palladion. Athens, gems in, 2. Attica, gems from, 45, 69, 86, 98. Augustus, 88–9. Bellerophon, 113. Benedetti, Comm., gem in the possession of, 59. Berenike I, 80. Berlin, gems in, 2, 11, 12, 16, 19, 25, 30, 43, 57, 59, 65, 66, 67, 68, 71, 88, 89, 90, 93, 94, 95, 96, 97, 103, 108, 114. Beverley collection, gems in the, 111. Birds, 6, 42, 51; see dove, eagle, goose, hawk, heron. Boar, 64. Greek Border of diagonal strokes, scarabs with vertical, 10.

Boston, gems in, 2, 17, 30, 57, 59, 60, 65, 68, 73, 93. Boulton collection, gems formerly in the, 58, 74. Bowdoin College, Brunswick, Maine, gems in, 49, 59, 66. British Museum, see London. Bronze head, 89; reliefs, 24, 52, 72, 90; scaraboids, 71; statuettes, 38, 96; see cistae, mirrors, rings. Brunswick, gem in, 107. Bucranium, 53. Bull, 1, 4, 30, 67; see calf, cow, zebu. Cagliari, gems in, 9, 71. Calanice, 74. Calf, 2, 65-6. Cambridge, gems in, 46, 48. Carlsruhe, ring in, 108. Cartouche, 6. Cassandra, 55, 77, 79. Castellani collection, gems in the, 115. Centaur, 75, 93. Cerberus, 96. Chariot, 5, 16, 51, 88. Chesterfield, Lord, advice about gems, 116. Cistae, bronze, 8, 35, 36. Clay reliefs, 22 (Melian), 23 (Locrian), 55 (Hellenistic), 78 and 105 (Greco-Roman): statuette, 85; temple decoration, 115. Cock, 9, 13. Cockerell collection, gem in the, 49. Coins, see under the several states. Coitus, 54, 56. Commagene, coins of, 83. Conjoined in a single head, two bodies, 1. Copenhagen, gems in, 38, 39. Corfu, gem from, 33. Corneto, gems in, 11, 14, 40. Cos, coins of, 22. Cow, 2. Crete, gem from, 2.

Gorgon, 13.

Gorgoneion, 19-20.

Greco-Persian, 56.

particular localities.

Cyprus, gems from, 15, 25, 27, 29. Cythera, gem from, 53. Cyzicus, coins of, 30, 58.

Death-demons, 33, 34, 35. De Clercq collection, gems in the, 25, 30, 86. Deer, 1, 51, 65. Delphi, frieze of treasury at, 24; gem from, 44. Dexamenos, gem-engraver, 46-9, 62. Diomed, 53, 92, 102. Dionysos in relief on pseudo-scarab, 31. Dioskourides, gem-engraver, 94, 107, 113. Dog, 51, 54, 95-6. Dolon, 92-3. Donkey, 69. Doris gem from, 55. Dorpat, gem in, 28. Dove, 68.1 Dragon, 41.

Eagle, 29, 56. Egypt, gems from, 20, 54, 68. Elis, coin of, 47. Epimenes, gem-engraver, 20-4. Erinys, 13. Eros, 14, 27, 28, 40, 50, 52, 104; dogbodied, 54. Erotostasia, 50. Erythrai, coins of, 14, 24. Etruria, gems from: Arezzo, 40; Chiusi, 39; Corneto, 6, 10, 14, 16, 41, 72; Vulci, 37. Euboea, gems from 77 (Chalcis), 85 (Eretria). Euripides, 110. Evans collection, gems in the: 1, 30, 38, 58, 100, 114; once in the, 42, 54. Eyelashes, 46–8.

Florence, gems in: Museo Archeologico, 76, 106, 115; Uffizi, 117.
Flutes, 87, 102.
Foreshortening, archaic, 21-2, 36, 37, 39; of bull's head, 67; of horse's head, 51.

Gelon, gem-engraver, 86. Goat, 64, 67, 76; wild, 7. Golgoi, coins of, 29. Goose, 52.

Fountain, woman at, 112.

Griffin, 24, 69-71; leonine, 5. Ground line: hatched, 62; pelleted, 25, 27; two ground lines, 45. Hawk, 41. Head, oracular, 73; youthful, 8; see portrait. Head-dress and head-gear, 44, 49, 56, 80, 81, 82, 83, 84. Headpiece of bridle, dotted, 14, 23, 115. Helmet, fantastic, 8; youth picking up, 25. Herakleia, coins of, 74. Herakles, 9, 10, 14, 15, 32, 38, 39, 70, 71, 73, 74: Hermaphrodite, 107. Hermes, 14, 43. Hermotimos, owner of gem, 31. Heron, 59–61. Horses, 5, 14, 21-4, 45, 51, 62, 69, 88, 113. Horse-tamers, 15, 21-4, 113. Hyele, coins of, 29, 68. Hyperechios, gem-engraver, 97.

Greece, gem from, 57; see also under

Ichnai, coins of, 14.
Io, head of, 94.
Ionides collection, gem in the, 11.
Isis, queen as, 80.
Iviza, gems from, 7, 8, 9.
Ivory diptych, 105; plaques, 15.

Jason, 41. Julius Caesar, 99.

Kanachos, 91.
Kaulonia, coin of, 45.
Kelenderis, coins of, 22, 62.
Kition, coin of, 58.

Lamb collection, gems in the, 7.
Laos, coin of, 27.
Lecce, gems in, 43, 64, 66.
Leda, 106.
Lesbos, gem from, 87.
Lion, 1, 6, 15, 29, 54, 68, 71, 74, 97;
lioness, 1, 58; lion with bristly back, 58, 115; lion's head, 8.

Lion-griffin, 5.
Lion with human forepart, 7.
London, British Museum, gems in the, 2, 6, 7, 8, 9, 10, 11, 13, 14, 16, 17, 18, 20, 25, 30, 31, 35, 38, 49, 50, 52, 57, 58, 60, 61, 64, 67, 68, 72, 74, 75, 78, 82, 85, 86, 87, 88, 90, 92, 93, 94, 96, 98, 100, 109, 112, 114, 115.
Louvre, gems in the, see Paris.
Lucius Verus, 101.
Lugalgirra, 3.
Lykomedes, gem-engraver, 80.

Macedon, coins of, 68, 70. Macedonia, gems from, 76 (Salonica), 96. Maenads and nymphs, 10, 93, 94, 111. Mane, in lionesses, 1, 58, 115. Marbles, *see* reliefs, statues. Marlborough collection, gem once in the, 104. Marsyas and Olympos, 87. Maschalismos, 74. Mashmash, 3. Melos, gem from, 45. Memnon, body of, 35. Messana, coin of, 68. Miletus, coins of, 91-2. Mirrors, bronze, 28, 39, 47, 55, 58, 74. Montigny collection, gem once in the, 98. Morrison collection, gems once in the, 6, Mosaic, Alexander, 6, 23. Mule, 63. Munich, gems in, 2, 22, 60, 90, 91, 102.

Naples, gems in, 113, 117. Negress, head of, 49. Negro boy, 40. New York, gems in, 2, 12, 28, 30, 42, 57, 60, 112. Nike, 78. Nut, hazel, 63.

Mycenae, gems from, 1, 2.

Odysseus, 92.
Olympia, sculpture of temple at, 42, 67, 73.
Onesimos, gem-engraver, 17.
Orestes and Pylades, 108-11.
Ovid, 54.
Oxford, gems in, 48, 56, 60, 61, 64, 65.

Paetinius, 100-1. Paintings: in Etruscan tombs, 22, 24, 34; Pompeian and Herculanean, 87, 93, 102. Palladion and image of Athena, 53, 55, 77, 79, 102. Pantheress, 67. Paris, gems in : Cabinet des Médailles, 13, 17, 25, 31, 44, 48, 51, 56, 58, 60, 62, 67, 75, 79, 90, 109; Louvre, 13, 18. Pegasus, 113. Peleus, 40. Pellets terminating head at neck, 8. Peloponnese, gems from, 67 (Messenia), 1 and 2 (Mycenae), 41 (Sparta), 30 (Stimnitza), 56 (Tripolitza). Pelta, 19. Penthesilea, 25. Pergamon, coin of, 53. Persis, coins of, 83, 84. Petrograd, gems in, 48, 49, 52, 59, 61, 62, 65, 67, 86, 89, 96. Peytrel, 23, 115. Phigaleia, frieze of temple at, 78, 107. Pillar, figures leaning on, 43. Pindar, 39. Polykleitos, 90. Polypus, 86. Popilius Albanus, owner of gem, 88. Portraits, 46–8, 49, 80–5, 98–101, 104. Protarchos, gem-engraver, 104–6. Pseudo-scarabs, 16, 31, 40. Ptolemaic queen, 80, 81, 104. Pubes, female, 27.

Regulus, 98–9.
Reliefs: Assyrian, 23; Persian, 5; archaic, 15, 16, 22, 24, 44; fifth and fourth century, 51, 77, 105, 112; Etruscan tombstone, 33; Etruscan urns, 110; Greco-Roman and Roman, 79, 89, 90, 94, 102, 114. See also bronze, Delphi, Olympia, Phigaleia, sarcophagi.
Rings, ancient: engraved, 2, 15, 19, 43, 50, 51, 54, 68, 69; settings, 27, 28, 37, 85, 99, 101, 102.
Roger de Sivry collection, gem once in the, 58.
Rome, gems from, 107, 113.

Sand, athlete with, 37. Sandal, 66.

Sarcophagi, Clazomenian, 23; marble, 15, 94, 102, 109-11. Sarti collection, gem once in the, 30. Satyr, see silen. Scaraboids engraved on both sides, 56–7. Scarabs engraved on both sides, 43. Sceptre, 42. Sea-horses, 88. Sea-pantheress, 86. Septicianus, 100–1. Sheep, 31. Sicily, gem from, 67. Sicyon, coins of, 68, 78. Sieveking, Sir Edward, gem in the possession of, 91. Silen, Silenus, satyr, 8, 10, 11, 12, 17, 76, 89, 106, 107, 111; head of, 8; tailless, Silver vessels, 78. Siren, 40. Sirius, 95. Snake, 13, 29, 66. Sophocles, 34. Southesk collection, gems in the, 20, 21, 30, 40, 59, 74, 78. Sow, 55; wild, 63. Sphinx, wingless, 12. Star, 26. Statues: archaic, 42; fifth and fourthcentury types, 43, 52, 105; Hellenistic and Greco-Roman, 88, 96, 97, 107. See bronze, &c. Story Maskelyne collection, gem in the, 10. Strabo, 114.

Sybaris, coin of, 27.

Syracuse, coins of, 47, 50, 51, 52, 68; gem in, 61.
Syries, gem-engraver, 11, 18.

Tarentum, coins of, 52.
Tarsos, coin of, 70.
Teos, coins of, 58.
Terracotta, see clay.
Thebes, coin of, 44.
Theognis, 27.
Theseus, 55, 90, 101.
Torc, 82.
Tree, animals symmetrically disposed about a, 2.
Tripod, 10, 44, 69.
Triton, 88, 103.

Vases: Clazomenian, 22, 23; 'Caeretan', 22, 24; Etrusco-Ionian, 20, 22, 58; Attic, 12, 14, 16, 20, 21, 24, 26, 28, 35, 37, 39, 41, 42, 43, 45, 47, 48, 50, 51, 52, 61, 63, 73, 75, 83, 105, 115; Boeotian, 39; Italian, 12, 105; Lucanian, 45; Campanian, 47, 50, 56; Paestan, 77; Calene, 107; marble, see among reliefs.
Vienna, gem in, 89.

Wings, at ankle, 28; on head, 14; recurved, 5, 13, 27, 28; slightly recurved, 7.


Wyndham Cook collection, gems in the, 25, 30, 38, 57, 60, 64, 67, 79.

Zebu, 57.

# DESCRIPTION OF THE ILLUSTRATIVE PLATES

			A				PA	GE
1.	New York, sard							12
2.	London, agate scaraboid .			,				75
3.	New York, sard scaraboid.							28
4.	Cowper collection, sard scarab							28
5.	Louvre, steatite scarab .							18
6.	London, rock-crystal scaraboid							20
7.	De Clercq collection, sard scaral	ooid						25
8.	London, rock-crystal scaraboid				•			13
9.	London, rock-crystal scaraboid						29,	85
10.	Southesk collection, discoloured	scaral	boid				20,	21
11.	Sard scarab from Iviza .							71
12.	Green jasper scarab from Iviza							71
13	Green jasper scarab from Iviza					•		9
14.	Wyndham Cook collection, sard	scaral	0					30
15.	Boston, rock-crystal scaraboid							30
16.	Corneto, agate scarab .							40
17.	Copenhagen, sard scarab .							39
18.	London, sard scarab.							74
19.	London, sard scarab.							38
20.	Wyndham Cook collection, sard	scaral	)					38
21.	Boston, sard scarab							73
22.	Lecce, sard scarab							43
23.	Formerly in the Evans collection	, glass	s scara	aboid				42
24.	Southesk collection, sard .							74
25.	London, sard scarab.							72
26.	Wyndham Cook collection, chalc	edony	y scara	aboid				67
27.	Southesk collection, mottled jasp	er sca	araboi	d				39
28.	London, rock-crystal scaraboid							64
29.	Oxford, gold ring							48
30.	Boston, sard		,					65

		В				PAGE
ı.	Lecce, chalcedony scaraboid					64
2.	Lewes, banded agate barrel				6	0, 77
3.	Petrograd, chalcedony scaraboid					48
4.	Bowdoin, banded agate barrel				4	9, 59
5.	Bowdoin, chalcedony scaraboid					66
-	London, rock-crystal scaraboid				6.	4, 67
	De Clercq collection, convex sar					86
	Chalcedony scaraboid .					65
	London, paste					0
	London, convex chalcedony					82
	London, sard					98
	Once in the Montigny collection					98
	London, sard					98
_	Chalcedony, number 126 .					103



































































GEMS IN OTHER COLLECTIONS





GEMS IN OTHER COLLECTIONS





## Date Due

April6.	48	
DEC 2 1 19	81	
e.		
<b>AR</b> 1 9	691	
MAY 16	1881	
MAY 0	8 2002	
	- 2002	
-		

L. B CAT. NO. 1137



. qNK 5515 L5W3					
Beazle		Collect	I00493		
DATE DUE		Ancient			
/ 1	1				

qNK 5515 L5W3

